



Shelby County Government

MARK H. LUTTRELL, JR.
MAYOR

March 10, 2014

To Whom It May Concern:

RE: RFP # 14-002-46, HVAC Renovation, 1362 Mississippi Blvd.

ADDENDUM # 3

This is an addendum to RFP # 14-002-46, HVAC Renovation, 1362 Mississippi Blvd, due at 4:00 p.m., Friday, March 14, 2014.

Please the following General Note to Sheet P1:

Plumbing General Note: Remove existing abandoned VTRs at all locations indicated on the Architectural Rooftop Demolition Plan (A-1). Verify that the vent is inactive and remove entire run of inactive vent pipe. Where necessary, Contractor shall saw cut and permanently cap pipe at point where pipe begins servicing active plumbing fixtures. Existing VTR roof deck openings shall be covered with steel plates screwed to deck. Refer to Architectural for steel plate sizes and more information. See Roof plan and field verify all conditions surrounding each opening. HVAC Contractor shall maintain weather tight building envelope.

If there are any questions or concerns, please contact me at nelson.fowler@shelbycountyttn.gov or call at 901-222-2251.

Thank you,

Nelson Fowler, Manager A
Shelby County Government

Cc: Diep Tran, Support Services
Dave Canup, Canup Engineering, Inc.
RFP # 14-002-46