

**SHELBY COUNTY GOVERNMENT
CORRECTIONS RE-ENTRY PROGRAM
HVAC PACKAGE
1362 MISSISSIPPI BLVD.
MEMPHIS, TN 38106
RFP 14-002-46-A
Addendum No. 1
May 8, 2014**

1. Refer to drawing M1; HVAC Floor Plan: The existing boiler referenced to be abandoned and to have the gas line removed has been demolished by the owner. No additional work is required under this contract.

The following clarifications are offered for the contract documents:

1. Sheet M1 references connections of the duct mounted smoke detector. For this project there is no fire alarm system so the contractor shall install local alarms and reset switches grouped together for the new HVAC units. Coordinate the location of the alarms with the owner to ensure they are located in a normally attended area. The detectors shall perform the required shutdown of the respective unit.
- 2 . Architectural Clarification Notes as follows:
 - a. Remove all rooftop equipment and items and terminate or cap abandoned utility infrastructure as shown on Sheet A-1. All resulting openings in the existing roof deck shall receive a watertight roof patch installed by a roofer qualified by the roofing material manufacturer to install the product. Refer to Sheet A-1 General Roof Note "E" for acceptable roof patch material, Sheet A-2 for new roof patch locations and Sheet A-3 for associated details pertaining to roof patching.
 - b. Reference Sheet M2 for locations of new rooftop equipment and coordinate with Sheet A-2. New rooftop insulation is not in the scope of this project. The Contractor IS RESPONSIBLE for providing protection against water infiltration into the building throughout the course of the project and a watertight roof envelope upon completion of the project with a one year warranty against material and workmanship defects.

End of Addendum No. 1