

Addendum 2 - RFP 14-009-14A

12077Ad02.wpd

To: Registered plan holders via email
cc: Nelson Fowler, Diep Tran - Shelby County Government
From: Rodney Hubbard - MEDFAC Engineering LLC
Subject Shelby County Government - Boiler Modifications
Date: November 11, 2013
Re: Addendum 2 - (1 page total)

Incorporate the following items into the Project Manual and Drawings. This addendum is a binding part of the Contract Documents. Acknowledge receipt of this Addendum in bid documents.

1. The new boilers at 201 Poplar shall be shifted from the location shown east approximately 12" to 16" while maintaining all required equipment service clearances.
2. 140 Adams has primarily two way valves on the heating water coils. The modification of remaining 3 way valves to 2 way is achieved by closing the bypass valve and removing the handle as noted in the detail drawings. Field verify which locations require this modification.
3. 140 Adams - Sheet D1.2 - Remove existing steam boiler(s) and breeching only as required to allow for installation of new steam boiler B4, boiler room and boiler vent piping. Abandon breeching and steam boilers in place where possible.
4. Camus Hydrionics Ltd is an allowed alternate boiler manufacturer under specification section Fire Tube Condensing Boiler 15565 2.01 A.

END OF ADDENDUM