

ADDENDUM 1

REFERENCE PROJECT:

**DOWNTOWN DISTRICT COOLING LOOP
AND UTILITY INFRASTRUCTURE UPGRADE
Memphis, TN 38103**

OWNER: Shelby County Support Services

FROM: SSR
SSR No: 13650760

DATE: March 18, 2015

Revise Project Documents as follows:

- Item AD-1. Section 004113 Bid Form: Replace with the attached revised section which includes the revised contract time.
- Item AD-2. Section 262923 Variable-Frequency Motor Controllers; paragraph 2.6 (Bypass Systems); delete in its entirety.
- Item AD-3. Drawing M1.1, Pump Schedule, Notes; add the following note number 7 "Provide Motor Shaft Grounding Ring".
- Item AD-4. Drawing M1.1, Pump Schedule; Pump P-1; under column entitled "Application" change Condenser Water Pump to Chilled Water Pump; under column entitled "GPM" change 1800 to 1050; under column entitled "Access" add new note number 7 "Provide Motor Shaft Grounding Ring".
- Item AD-5. Drawing M1.1, Pump Schedule; Pumps P-PL-1, P-PL-2, P-CW-1, P-CW-2; under column entitled "Access", for each pump add new note number 7 "Provide Motor Shaft Grounding Ring".
- Item AD-6. Drawing M1.1, Cooling Tower Schedule; Cooling Tower CT-1L; under column entitled "E.W.T." change 95 F to 94.4 F.
- Item AD-7. Clarification: Existing underground utility information provided by MLGW. Refer to attached drawings for existing mlgw water, gas,

and electric utilities drawings. Contractor responsible for verifying actual location of utilities.

- Item AD-8. Clarification: Contractor is responsible for smoke control inside building during welding.
- Item AD-9. Clarification: Buildings will be occupied during construction. Contractor may be asked to adhere to occupants request to minimize noise during normal working hours.
- Item AD-10. Clarification: Bid results will be made public after review by owner and approved by mayor's office.
- Item AD-11. Clarification: Grooved pipe is not acceptable in lieu of weld pipe.
- Item AD-12. Clarification: Quality control inspection requirements listed on structural sheet S0.2 apply to structural design components only. Contractor is responsible for arranging, payment, and coordination of inspections.
- Item AD-13. Clarification: Daikin and McQuay chillers are not an acceptable substitution.
- Item AD-14. Clarification: Contact Steve Harkness Steve.Harkness@shelbycountyttn.gov 901-222-2428 to arrange a site visit.

Acknowledgment

Acknowledge receipt of this Addendum by inserting its number and date in the space provided in the Bid Form.

End of Addendum