



# Shelby County Tennessee

Mark H. Luttrell, Jr., Mayor

## Addendum No. 5

*Issued: April 28, 2016*

**RFP 16-003-62**

### **ACCESSIBILITY IMPROVEMENTS 140 ADAMS AVENUE, MEMPHIS, TN**

#### **TO ALL PROSPECTIVE BIDDERS:**

**The above described RFP modified to reflect the following change:**

#### **Clarification Note regarding handrail installation:**

At drawings 4/A2.2 and 5/A2.2, the Architectural Handrail posts are shown set in sleeves cast in concrete. These should be 3" diameter PVC pipe sleeves at each post, finished with non shrink grout "lockrock" or equal. Set posts vertical, extending to 30" below the finish surface of the walk, in a 12" diameter, 36" deep concrete filled post hole in compacted fill. Rails are continuous and set parallel to the slope of the ramp and/or landing.

**THIS ADDENDUM MUST BE RECOGNIZED ON THE BID FORM.**

If you have any questions, please contact me via email at [tosha.davenport@shelbycountyttn.gov](mailto:tosha.davenport@shelbycountyttn.gov)

Sincerely,

**Signed Original on File**

Tosha Davenport, Purchasing Specialist  
Purchasing Department  
Shelby County Government