



Shelby County Government

MARK H. LUTTRELL, JR.
MAYOR

May 6, 2015

TO ALL PLAN HOLDERS:

RE: Addendum No. 1 to Sealed Bid No. I-000326
Congestion Management Program – Signal System Set #8
PIN 115241.14

Please make the attached documents part of your proposal:

Revisions to the plan sheets are denoted with revision clouds. Copies of these revised sheets are attached.

Question 1: Can the concrete required to be installed around the proposed pull boxes be included under a separate item?

Answer: Yes, please see revised bid form and quantities sheet.

Question 2: Please provide clarity on the difference between the two types of cable markers.

Answer: Item No. 725-03.60 CABLE MARKER is for post type cable markers to be used in the open areas of the Interstate 40 interchange to identify where the underground fiber is located. Item No. 730-12.42 CURB MARKER (CURB MOUNTED CABLE MARKER) is for the curb mounted underground cable markers. Please see the attached detail sheet for the type of post cable markers to be used. This detail sheet is provided only to illustrate the basic post design and is not intended as a requirement to supply the specific brand of post shown; equivalent products are allowable.

Question 3: Can a dual RDS unit be operated with a single solar panel and associated cabinet equipment or are two solar panels and associated cabinet equipment required?

Answer: The plans and estimated quantities provide for a separate solar power system for each RDS unit at the location in question (RDS AP-2). However, upon review it was determined that a preferable communication design would be to have two fully independent RDS installations at this location with fiber optic drop cable interconnection between the two units in lieu of the RDS cable previously shown. The bid form and quantity sheet have been revised as follows:

- Quantity of Item No. 725-03.09 ETHERNET SWITCH (TYPE A) is increased to 15 EACH.
- Quantity of Item No. 725-21.96 RDS COMM CABLE is reduced to 210 L.F.
- Quantity of Item No. 725-24.01 CABINET (TYPE A) is increased to 7 EACH.
- Item No. 725-24.04 CABINET (TYPE D) is eliminated.
- Quantity of Item No. 730-03.31 FIBER DISTRIBUTION BOX is increased to 15 EACH.
- Quantity of Item NO. 730-08.41 INTERCONNECT CABLE – FIBER OPTIC (DROP CABLE, 6-FIBER, SINGLE MODE) is increased to 1330 L.F.

Question 4: Can an item for water be included to be used with the sod item?

Answer: Yes, Item No. 801-03 WATER (SEEDING & SODDING) has been included on the revised bid form and quantities sheet.

If you have any questions, please call me at 222-7705.

Sincerely,

A handwritten signature in black ink, appearing to read "Nelson Fowler", written in a cursive style.

Nelson Fowler, Manager A
Shelby County Government
901-222-2250

Cc: Darren Sanders, Shelby County Engineer
James Crook, Shelby County Engineering Department
Sealed Bid File SBI-000326