

- 23 INCLUDES RISER ASSEMBLY, BUILDING ENTRANCE ENCLOSURE, AND WALL PENETRATION.
- 24 LUMP SUM ITEM TO INCLUDE ALL COSTS RELATED TO PROCURING AND MAINTAINING FOR THE DURATION OF THE PROJECT RAILROAD PROTECTIVE LIABILITY (RPL) INSURANCE AS MAY BE REQUIRED BY THE RAILROAD(S) HAVING FACILITIES WITHIN THE PROJECT LIMITS. INSURANCE COVERAGE SHALL BE OF THE FORM AND LIMITS REQUIRED BY THE VARIOUS RAILROAD COMPANIES. PAYMENT WILL BE MADE IN AN AMOUNT EQUAL TO THE ACTUAL COST OF THE RPL POLICIES AS DOCUMENTED BY INVOICES FROM THE INSURER WITH PROOF OF PAYMENT.
- 25 ITEM TO BE USED FOR SIDEWALK REMOVAL OUTSIDE OF FOOTPRINT FOR NEW RAMPS.
- 26 ITEM TO BE USED TO INSTALL NEW SIDEWALK OUTSIDE OF FOOTPRINT OF NEW RAMPS.
- 27 ITEM TO INCLUDE THE INSTALLATION OF NEW CURB RAMPS WHERE EXISTING RAMPS ARE LOCATED, REMOVAL OF EXISTING SIDEWALK MATERIAL WITHIN FOOTPRINT OF NEW RAMPS, AND/OR THE INSTALLATION OF TRUNCATED DOMES ON EXISTING RAMPS WHERE SHOWN ON PLANS.
- 28 TO INCLUDE THE REMOVAL OF PUSH BUTTONS, PEDESTRIAN SIGNS, AND/OR DISPLAYS AS SPECIFIED ON PLANS, PER INTERSECTION.
- 29 ITEM INCLUDES CONCRETE FOUNDATION OR SCREW DOWN ANCHOR FOUNDATION AS APPROVED BY THE ENGINEER.
- 30 ITEM TO INCLUDE ALL MATERIALS NECESSARY TO INSTALL A FULLY FUNCTIONAL AUDIBLE PEDESTRIAN SYSTEM. APS TO HAVE A STAND ALONE POWER SUPPLY, BUILT IN CONFLICT MONITORING SYSTEMS, AND ETHERNET CAPABILITIES. PUSH BUTTONS TO HAVE THE ABILITY TO PROGRAM CUSTOM AUDIO MESSAGES FOR EACH INDIVIDUAL BUTTON, CONFIRMATION OF BUTTON PUSH VIA LED, SOUND, AND TACTILE BOUNCE, VIBRATE DURING ASSOCIATED WALK PHASE, AND VOLUMES THAT AUTOMATICALLY ADJUST TO AMBIENT NOISE.
- 31 FOR TREE TRIMMING AS DIRECTED BY THE ENGINEER.