

Site Preparation Notes:

- BEFORE ANY LAND DISTURBING ACTIVITY BEGINS DOWNSLOPE AND SIDE SLOPE PERIMETER EROSION CONTROLS MUST BE IN PLACE.
- PRIOR TO THE PLACEMENT OF ANY FILL OR PAVEMENT CONSTRUCTION, ALL TOPSOIL, SURFACE VEGETATION, AND ANY SOFT OR LOOSE SOILS SHALL BE COMPLETELY REMOVED FROM THE PROPOSED CONSTRUCTION AREAS. TOPSOIL OR OTHER SUCH MATERIAL CONTAINING ORGANIC MATTER SHALL NOT BE USED AS FILL BUT MAY BE STOCKPILED AND USED FOR LANDSCAPING PURPOSES.
- ISOLATED SOFT OR LOOSE AREAS, WHICH ARE UNDERCUT, SHOULD BE BACKFILLED WITH MATERIAL COMPACTED TO THE REQUIRED DENSITY AND IN THE MANNER SPECIFIED BY THE SOILS ENGINEER.
- IN AREAS TO BE FILLED OR PAVED, THE SURFACE OF THE STRIPPED SOIL SHOULD BE DISKED OR SCARIFIED TO A DEPTH OF 6 INCHES AND RECOMPACTED BEFORE PLACING FILL OR PAVEMENT BASE MATERIAL.
- PLACE ANY FILL REQUIRED TO RAISE THE GRADE OF THE SITE IN 6 INCH LAYERS AND COMPACT. SEE SOILS REPORT FOR DETAILED SPECIFICATIONS ON CLEARING AND COMPACTING.
- ALL NEWLY CUT OR FILLED AREAS ARE TO BE FERTILIZED, MULCHED, AND SEEDED AND/OR SODDED TO ADEQUATELY CONTROL SOIL EROSION (INCLUDING ALL BANK STABILIZATION, DITCH IMPROVEMENT AND ANY OTHER WORK THAT INVOLVES EARTHWORK). FERTILIZE, MULCH AND SEED MIX AND/OR SOD SHALL BE APPROVED BY PROJECT ENGINEER OR LANDSCAPE ARCHITECT.
- THE MAXIMUM ALLOWABLE SLOPE ON THIS PROJECT SHALL BE A 3:1 SLOPE.
- THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS FOR HAULING, GRADING, AND DUMPING.
- A STRAIGHT GRADE SHALL BE MAINTAINED BETWEEN THE SPOT ELEVATIONS AND PROPOSED CONTOURS SHOWN ON THE PLAN. ALL ELEVATIONS ARE TO FINISHED GRADE UNLESS OTHERWISE INDICATED.
- FOR UNDERGROUND UTILITY LOCATIONS CALL 1-800-351-1111.
- TWENTY-FOUR (24) HOURS PRIOR TO BEGINNING CONSTRUCTION, THE CONTRACTOR MUST NOTIFY THE CITY OF MEMPHIS CONSTRUCTION INSPECTION OFFICE AT 729-2462.
- ALL DESIGN, CONSTRUCTION, AND MATERIAL SHALL BE IN COMPLIANCE WITH THE CITY OF MEMPHIS AND SHELBY COUNTY CONSTRUCTION SPECIFICATIONS AND STANDARDS.
- ENGINEER'S CERTIFICATION: THE PUBLIC IMPROVEMENTS FOR THIS PROJECT HAVE BEEN DESIGNED IN ACCORDANCE WITH THE CITY OF MEMPHIS DRAINAGE MANUAL AND THE MEMPHIS AND SHELBY COUNTY SUBDIVISION REGULATIONS.

Construction Notes:

- THE LOCATION OF EXISTING UNDERGROUND UTILITIES IS APPROXIMATE AND IS NOT NECESSARILY ALL OF SAME. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING THE APPROPRIATE UTILITY COMPANY TO DETERMINE THE EXACT LOCATION OF ALL UTILITIES AND/OR UNDERGROUND STRUCTURES PRIOR TO THE INITIATION OF ANY CONSTRUCTION. CONTRACTOR SHALL ALSO ASSUME FULL RESPONSIBILITY FOR DAMAGE TO ANY UTILITIES ENCOUNTERED WITHIN CONSTRUCTION PERIMETERS. FOR SITE LOCATION OF EXISTING UTILITIES INVOLVING M.L.G.&W., BELL SOUTH AND/OR TEXAS GAS COMPANY, PLEASE CALL 1-800-351-1111. FOR SEWER SERVICE LOCATIONS, CALL 529-8025.
- NO TRAFFIC CONTROL PLAN IS INCLUDED IN THIS SET. IT IS THE CONTRACTOR'S RESPONSIBILITY TO PREPARE A TRAFFIC CONTROL PLAN FOR APPROVAL. NOTHING IN THIS PLAN IS INTENDED TO SUPERSEDE OR RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY OF INSTALLING APPROPRIATE TRAFFIC CONTROL DEVICES IN ACCORDANCE WITH THE CURRENT MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS.
- NO WORK SHALL BE STARTED UNTIL THE CONTRACTOR'S PLAN FOR THE STAGING OF OPERATIONS HAS BEEN ACCEPTED BY THE ENGINEER.

General Notes:

- PROPERTY LINES SHALL BE FIELD VERIFIED PRIOR TO CONSTRUCTION. GRADING, CLEARING AND THE ERECTION OR REMOVAL OF FENCES ALONG PROPERTY LINES SHALL BE FULLY COORDINATED WITH ADJACENT PROPERTY OWNERS.
- VERIFY SITE CONDITIONS PRIOR TO CONSTRUCTION. NOTIFY THE PROJECT ENGINEER OF ANY VARIATIONS PRIOR TO COMMENCEMENT OF WORK.
- ALL GRADING WORK SHALL BE PERFORMED IN SUCH A MANNER THAT ADJACENT PROPERTIES ARE NOT DAMAGED OR ADVERSELY AFFECTED.
- NEWLY CUT OR FILLED EMBANKMENTS SHALL BE SODDED SOLID OR SEEDDED, MULCHED AND STAKED TO ADEQUATELY PREVENT SOIL EROSION.
- THE LOCATION OF ALL EXISTING UTILITIES SHALL BE VERIFIED PRIOR TO CONSTRUCTION. ALL WORK SHALL BE PERFORMED IN A MANNER TO INSURE THAT EXISTING UTILITIES ARE NEITHER INTERFERED WITH NOR DISRUPTED.
- ALL FILL AREAS AND/OR TRENCH BACKFILL SHALL BE COMPACTED TO 95% STANDARD PROCTOR DENSITY IN 6" LIFTS WITH MOISTURE CONTENT NOT TO EXCEED ±3% OF OPTIMUM. JETTING OR FLOODING OF TRENCHES OR OTHER BACKFILL IS NOT ALLOWED.
- THE CONTRACTOR PERFORMING THE SITE WORK SHALL VERIFY THAT ALL UTILITY TRENCHES -EXISTING & NEW- HAVE BEEN ADEQUATELY COMPACTED TO SUPPORT THE INTENDED LOADS AS SPECIFIED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY PAVING OR TRENCH FAILURES.
- ALL PARKING AREAS ACCESSED FROM THE LOOP ROAD MUST REMAIN ACCESSIBLE DURING CONSTRUCTION. A COUNTY ENGINEERING REPRESENTATIVE WILL BE AVAILABLE TO ASSIST THE CONTRACTOR WITH THIS COORDINATION.
- AT THE END OF THE PROJECT, THE CONTRACTOR SHALL COMPLETELY RESTORE THE AREA USED FOR STAGING OF EQUIPMENT AND THE STOCKPILING OF MATERIAL.

Utility Owners

Electric: Memphis Light, Gas, and Water
Brunswick Service Center
Memphis, Tennessee
Ph. (901) 528-4333
Rep. Keenan Wilburn

Water: Memphis Light, Gas, and Water
220 South Main Street
Memphis, Tennessee 38103
Ph. (901) 528-4720
Rep. Quinton Clark

Gas: Memphis Light, Gas, and Water
Brunswick Service Center
Memphis, Tennessee
Ph. (901) 321-6935
Rep. Jason Simon

Sewer: The City of Memphis
125 North Main Street, Room 639
Memphis, Tennessee 38103
Ph. (901) 576-6725
Rep. Gary W. Vaden

Lighting: Memphis Light, Gas, and Water
Brunswick Service Center
Memphis, Tennessee
Ph. (901) 528-4183
Rep. Ron Couturier

Telephone: BellSouth Telecommunications
3845 Outland Road
Memphis, Tennessee 38118
Ph. (901) 362-9213
Rep. John Cowart

Lighting: To initiate an LOL
work request call
Ph. (901) 367-3343
Option 2


Cable: Comcast Communications
5450 Winchester Road
Memphis, Tennessee 38115
Ph. (901) 365-1770 ext. 4145
Rep. Wade Chillis

Scope of Work for The Peggy Edmiston Administration Center

The work will provide a new roadway for a portion of the Loop Road, which includes curb and gutter, asphalt pavement, improvements to the existing drainage system, and new drainage pipe and structures. The work will require the removal of existing curb and gutter, drainage structures and pipe, pavements, walks and ramps, and the relocation of utilities as indicated on the plans.

SR CONSULTING, LLC
ENGINEERING - PLANNING
LANDSCAPE ARCHITECTURE
5909 Shelby Oaks Drive
Suite 200
Memphis TN 38134
901-373-0380
(fax) 373-0370
info@SRCE-memphis.com

REVISIONS		
CIP PROJECT No. 100102		
ITEM No.	DESCRIPTION OF CHANGE	APPROVAL DATE



DIVISION OF PUBLIC WORKS

GENERAL NOTES

SHELBY COUNTY, TN

SURVEY	Milestone Land Surveying, Inc.	DATE 4/03	BOOK
DRAFTED	SR Consulting, LLC	DATE 3/12	SCALE none
DESIGN	SR Consulting, LLC	DATE 3/12	CHECKED DATE

10/11/2011 10:01:00 AM 3: Peggy Edmiston\pel... 10/11/2011 10:01:00 AM 3:00pm