

ADDENDUM #3 BID FORM

FITE ROAD

1/17/2014

ROADWAY ITEMS

| ITEM NO.  | DESCRIPTION                                           | UNIT | QTY     | UNIT COST | TOTAL |
|-----------|-------------------------------------------------------|------|---------|-----------|-------|
| 105-01    | CONSTRUCTION STAKES, LINES AND GRADES                 | L.S. | 1       |           |       |
| 201-01    | CLEARING AND GRUBBING                                 | L.S. | 1       |           |       |
| 202-01    | REMOVAL OF STRUCTURES AND OBSTRUCTIONS                | L.S. | 1       |           |       |
| 203-03.10 | SELECT GRANULAR MATERIAL                              | TON  | 7,000   |           |       |
| 203-04    | PLACING AND SPREADING TOPSOIL                         | C.Y. | 5,000   |           |       |
| 203-05    | UNDERCUTTING                                          | C.Y. | 20,000  |           |       |
| 203-06    | WATER                                                 | M.G. | 2,500   |           |       |
| 203-10    | EMBANKMENT (COMPACTED IN PLACE)                       | C.Y. | 340,706 |           |       |
|           |                                                       |      |         |           |       |
| 204-08    | FOUNDATION FILL MATERIAL                              | C.Y. | 388     |           |       |
| 204-08.01 | BACK FILL MATERIAL (FLOWABLE FILL)                    | C.Y. | 200     |           |       |
|           |                                                       |      |         |           |       |
| 209-02.03 | 8" TEMPORARY SLOPE DRAIN                              | L.F. | 1,700   |           |       |
| 209-02.05 | 12" TEMPORARY SLOPE DRAIN                             | L.F. | 500     |           |       |
| 209-05    | SEDIMENT REMOVAL                                      | C.Y. | 1,000   |           |       |
| 209-08.02 | TEMPORARY SILT FENCE (WITH BACKING)                   | L.F. | 14,000  |           |       |
| 209-08.03 | TEMPORARY SILT FENCE (WITHOUT BACKING)                | L.F. | 11,495  |           |       |
| 209-08.07 | ROCK CHECK DAM PER                                    | EACH | 24      |           |       |
| 209-08.08 | ENHANCED ROCK CHECK DAM                               | EACH | 49      |           |       |
| 209-09.01 | SANDBAGS                                              | BAG  | 6,500   |           |       |
| 209-09.03 | SEDIMENT FILTER BAG (15' X 15')                       | EACH | 22      |           |       |
| 209-10.20 | TEMPORARY SEDIMENT TRAP                               | C.Y. | 300     |           |       |
| 209-20.03 | POLYETHYLENE SHEETING (6 MIL. MINIMUM)                | S.Y. | 5,000   |           |       |
| 209-40.30 | CATCH BASIN PROTECTION (TYPE A)                       | EACH | 2       |           |       |
| 209-40.33 | CATCH BASIN PROTECTION (TYPE D)                       | EACH | 2       |           |       |
| 209-40.34 | CATCH BASIN PROTECTION (TYPE E)                       | EACH | 4       |           |       |
| 209-40.41 | CATCH BASIN FILTER ASSEMBLY (TYPE 1)                  | EACH | 2       |           |       |
| 209-65.03 | TEMPORARY DIVERSION CHANNEL                           | L.F. | 650     |           |       |
|           |                                                       |      |         |           |       |
| 303-01    | MINERAL AGGREGATE, TYPE A BASE, GRADING D             | TON  | 7,800   |           |       |
| 303-02    | MINERAL AGGREGATE, TYPE B BASE, GRADING D             | TON  | 7,460   |           |       |
| 303-01.01 | GRANULAR BACKFILL (ROADWAY)                           | TON  | 4,121   |           |       |
| 303-10.01 | MINERAL AGGREGATE (SIZE 57)                           | TON  | 900     |           |       |
|           |                                                       |      |         |           |       |
| 307-01.01 | ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A    | TON  | 5,212   |           |       |
| 307-01.08 | ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2 | TON  | 5,277   |           |       |
| 307-02.01 | ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A    | TON  | 347     |           |       |
| 307-02.02 | ASPHALT CEMENT (PG70-22) (BPMB-HM) GRADING A-S        | TON  | 9       |           |       |
| 307-02.03 | AGGREGATE (BPMB-HM) GRADING A-S                       | TON  | 268     |           |       |
| 307-02.08 | ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2 | TON  | 341     |           |       |
|           |                                                       |      |         |           |       |
| 309-01.01 | MINERAL AGGREGATE (A-CBC)                             | TON  | 10,164  |           |       |
| 309-01.02 | PORTLAND CEMENT (A-CBC)                               | TON  | 497     |           |       |
| 309-02    | BITUMINOUS MATERIAL (A-CBC)                           | TON  | 31      |           |       |
|           |                                                       |      |         |           |       |
| 402-01    | BITUMINOUS MATERIAL FOR PRIME COAT (PC)               | TON  | 66      |           |       |
| 403-01    | BITUMINOUS MATERIAL FOR TACK COAT (TC)                | TON  | 28      |           |       |
|           |                                                       |      |         |           |       |
| 407-02.13 | REMOVAL & DISPOSAL OF EXISTING ASPHALT PAVEMENT       | S.Y. | 345     |           |       |
|           |                                                       |      |         |           |       |
| 411-01.07 | ACS MIX(PG64-22) GRADING E SHOULDER                   | TON  | 488     |           |       |
| 411-01.10 | ACS MIX(PG64-22) GRADING D                            | TON  | 2,667   |           |       |
| 411-02.10 | ACS MIX(PG70-22) GRADING D                            | TON  | 167     |           |       |
|           |                                                       |      |         |           |       |
| 415-01.02 | COLD PLANING BITUMINOUS PAVEMENT                      | S.Y. | 500     |           |       |
|           |                                                       |      |         |           |       |
| 604-01.01 | CLASS A CONCRETE (ROADWAY)                            | C.Y. | 347     |           |       |

ADDENDUM #3 BID FORM

| ITEM NO.  | DESCRIPTION                                | UNIT | QTY     | UNIT COST | TOTAL |
|-----------|--------------------------------------------|------|---------|-----------|-------|
| 604-01.02 | STEEL BAR REINFORCEMENT (ROADWAY)          | LB.  | 55,830  |           |       |
| 604-02.01 | CLASS A CONCRETE (BOX BRIDGES)             | C.Y. | 755     |           |       |
| 604-02.02 | STEEL BAR REINFORCEMENT (BOX BRIDGES)      | LB.  | 117,790 |           |       |
| 604-07.01 | RETAINING WALL (WALL NO. 1)                | S.F. | 4,421   |           |       |
| 604-07.02 | RETAINING WALL (WALL NO. 2)                | S.F. | 9,631   |           |       |
| 604-07.03 | RETAINING WALL (WALL NO. 3)                | S.F. | 5,896   |           |       |
| 604-09.10 | CLASS A CONCRETE (GENERAL USE)             | C.Y. | 100     |           |       |
|           |                                            |      |         |           |       |
| 606-24.10 | SHEET PILES                                | S.F. | 1,800   |           |       |
| 606-24.12 | TEMPORARY SHEET PILES                      | S.F. | 3,750   |           |       |
|           |                                            |      |         |           |       |
| 607-03.02 | 18" CONCRETE PIPE CULVERT (CLASS III)      | L.F. | 449     |           |       |
| 607-05.02 | 24" CONCRETE PIPE CULVERT (CLASS III)      | L.F. | 324     |           |       |
| 607-05.03 | 24" CONCRETE PIPE CULVERT (CLASS IV)       | L.F. | 244     |           |       |
| 607-06.02 | 30" CONCRETE PIPE CULVERT (CLASS III)      | L.F. | 68      |           |       |
| 607-07.02 | 36" CONCRETE PIPE CULVERT (CLASS III)      | L.F. | 69      |           |       |
| 607-08.02 | 42" CONCRETE PIPE CULVERT (CLASS III)      | L.F. | 67      |           |       |
| 607-09.02 | 48" CONCRETE PIPE CULVERT (CLASS III)      | L.F. | 50      |           |       |
| 607-39.02 | 18" PIPE CULVERT (SIDE DRAIN)              | L.F. | 92      |           |       |
| 607-39.02 | 24" PIPE CULVERT (SIDE DRAIN)              | L.F. | 70      |           |       |
| 607-57.04 | REINFORCED CONCRETE PIPE ARCH (44"x27")    | L.F. | 41      |           |       |
|           |                                            |      |         |           |       |
| 610-07.03 | 18" PIPE DRAIN (BRIDGE DRAIN)              | L.F. | 295     |           |       |
|           |                                            |      |         |           |       |
| 611-01.20 | ADJUSTMENT OF EXISTING MANHOLE             | EACH | 8       |           |       |
| 611-02.10 | JUNCTION BOX, TYPE 1                       | EACH | 1       |           |       |
| 611-02.13 | JUNCTION BOX, TYPE 4                       | EACH | 1       |           |       |
|           |                                            |      |         |           |       |
| 611-07.01 | CLASS A CONCRETE (PIPE ENDWALLS)           | C.Y. | 36.4    |           |       |
| 611-07.02 | STEEL BAR REINFORCEMENT (PIPE ENDWALLS)    | LB.  | 3,091   |           |       |
| 611-07.03 | STRUCTURAL STEEL (PIPE ENDWALLS)           | LB.  | 1,837   |           |       |
| 611-14.02 | CATCH BASINS, TYPE 14, > 4' - 8' DEPTH     | EACH | 4       |           |       |
| 611-42.01 | CATCH BASINS, TYPE 42, 0' - 4' DEPTH       | EACH | 1       |           |       |
| 611-42.02 | CATCH BASINS, TYPE 42, >4' - 8' DEPTH      | EACH | 1       |           |       |
|           |                                            |      |         |           |       |
| 620-01    | ALUMINUM RAILING (RETAINING WALLS)         | L.F. | 757     |           |       |
|           |                                            |      |         |           |       |
| 621-01.10 | TEMPORARY STRUCTURE (3-84"PIPES)           | L.S. | 1       |           |       |
| 621-03.02 | 18" TEMPORARY DRAINAGE PIPE                | L.F. | 30      |           |       |
| 621-03.03 | 24" TEMPORARY DRAINAGE PIPE                | L.F. | 70      |           |       |
| 621-03.04 | 30" TEMPORARY DRAINAGE PIPE                | L.F. | 100     |           |       |
| 621-03.06 | 42" TEMPORARY DRAINAGE PIPE                | L.F. | 30      |           |       |
|           |                                            |      |         |           |       |
| 702-03    | CONCRETE COMBINED CURB & GUTTER            | C.Y. | 7       |           |       |
|           |                                            |      |         |           |       |
| 703-01    | CEMENT CONCRETE DITCH PAVING               | C.Y. | 70      |           |       |
|           |                                            |      |         |           |       |
| 705-01.01 | GUARDRAIL AT BRIDGE ENDS                   | L.F. | 108     |           |       |
| 705-02.02 | SINGLE GUARDRAIL (TYPE 2)                  | L.F. | 4,514   |           |       |
| 705-04.03 | GUARDRAIL TERMINAL (TYPE 13)               | EACH | 1       |           |       |
| 705-04.04 | GUARDRAIL TERMINAL (TYPE 21)               | EACH | 5       |           |       |
| 705-04.07 | TAN ENERGY ABSORBING TERM (NCHRP 350, TL3) | EACH | 10      |           |       |
| 705-04.09 | EARTH PAD FOR TYPE 38 GR END TREATMENT     | EACH | 10      |           |       |
| 705-08.51 | PORTABLE IMPACT ATTENUATOR NCHRP350 TL-3   | EACH | 8       |           |       |
|           |                                            |      |         |           |       |
| 709-01.01 | RUBBLE STONE RIP-RAP                       | C.Y. | 11      |           |       |
| 709-05.05 | MACHINED RIP-RAP (CLASS A-3)               | TON  | 5,705   |           |       |
| 709-05.06 | MACHINED RIP-RAP (CLASS A-1)               | TON  | 3,224   |           |       |
| 709-05.08 | MACHINED RIP-RAP (CLASS B)                 | TON  | 1,512   |           |       |

**ADDENDUM #3 BID FORM**

| ITEM NO.  | DESCRIPTION                                             | UNIT   | QTY   | UNIT COST   | TOTAL       |
|-----------|---------------------------------------------------------|--------|-------|-------------|-------------|
| 709-05.09 | MACHINED RIP-RAP (CLASS C)                              | TON    | 2,555 |             |             |
| 710-02    | AGGREGATE UNDERDRAINS (WITH PIPE)                       | L.F.   | 1,100 |             |             |
| 710-05    | LATERAL UNDERDRAIN                                      | L.F.   | 120   |             |             |
| 710-06.13 | LATERAL UNDERDRAIN ENDWALL (4:1)                        | EACH   | 5     |             |             |
| 712-01    | TRAFFIC CONTROL                                         | L.S.   | 1     |             |             |
| 712-02.02 | INTERCONNECTED PORTABLE BARRIER RAIL                    | L.F.   | 1,360 |             |             |
| 712-04.01 | FLEXIBLE DRUMS (CHANNELIZING)                           | EACH   | 400   |             |             |
| 712-05.03 | WARNING LIGHTS (TYPE C)                                 | EACH   | 134   |             |             |
| 712-06    | SIGNS (CONSTRUCTION)                                    | S.F.   | 1,590 |             |             |
| 712-07.03 | TEMPORARY BARRICADES (TYPE III)                         | L.F.   | 220   |             |             |
| 712-08.03 | ARROW BOARD (TYPE C)                                    | EACH   | 2     |             |             |
| 713-11.01 | "U" SECTION STEEL POSTS                                 | LB.    | 1,400 |             |             |
| 713-11.02 | PERFORATED/KNOCKOUT SQUARE TUBE POST                    | LB.    | 690   |             |             |
| 713-13.02 | FLAT SHEET ALUMINUM SIGNS (0.080" THICK)                | S.F.   | 220   |             |             |
| 713-13.03 | FLAT SHEET ALUMINUM SIGNS (0.100" THICK)                | S.F.   | 225   |             |             |
| 713-16.07 | END OF ROADWAY SIGN AND SUPPORT                         | EACH   | 4     |             |             |
| 713-16.20 | SIGN (R3-5R RIGHT TURN ONLY)                            | EACH   | 3     |             |             |
| 713-16.21 | SIGN (R3-5L LEFT TURN ONLY)                             | EACH   | 3     |             |             |
| 713-16.22 | SIGN (D3-3 HWY 51)                                      | EACH   | 1     |             |             |
| 713-16.23 | SIGN (D3-3 FITE ROAD)                                   | EACH   | 2     |             |             |
| 713-16.24 | SIGN (R10-10L LEFT TURN SIGNAL)                         | EACH   | 1     |             |             |
| 716-02.04 | PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING)       | S.Y.   | 93    |             |             |
| 716-02.05 | PLASTIC PAVEMENT MARKING (STOP LINE)                    | L.F.   | 305   |             |             |
| 716-02.06 | PLASTIC PAVEMENT MARKING (TURN LANE ARROW)              | EACH   | 20    |             |             |
| 716-02.08 | PLASTIC PAVEMENT MARKING (8" DOTTED LINE)               | L.F.   | 65    |             |             |
| 716-02.10 | PLASTIC PAVEMENT MARKING (6" LINE)                      | L.M.   | 2.4   |             |             |
| 716-02.12 | PLASTIC PAVEMENT MARKING (8" LINE)                      | L.M.   | 0.2   |             |             |
| 716-03.01 | PLASTIC WORD PAVEMENT MARKING (ONLY)                    | EACH   | 8     |             |             |
| 716-05.01 | PAINTED PAVEMENT MARKING (4" LINE)                      | L.M.   | 4     |             |             |
| 716-05.02 | PAINTED PAVEMENT MARKING (8" LINE)                      | L.F.   | 6,320 |             |             |
| 716-05.20 | PAINTED PAVEMENT MARKING (6" LINE)                      | L.F.   | 423   |             |             |
| 716-06.01 | REMOVAL OF PAVEMENT MARKING (LINE)                      | L.F.   | 8,239 |             |             |
| 716-08.02 | REMOVAL OF PAVEMENT MARKING (8" BARRIER LINE)           | L.F.   | 5,888 |             |             |
| 716-12.01 | ENHANCED FLATLINE THERMO PVMT MRKNG (4IN LINE)          | L.M.   | 1.3   |             |             |
| 716-12.04 | ENHANCED FLATLINE THERMO PVMT MRKNG (4IN DOTTED LINE)   | L.F.   | 45    |             |             |
| 716-12.05 | ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)   | L.F.   | 127   |             |             |
| 716-13.06 | SPRAY THERMO PVMT. MRKNG (40 mil) (4IN LINE)            | L.M.   | 4.7   |             |             |
| 717-01    | MOBILIZATION                                            | L.S.   | 1     |             |             |
| 730-02.09 | SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)               | EACH   | 6     |             |             |
| 730-02.30 | SIGNAL HEAD ASSEMBLY (130A3 WITH BACKPLATE)             | EACH   | 1     |             |             |
| 730-03.21 | INSTALL PULL BOX (TYPE B)                               | EACH   | 6     |             |             |
| 730-05.01 | ELECTRICAL SERVICE CONNECTION                           | ALLOW. | 1     | \$10,000.00 | \$10,000.00 |
| 730-08.03 | SIGNAL CABLE - 7 CONDUCTOR                              | L.F.   | 590   |             |             |
| 730-08.05 | SIGNAL CABLE - 12 CONDUCTOR                             | L.F.   | 280   |             |             |
| 730-08.07 | SIGNAL CABLE - 16 CONDUCTOR                             | L.F.   | 230   |             |             |
| 730-09.01 | SPAN WIRE ASSEMBLY(20,800 LBS.MIN.BRK STRENGTH)         | L.F.   | 508   |             |             |
| 730-10.01 | TETHER WIRE ASSEMBLY - 1/4" DIAMETER                    | L.F.   | 508   |             |             |
| 730-12.01 | CONDUIT 1" DIAMETER (PVC)                               | L.F.   | 900   |             |             |
| 730-12.02 | CONDUIT 2" DIAMETER (PVC)                               | L.F.   | 40    |             |             |
| 730-12.03 | CONDUIT 3" DIAMETER (PVC)                               | L.F.   | 30    |             |             |
| 730-12.13 | CONDUIT 2" DIAMETER (JACK AND BORE)                     | L.F.   | 90    |             |             |
| 730-13.01 | VEHICLE LOOP DETECTOR (SHELF MOUNT)                     | EACH   | 7     |             |             |
| 730-13.06 | VEHICLE DETECTOR (OPTICALLY ACTIVATED PRIORITY CONTROL) | EACH   | 1     |             |             |

**ADDENDUM #3 BID FORM**

| ITEM NO.                                  | DESCRIPTION                                            | UNIT   | QTY    | UNIT COST    | TOTAL               |
|-------------------------------------------|--------------------------------------------------------|--------|--------|--------------|---------------------|
| 730-14.01                                 | SHIELDED DETECTOR CABLE                                | L.F.   | 1,550  |              |                     |
| 730-14.02                                 | SAW SLOT                                               | L.F.   | 920    |              |                     |
| 730-14.03                                 | LOOP WIRE                                              | L.F.   | 2,500  |              |                     |
| 730-15.07                                 | CABINET EIGHT PHASE BASE MOUNTED                       | EACH   | 1      |              |                     |
| 730-16.02                                 | EIGHT PHASE ACTUATED CONTROLLER                        | EACH   | 1      |              |                     |
| 730-23.02                                 | STEEL STRAIN POLE (SIGNAL SUPPORT POLES #1-4)          | EACH   | 4      |              |                     |
| 730-23.03                                 | STEEL STRAIN POLE (OVERHEAD SIGN POLES - 30)           | EACH   | 2      |              |                     |
|                                           |                                                        |        |        |              |                     |
| 740-10.03                                 | GEOTEXTILE (TYPE III)(EROSION CONTROL)                 | S.Y.   | 9,746  |              |                     |
| 740-10.04                                 | GEOTEXTILE (TYPE IV) (STABILIZATION)                   | S.Y.   | 10,000 |              |                     |
| 740-11.02                                 | TEMPORARY SEDIMENT TUBE (12 INCH)                      | L.F.   | 19,000 |              |                     |
| 740-11.04                                 | TEMPORARY SEDIMENT TUBE (20IN)                         | L.F.   | 1,000  |              |                     |
| 740-07.02                                 | GEOGRID REINFORCEMENT (SOIL SLOPES)                    | S.Y.   | 31,000 |              |                     |
|                                           |                                                        |        |        |              |                     |
| 797-05.30                                 | 30 IN DUCTILE IRON PIPE GRAVITY SEWER (6FT-12FT) DEPTH | L.F.   | 360    |              |                     |
| 797-11.38                                 | BY-PASS PUMPING                                        | L.S.   | 1      |              |                     |
| 797-06.97                                 | OPEN CUT 42 IN STEEL CASING PIPE                       | L.F.   | 360    |              |                     |
| 797-07.27                                 | 72 IN MANHOLE 10FT-12FT DEPTH                          | EACH   | 1      |              |                     |
| 797-07.29                                 | 72 IN MANHOLE 14FT-16FT DEPTH                          | EACH   | 1      |              |                     |
|                                           |                                                        |        |        |              |                     |
| 801-01                                    | SEEDING (WITH MULCH)                                   | UNIT   | 219    |              |                     |
| 801-01.05                                 | SEEDING (SPECIAL MIXTURE - SHADE MIX)                  | UNIT   | 31     |              |                     |
| 801-01.06                                 | SEEDING (SPECIAL MIXTURE - SUN MIX)                    | UNIT   | 31     |              |                     |
| 801-01.07                                 | TEMPORARY SEEDING (WITH MULCH)                         | UNIT   | 35     |              |                     |
| 801-01.10                                 | SEEDING (WITH BONDED FIBER MATRIX)                     | UNIT   | 61     |              |                     |
| 801-01.13                                 | BONDED FIBER MATRIX HYDROMULCH (WO/SEED)               | UNIT   | 100    |              |                     |
| 801-01.34                                 | GRASS SEED MIX (RIPZN/FLPL)                            | UNIT   | 81     |              |                     |
| 801-02                                    | SEEDING (WITHOUT MULCH)                                | UNIT   | 622    |              |                     |
| 801-02.08                                 | TEMPORARY SEEDING (WITHOUT MULCH)                      | UNIT   | 35     |              |                     |
| 801-03                                    | WATER (SEEDING & SODDING)                              | M.G.   | 50     |              |                     |
|                                           |                                                        |        |        |              |                     |
| 802-12.07                                 | BETULA NIGRA (RIVER BIRCH SEEDLING B.R.)               | EACH   | 89     |              |                     |
| 802-12.33                                 | QUERCUS MICHAUXII (SWMP CHSTNT OAK SEEDLING B.R.)      | EACH   | 89     |              |                     |
| 802-12.35                                 | QUERCUS NIGRA (WATER OAK SEEDLING B.R.)                | EACH   | 131    |              |                     |
| 802-12.36                                 | QUERCUS NUTTALLII (NUTTALL OAK SEEDLING B.R.)          | EACH   | 131    |              |                     |
| 802-12.42                                 | TAXODIUM DISTICHUM (BALD CYPRESS SEEDLING B.R.)        | EACH   | 89     |              |                     |
| 802-12.59                                 | PRUNUS AMERICANA (AMERICAN PLUM SEEDLING B.R.)         | EACH   | 131    |              |                     |
|                                           |                                                        |        |        |              |                     |
| 803-01                                    | SODDING (NEW SOD)                                      | S.Y.   | 25,010 |              |                     |
|                                           |                                                        |        |        |              |                     |
| 805-01.03                                 | TURF REINFORCEMENT MAT (CLASS III)                     | S.Y.   | 6,680  |              |                     |
| 805-12.02                                 | EROSION CONTROL BLANKET (TYPE II)                      | S.Y.   | 76,566 |              |                     |
| 805-12.03                                 | EROSION CONTROL BLANKET (TYPE III)                     | S.Y.   | 3,733  |              |                     |
|                                           |                                                        |        |        |              |                     |
| 920-10                                    | ICRR FLAGMAN ALLOWANCE                                 | ALLOW. | 1      | \$300,000.00 | \$300,000.00        |
| <b>SUBTOTAL COSTS (FOR ROADWAY ITEMS)</b> |                                                        |        |        |              | <b>\$310,000.00</b> |

**ADDENDUM #3 BID FORM**

| ITEM NO.                                 | DESCRIPTION                                   | UNIT | QTY    | UNIT COST | TOTAL               |
|------------------------------------------|-----------------------------------------------|------|--------|-----------|---------------------|
| <b>BRIDGE ITEMS</b>                      |                                               |      |        |           |                     |
| 204-02.01                                | DRY EXCAVATION (BRIDGES)                      | C.Y. | 418    |           |                     |
| 303-01.02                                | GRANULAR BACKFILL (BRIDGES)                   | TON  | 44     |           |                     |
| 604-02.03                                | EPOXY COATED REINFORCING STEEL                | LB.  | 85,961 |           |                     |
| 604-03.01                                | CLASS A CONCRETE (BRIDGES)                    | C.Y. | 298    |           |                     |
| 604-03.02                                | STEEL BAR REINFORCEMENT (BRIDGES)             | LB.  | 58,797 |           |                     |
| 604-03.04                                | PAVEMENT @ BRIDGE ENDS                        | S.Y. | 315    |           |                     |
| 604-03.09                                | CLASS D CONCRETE (BRIDGE DECK)                | C.Y. | 320    |           |                     |
| 604-04.01                                | APPLIED TEXTURE FINISH (NEW STRUCTURES)       | S.Y. | 1,022  |           |                     |
| 604-05.31                                | BRIDGE DECK GROOVING (MECHANICAL)             | S.Y. | 1,075  |           |                     |
| 606-09.01                                | TEST PILES (PRECAST CONCRETE, SIZE 1)         | L.F. | 305    |           |                     |
| 606-09.02                                | LOADING TEST (PRECAST CONCRETE, SIZE 1)       | EACH | 1      |           |                     |
| 606-09.03                                | PRECAST CONCRETE PILES (SIZE 1)               | L.F. | 3,775  |           |                     |
| 606-12.01                                | PILE ANCHORAGE SYSTEM (SEISMIC)               | EACH | 66     |           |                     |
| 615-01.03                                | PRESTRESSED CONCRETE I-BEAM (TYPE III)        | L.F. | 933    |           |                     |
| 620-05                                   | CONCRETE PARAPET(MODIFIED PARAPET)            | L.F. | 388    |           |                     |
| 709-05.05                                | MACHINED RIP-RAP (CLASS A-3)                  | TON  | 286    |           |                     |
| 710-04                                   | FILTER CLOTH UNDERDRAIN (WITH PIPE)           | L.F. | 240    |           |                     |
| 710-09.01                                | 6" PERFORATED PIPE WITH VERTICAL DRAIN SYSTEM | L.F. | 180    |           |                     |
| 710-09.02                                | 6" PIPE UNDERDRAIN                            | L.F. | 210    |           |                     |
| <b>SUBTOTAL COSTS (FOR BRIDGE ITEMS)</b> |                                               |      |        |           | <b>\$0.00</b>       |
|                                          |                                               |      |        |           |                     |
| <b>SUBTOTAL COSTS (ROADWAY ITEMS)</b>    |                                               |      |        |           | <b>\$310,000.00</b> |
| <b>SUBTOTAL COSTS (BRIDGE ITEMS)</b>     |                                               |      |        |           | <b>\$0.00</b>       |
| <b>TOTAL COSTS</b>                       |                                               |      |        |           | <b>\$310,000.00</b> |