

ADDENDUM 1 REVISED BID FORM

SIGNALIZATION OF THE INTERSECTION OF CENTENNIAL DRIVE/ MISTY MEADOWS DRIVE WITH HACKS CROSS ROAD

ITEM NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY	UNIT PRICE	TOTAL AMOUNT
105-01	Construction Stakes, Lines, And Grades	LS	1		
209-01.10	Erosion And Siltation Control (Signalization Project)	LS	1		
701-01.01	Concrete Sidewalk (4")	SF	125		
712-01	Traffic Control	LS	1		
712-04.01	Flexible Drums (Channelizing)	EACH	30		
712-05.03	Warning Lights (Type C)	EACH	30		
712-06	Signs (Construction)	S.F.	168		
712-08.03	Arrow Board (Type C)	EACH	1		
713-15	Removal Of Signs, Posts And Footings	LS	1		
713-15.07	Suspended Flat Sheet Aluminum Sign (0.080" Thick)	EACH	6		
713-16.30	Signs (D-3 Sign "Centennial Dr")	EACH	2		
713-16.31	Signs (D-3 Sign "Hacks Cross Rd")	EACH	4		
713-16.32	Signs (D-3 Sign "Misty Meadows Ln")	EACH	2		
716-02.03	Plastic Pavement Marking (Cross-Walk)	L.F.	660		
716-02.05	Plastic Pavement Marking (Stop Line)	L.F.	180		
716-02.06	Plastic Pavement Marking (Turn Lane Arrow)	EACH	4		
716-03.01	Plastic Word Pavement Marking (Only)	EACH	4		
716-08.01	Removal Of Pavement Marking (Line)	L.F.	550		
716-08.03	Removal Of Pavement Marking (Cross-Walk)	L.F.	140		
716-13.06	SPRAY THERMO PVMT MRKNG (40 Mil) (4IN LINE)	L.M.	0.4		
717-01	Mobilization	LS	1		
730-02.08	Signal Head Assembly (130 Pole Mounted)	EACH	2		
730-02.09	Signal Head Assembly (130 With Backplate)	EACH	12		
730-02.17	Signal Head Assembly (150 A2h With Backplate)	EACH	2		
730-02.18	Signal Head Assembly (150 A2v)	EACH	2		
730-03.20	Install Pull Box (Type A)	EACH	1		
730-03.21	Install Pull Box (Type B)	EACH	3		
730-03.23	Install Pull Box (Fiber Optic-Type A)	EACH	1		
730-03.24	Install Pull Box (Fiber Optic-Type B)	EACH	1		
730-05.01	Electrical Service Connection	EACH	1		
730-05.09	Electrical Service Connection (MLGW Allowance)	ALLOW.	1	\$5,000	\$5,000
730-05.02	Service Cable (2 Conductor, # 8 Awg)	L.F.	120		
730-05.03	Service Cable (1 Conductor, # 6 Awg)	L.F.	200		
730-08.01	Signal Cable - 3 Conductor	L.F.	270		
730-08.02	Signal Cable - 5 Conductor	L.F.	670		
730-08.03	Signal Cable - 7 Conductor	L.F.	940		
730-08.05	Signal Cable - 12 Conductor	L.F.	630		

Bid Form, page 2.			ESTIMATED	UNIT	TOTAL
ITEM NO.	DESCRIPTION	UNIT	QUANTITY	PRICE	AMOUNT
730-12.01	Conduit 1" Diameter (PVC)	L.F.	340		
730-12.02	Conduit 2" Diameter (PVC)	L.F.	160		
730-12.07	Conduit 1" Diameter (RGS)	L.F.	10		
730-12.16	Conduit (2 1/2" Diameter, Direct Drill)	L.F.	550		
730-12.17	Conduit (3" Diameter, Direct Drill)	L.F.	120		
730-12.42	Curb Marker (Plastic Disk "Glue-On")	EACH	14		
730-13.02	Vehicle Detector (Video)	EACH	4		
730-13.03	Vehicle Detector (4 - Channel, Rack Mount)	EACH	1		
730-13.06	Vehicle Detector (Optically Activated Priority Control)	EACH	4		
730-14.01	Shielded Detector Cable	L.F.	2760		
730-14.02	Saw Slot	L.F.	240		
730-14.03	Loop Wire	L.F.	720		
730-16.02	Eight Phase Actuated Controller	EACH	1		
730-23.30	Pedestal Pole (Type B, 17' X 4")	EACH	1		
730-23.96	Cantilever Signal Support (1 Arm @ 52') (Pole C)	EACH	1		
730-23.97	Cantilever Signal Support (1 Arm @ 60') (Pole B)	EACH	1		
730-23.98	Cantilever Signal Support (1 Arm @ 62') (Pole A)	EACH	1		
730-23.99	Cantilever Signal Support (1 Arm @ 64') (Pole D)	EACH	1		
730-26.05	Countdown Pedestrian Signal	EACH	8		
730-26.09	Pedestrian Pushbutton With 15 Inch Sign	EACH	8		
801-03	Water (Seeding And Sodding)	M.G.	1		
803-01	Sodding (New Sod)	S.Y.	40		