

1
2
3, 4
3, 4

5
6
7
8
9

10
10

11
12

13

14
15
16
17
17
18
18
18
18
19

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	S.Y.	15		
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	C.Y.	50		
203-06	WATER	M.G.	1.5		
209-05	SEDIMENT REMOVAL	C.Y.	5		
306-03.01	PORTLAND CEMENT CONCRETE BASE (PLAIN) 8"	S.Y.	88		
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	TN	0.01		
407-20.05	SAW CUTTING ASPHALT PAVEMENT	L.F.	188		
411-01.10	ASPHALT CEMENT (PG64-22) (ACS) GRADING D	TN	7		
701-02.01	CONCRETE CURB RAMP (RETROFIT)	S.F.	175		
701-02.03	CONCRETE CURB RAMP	S.F.	135		
702-01.02	CONCRETE CURB	L.F.	170		
707-08.10	TEMPORARY CONSTRUCTION FENCE	L.F.	155		
712-01	TRAFFIC CONTROL	LS	1		
713-16.20	SIGNS (MAST ARM MOUNTED STREET NAME SIGN)	EACH	2		
713-16.21	SIGNS (MAST ARM MOUNTED STREET NAME SIGN)	EACH	2		
713-16.22	SIGNS (MAST ARM MOUNTED)	EACH	4		
714-25.09	ELECTRICAL CONNECTION (FOR MLGW COST ONLY)	EACH	1	\$10,000.00	\$10,000.00
716-02.01	PLASTIC PAVEMENT MARKING (4" LINE) - SINGLE	L.M.	0.35		
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	L.F.	410		
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	L.F.	180		
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	EACH	6		
716-03.01	PLASTIC WORD PAVEMENT MARKING (ONLY)	EACH	5		
716-04.01	PLASTIC PAVEMENT MARKING (STRAIGHT-TURN ARROW)	EACH	1		
716-04.05	PLASTIC PAVEMENT MARKING (STRAIGHT ARROW)	EACH	2		
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	L.F.	530		
716-08.03	REMOVAL OF PAVEMENT MARKING (CROSS-WALK)	L.F.	165		
716-08.09	REMOVAL OF PAVEMENT MARKING (DOTTED LINE)	L.F.	97		
716-10.30	TRUNCATED DOME DETECTABLE WARNING MAT	S.F.	30		
717-01	MOBILIZATION	LS	1		
725-02.79	FIBER SPLICE ENCLOSURE(WEATHER PROOF)	EACH	1		
725-10.01	ETHERNET CABINET SWITCH (LAYER 2)	EACH	1		
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	EACH	6		
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	EACH	4		
730-02.18	SIGNAL HEAD ASSEMBLY (150 A2V POLE MOUNTED)	EACH	4		
730-03.16	FIBER DISTRIBUTION BOX	EACH	1		
730-03.20	INSTALL PULL BOX (TYPE B)	EACH	4		
730-03.24	INSTALL PULL BOX (FIBER OPTIC-TYPE B)	EACH	1		
730-05.01	ELECTRICAL SERVICE CONNECTION	EACH	1		
730-08.01	SIGNAL CABLE - 3 CONDUCTOR	L.F.	80		
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	L.F.	400		
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	L.F.	670		
730-08.41	INTERCONNECT CABLE - FIBER OPTIC (DROP CABLE, 6-FIBER, SINGLE MODE)	L.F.	140		
730-12.03	CONDUIT 3" DIAMETER (PVC)	L.F.	60		
730-12.13	CONDUIT 2" DIAMETER (JACK AND BORE)	L.F.	140		
730-12.14	CONDUIT 3" DIAMETER (JACK AND BORE)	L.F.	455		
730-12.42	CURB MARKER (CURB MOUNTED CABLE MARKER)	EACH	6		
730-13.02	VEHICLE DETECTOR (VIDEO)	EACH	1		
730-13.06	VEHICLE DETECTOR (OPTICALLY ACTIVATED PRIORITY CONTROL)	EACH	1		
730-15.32	CABINET (EIGHT PHASE BASE MOUNTED)	EACH	1		
730-16.02	EIGHT PHASE ACTUATED CONTROLLER	EACH	1		
730-23.36	CANTILEVER SIGNAL SUPPORT (1 ARM @ 68')	EACH	1		
730-23.37	CANTILEVER SIGNAL SUPPORT (1 ARM @ 56')	EACH	1		
730-23.38	CANTILEVER SIGNAL SUPPORT (1 ARM @ 52')	EACH	1		
730-23.39	CANTILEVER SIGNAL SUPPORT (1 ARM @ 70')	EACH	1		
730-26.05	COUNTDOWN PEDESTRIAN SIGNAL	EACH	6		
771-30.32	CONCRETE CURB AND GUTTER	L.F.	170		
771-30.33	CONCRETE SIDEWALK	S.F.	230		
802-01.10	TREES (REMOVAL)	EACH	5		
802-01.11	TREES (BURFORDI HOLLIES)	EACH	5		
803-01	SODDING (NEW SOD)	S.Y.	110		
TOTAL BID					