

ESTIMATED PROJECT QUANTITIES					
ITEM NO.	DESCRIPTION	UNIT	PROJECT 1 QUANTITY	PROJECT 2 QUANTITY	TOTAL QUANTITY
105-01	CONSTRUCTION STAKES, LINES AND GRADES	LS	1	1	2
201-01	CLEARING AND GRUBBING	LS	1	1	2
202-03.01	REMOVAL OF ASPHALT PAVEMENT	S.Y.	35	130	165
202-08.10	REMOVAL OF CURB AND GUTTER (6-18 MEDIAN CURB)	L.F.		200	200
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	C.Y.	50	50	100
203-03	BORROW EXCAVATION (UNCLASSIFIED)	C.Y.	50	50	100
203-06	WATER	M.G.	1	1	2
204-06.01	FLOWABLE FILL (GENERAL)	C.Y.		12	12
209-05	SEDIMENT REMOVAL	C.Y.	20	5	25
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	L.F.	990	910	1900
209-99.91	EROSION CONTROL	LS	1	1	2
407-20.05	SAW CUTTING ASPHALT PAVEMENT	L.F.	65	365	430
411-01.11	ACS MIX (PG64-22) GRADING E RDWY	TON	2520.0	50.0	2570
601-10.13	TREATED TIMBER PILE REPLACEMENT	L.F.	50		50
601-10.14	TREATED TIMBER STRINGER REPLACEMENT (6" X 6")	L.F.	95		95
601-10.15	TREATED TIMBER STRINGER REPLACEMENT (8" X 16")	L.F.	60		60
601-10.16	TREATED TIMBER DECKING REPLACEMENT (8 1/2" X 8 1/2" TIES)	L.F.	1325		1325
601-10.17	TREATED TIMBER BALLAST RETAINER REPLACEMENT (5" X 8 1/2" TIES)	L.F.	154		154
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	L.F.	30		30
611-02.10	JUNCTION BOX, TYPE 1	EA	1		1
611-07.31	18IN ENDWALL (SIDE DRAIN)	EA	1		1
701-01.01	CONCRETE SIDEWALK (4")	S.F.	332	735	1067
701-01.02	CONCRETE SIDEWALK (6")	S.F.	4225	600	4825
702-03.01	CONCRETE COMBINED CURB AND GUTTER (6-18 MEDIAN CURB)	L.F.		185	185
705-02.02	SINGLE GUARDRAIL (TYPE 2)	L.F.		50	50
705-04.07	TANGENT ENERGY ABSORBING TERMINAL (NCHRP 350, TL3)	EA		2	2
712-01	TRAFFIC CONTROL	LS	1	1	2
713-11.01	U-SECTION STEEL POSTS	LBS.	2000	335	2335
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	S.F.	346	67	413
716-01.12	RAISED PVMT MARKERS (MONO-DIRECTIONAL) (1 COLOR LENS)	EA	210		210
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	L.F.	117	80	197
716-02.13	PLASTIC PAVEMENT MARKING (CROSSWALK)	S.F.	1232	920	2152
716-04.10	PLASTIC PAVEMENT MARKING (HANDICAP SYMBOL)	EA	1		1
716-05.08	PAINTED PAVEMENT MARKING (PARKING LINE)	L.F.	305		305
716-08.01	REMOVAL OF PAVEMENT MARKING (LINE)	L.F.		480	480
716-10.30	TRUNCATED DOME DETECTABLE WARNING MAT	S.F.	400	105	505
716-13.01	SPRAY THERMO PVMT MRKNG (60 MIL) (4IN LINE)	L.M.		0.04	0.04
717-01	MOBILIZATION	LS	1	1	2
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	EA		6	6
730-03.21	INSTALL PULL BOX (TYPE B)	EA		4	4
730-03.25	INSTALL PULL BOX (FIBER OPTIC-TYPE B with Splice Enclosure)	EA		1	1
730-05.01	ELECTRICAL SERVICE CONNECTION	ALLOW		1	1
730-05.02	SERVICE CABLE (2 CONDUCTOR, #8 AWG)	L.F.		105	105
730-08.01	SIGNAL CABLE - 3 CONDUCTOR	L.F.		892	892
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	L.F.		535	535

UNIT COST	PROJECT 1 COST	PROJECT 2 COST	TOTAL COST
N/A			\$0.00
N/A			\$0.00
	\$0.00	\$0.00	\$0.00
		\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
		\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
N/A			\$0.00
	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
	\$0.00		\$0.00
	\$0.00		\$0.00
	\$0.00		\$0.00
	\$0.00		\$0.00
	\$0.00		\$0.00
	\$0.00		\$0.00
	\$0.00		\$0.00
	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
		\$0.00	\$0.00
		\$0.00	\$0.00
		\$0.00	\$0.00
N/A			\$0.00
	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
	\$0.00		\$0.00
	\$0.00	\$0.00	\$0.00
	\$0.00		\$0.00
	\$0.00		\$0.00
		\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
		\$0.00	\$0.00
		\$0.00	\$0.00
N/A			\$0.00
		\$0.00	\$0.00
		\$0.00	\$0.00
N/A		\$5,000.00	\$5,000.00
		\$0.00	\$0.00
		\$0.00	\$0.00
		\$0.00	\$0.00

