

STATE OF TENNESSEE

SHELBY COUNTY

DIVISION OF PUBLIC WORKS

PLAN FOR PROPOSED IMPROVEMENTS

CONGESTION MANAGEMENT PROGRAM

SIGNAL SYSTEM PROJECT SET #5

SCOPE OF WORK

THE SCOPE OF WORK INCLUDES INSTALLING CONDUIT WITH FIBER OPTIC CABLE INTERCONNECT ALONG YALE RD FROM SYCAMORE VIEW RD TO BROTHER BLVD AND ALONG JACKSON AVE FROM TREZEVANT ST TO WALES AVE. THE SCOPE OF WORK ALSO INCLUDES THE INSTALLATION OF VIDEO DETECTION AND/OR EMERGENCY VEHICLE PREEMPTION EQUIPMENT AT SELECT INTERSECTIONS WITHIN THE PROJECT AREA.

INVENTORY # - 351812Y
LOG MILE LOCATION - 0363.91


-  - PROJECT LOCATIONS
-  - PROJECT INTERSECTION LOCATIONS
-  - RADAR DETECTION SYSTEM LOCATIONS

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	GENERAL NOTES
3	QUANTITIES
4	TABULATED QUANTITIES
5	CABLE LAYOUT AND UTILITY SHEET KEY MAP
6	SYSTEM DETECTORS AND INTERSECTION I.D.
7	COMMUNICATIONS CABLE SCHEMATIC
8	COMMUNICATION CHANNEL SCHEMATIC
9	PHASING DIAGRAMS
10-24	CABLE LAYOUT SHEETS
25-40	INTERSECTION LAYOUT SHEET
41-52	SPLICE DIAGRAM SHEETS
53-67	EXISTING UTILITIES SHEETS
68-72	MISCELLANEOUS DETAILS

INVENTORY # - 348549W
LOG MILE LOCATION - 0371.91


INVENTORY # - 348548P
LOG MILE LOCATION - 0371.78



VICINITY MAP
NOT TO SCALE

EQUATIONS: NONE
EXCEPTIONS: NONE

TDOT P.I.N.: 115241.11
FEDERAL PROJECT NO.: CM-7900(48)
STATE PE NO.: 79LPLM-F1-284
STATE CONSTRUCTION NO.: 79LPLM-F3-285
LOCALLY MANAGED PROJECT



LOCATION MAP
NOT TO SCALE

NOTES:
PROPOSALS MAY BE REJECTED BY THE COUNTY ENGINEER IF ANY OF THE UNIT PRICES CONTAINED THEREIN ARE OBVIOUSLY UNBALANCED, EITHER EXCESSIVE OR BELOW THE REASONABLE COST ANALYSIS VALUE.

CONTRACTOR SHALL BE RESPONSIBLE FOR NOTIFYING ANY UTILITY COMPANY WHICH MAINTAINS A UTILITY LINE WITHIN THE BOUNDARIES OF THE PROJECT PRIOR TO THE INITIATION OF ANY CONSTRUCTION ON THE PROJECT OR IN THE STREETS BORDERING THE PROJECT. THE CONTRACTOR SHALL ALSO ASSUME RESPONSIBILITY FOR ALL DAMAGE TO ANY UTILITY LINES, WHETHER SHOWN ON THE CONSTRUCTION PLANS OR NOT, DURING WORK ON THE PROJECT.

THIS PROJECT TO BE CONSTRUCTED UNDER THE STANDARD SPECIFICATIONS OF THE TENNESSEE DEPARTMENT OF TRANSPORTATION DATED MARCH 1, 2006 AND ADDITIONAL SPECIFICATIONS AND SPECIAL PROVISIONS CONTAINED IN THE PLANS AND IN THE PROPOSAL CONTRACT.

HON. MARK H. LUTTRELL, JR, MAYOR

APPROVED: _____ DATE: _____

MR. DARREN SANDERS, P.E.
SHELBY COUNTY ENGINEER

THE FOLLOWING SIGNATURES ONLY APPLY TO LOCATIONS WITHIN THE CITY OF MEMPHIS LIMITS.

REVIEWED: _____ DATE: _____

CITY OF MEMPHIS ENGINEER

REVIEWED: _____ DATE: _____

CITY OF MEMPHIS TRAFFIC ENGINEER

INVENTORY # - 348511A
LOG MILE LOCATION - 0369.68



DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bld Set 5\Plans\BldSet 5-02-GeneralNotes.dwg Layout1 Jan 30, 2015 3:25PM BY: bblaine.lync

LEGEND
(FOR CABLE LAYOUT SHEETS)

	EXISTING	PROPOSED
WOOD POLE		
METAL/ALUMINUM PEDESTAL POLE		
GUY WITH ANCHOR		
STANDARD PULL BOX		
FIBER OPTIC PULL BOX		
POLE MOUNTED RDS CABINET		
POLE MOUNTED CONTROLLER CABINET		
BASE MOUNTED CONTROLLER CABINET		
BASE MOUNTED HUB CABINET		
SPLICE ENCLOSURE		
TRENCH CONDUIT		
JACKED OR BORED CONDUIT		
LOOP LEAD-IN WIRE IN SAW CUT	NOT SHOWN	
MASTARM POLE		
VIDEO DETECTION CAMERA		
SIGNAL HEAD		
SIGNAL HEAD WITH BACKPLATE		
PEDESTRIAN SIGNAL HEAD		
PEDESTRIAN PUSH BUTTON		
SINGLE CHANNEL EMERGENCY VEHICLE PREEMPTION DETECTOR		
DUAL CHANNEL EMERGENCY VEHICLE PREEMPTION DETECTOR		
EMERGENCY VEHICLE PREEMPTION CONFIRMATION LAMP		
EMERGENCY VEHICLE PREEMPTION CONFIRMATION BEACON		
WATER LINE		
ELECTRIC LINE		
GAS LINE		
SEWER LINE		
RIGHT OF WAY		

UTILITY OWNERS			
CITY OF MEMPHIS			
GAS, WATER, & ELECTRIC:	MEMPHIS LIGHT, GAS, & WATER 220 S. MAIN ST. MEMPHIS, TN 38103 (901) 528-4186 KEITH LEDBURY	CATV:	COMCAST INC. 5450 WINCHESTER RD. MEMPHIS, TN 38115 (901) 365-1770 EXT. 4114 REX MORRIS
TRAFFIC SIGNAL & COMMUNICATIONS	CITY OF MEMPHIS 980 S. THIRD ST. MEMPHIS TN, 38106 (901) 528-2844 JAY WALKO	CITY OF BARTLETT	
TELEPHONE:	AT&T 5530 STAGE RD. MEMPHIS, TN 38115 (901) 797-3501 ALEX LASKARIS	WATER & SEWER:	CITY OF BARTLETT 6382 STADE RD. BARTLETT, TN 38134 (901) 385-6499 TIMOTHY J. HERNDON, P.E.

TRAFFIC CONTROL NOTES

1. NOTHING IN THIS PLAN IS INTENDED TO SUPERSEDE OR RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY OF INSTALLING THE APPROPRIATE TRAFFIC CONTROL DEVICES IN ACCORDANCE WITH THE CURRENT STATE OF TENNESSEE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS."
2. THE CONTRACTOR SHALL BE REQUIRED TO NOTIFY THE JURISDICTION IN WHICH THE WORK IS BEING DONE A MINIMUM OF 72 HOURS PRIOR TO COMMENCING CONSTRUCTION OR IMPLEMENTING A TRAFFIC CONTROL PLAN. FOR THIS PROJECT THE CONTRACTOR SHALL CONTACT THE FOLLOWING AGENCIES:

CITY OF MEMPHIS CONSTRUCTION INSPECTION
(901) 636-2462

CITY OF BARTLETT
(901) 385-6499

ALL TRAFFIC CONTROL DEVICES MUST BE IN PLACE BEFORE CONSTRUCTION ACTIVITY BEGINS.
3. ALL TRAFFIC CONTROL DEVICES AND THEIR INSTALLATION SHALL MEET THE STANDARD PRESCRIBED IN THE STATE OF TENNESSEE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES AND SHALL COMPLY WITH THE STATE OF TENNESSEE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION SECTION 712 TEMPORARY TRAFFIC CONTROL.
4. ACCESS TO ADJACENT PROPERTIES SHALL BE MAINTAINED AT ALL TIMES.
5. SIDE STREET, DRIVEWAY ACCESS, AND SAFE PEDESTRIAN WAYS SHALL BE MAINTAINED AT ALL TIMES.
6. THE CONTRACTOR SHALL NOT BE PERMITTED TO PARK ANY VEHICLES OR CONSTRUCTION EQUIPMENT DURING PERIODS OF INACTIVITY, WITHIN THE RIGHT-OF-WAY OR WITHIN THIRTY (30) FEET OF THE EDGE OF PAVEMENT WHICHEVER IS LESS, WHEN THE LANE IS OPEN TO TRAFFIC, UNLESS PROTECTED BY GUARDRAIL, BRIDGE RAIL, AND/OR BARRIERS INSTALLED FOR OTHER PURPOSES. PRIVATELY OWNED VEHICLES SHALL NOT BE ALLOWED TO BE PARKED WITHIN THE RIGHT-OF-WAY OR WITHIN THIRTY (30) FEET OF AN OPEN TRAFFIC LANE WHICHEVER IS LESS, AT ANY TIME UNLESS PROTECTED AS DESCRIBED ABOVE.
7. IF USED, THE CONTRACTOR SHALL USE PLASTIC DRUMS WITH TYPE "C" WARNING LIGHTS TO SEPARATE TRAFFIC FROM THE CONSTRUCTION AREA.
8. DRUMS WITH TYPE "C" WARNING LIGHTS SHALL DELINEATE THE EDGE OF PAVEMENT THROUGH THE ENTIRE CONSTRUCTION AREA, IF USED.
9. THE CONTRACTOR SHALL COVER ALL EXISTING SIGNS THAT CONFLICT WITH THE TRAFFIC CONTROL PLAN SIGNS OR DEVICES DURING CONSTRUCTION AND THEY SHALL REMAIN COVERED DURING CONSTRUCTION AND UNTIL SUCH TIME THAT NO CONFLICT EXISTS.
10. DURING CONSTRUCTION, A MINIMUM OF ONE 11 FOOT LANE OF TRAFFIC IN EACH DIRECTION SHALL REMAIN OPEN TO TRAFFIC AT ALL TIMES.
11. ALL TEMPORARY OR PERMANENT TRAVELED SURFACE SHALL BE INSPECTED DAILY BY THE CONTRACTOR (INCLUDING WEEKENDS) AND NECESSARY PATCHING OR RE-FINISHING PERFORMED.
12. WORK WITHIN THE ROADWAY SHALL BE CONDUCTED BETWEEN 9:00 A.M. AND 4:00 P.M. THE ROADWAY SHALL BE COMPLETELY OPEN TO TRAFFIC AT ALL OTHER TIMES AND ALL INAPPROPRIATE SIGNS SHALL BE COVERED OR REMOVED.
13. THE CONTRACTOR SHALL CONTACT ALL APPROPRIATE AGENCIES BEFORE CLOSING ANY ROADWAYS.
14. THE CONTRACTOR SHALL CONTACT THE CITY OF MEMPHIS SIGNAL SHOP AT 901-528-2844 FOR LOCATION OF SIGNAL CONDUIT AND WIRES.

CABLE MARKERS

1. THE CONTRACTOR SHALL INSTALL CABLE MARKERS TO IDENTIFY THE PROPOSED SIGNAL CABLES AND FIBER OPTIC COMMUNICATION CABLES. LEGENDS AND COLORS FOR MARKERS ARE TO APPEAR ACCORDING TO THE INFORMATION SUPPLIED BY THE CITY OF MEMPHIS SIGNAL MAINTENANCE DEPARTMENT. THE MARKERS ARE TO BE PERMANENT, BRIGHTLY COLORED, NON-REFLECTIVE, WITH BLACK LETTERING. CURB MARKERS SHALL BE RED IN COLOR FOR TRAFFIC SIGNALS AND ORANGE IN COLOR FOR FIBER OPTIC CABLES. MARKERS ARE TO BE MANUFACTURED OF PLASTIC, VINYL OR FIBERGLASS MATERIAL THAT IS DURABLE, UV LIGHT-RESISTANT, WEATHER-PROOF AND SCRATCH-RESISTANT.
2. CURB MARKERS SHALL BE INSTALLED TO IDENTIFY CABLES THAT ARE IN OR NEAR THE STREET. CURB MARKERS ARE TO BE FOUR-INCH DIAMETER ROUND DISKS APPLIED TO CONCRETE OR METAL SURFACES WITH AN ADHESIVE ACCORDING TO THE RECOMMENDATIONS OF THE MANUFACTURER. CURB MARKERS ARE TO BE INSTALLED ON CABINET AND POLE FOUNDATIONS ON THE SIDE ABOVE THE CABLE. CURB MARKERS ARE TO BE INSTALLED ON THE STREET CURB OVER THE LOCATION OF CROSSING CABLES. CURB MARKERS ARE ALSO TO BE PLACED ON THE CURB AT 100-FOOT SPACING ALONG ANY RUN OF CABLE THAT IS PARALLEL TO THE CURB. WHERE PAVED SHOULDER EXISTS INSTEAD OF CURB, PLACE CURB MARKERS ON THE PAVEMENT SURFACE ONE FOOT FROM THE EDGE OF THE SURFACE, OR DIRECTLY OVER THE CONDUIT OR CABLE. CURB MARKERS ARE TO BE DURACAST STYLE CURB MARKERS AS MADE BY DAS MANUFACTURING, WILLIAM FRICK AND CO., OR APPROVED EQUAL. CURB MARKERS SHALL BE ABRASION AND UV-RESISTANT.
3. PAYMENT AT THE CONTRACT UNIT PRICE, PER EACH, SHALL BE MADE FOR EACH INSTALLED AND ACCEPTED CABLE MARKER AS FOLLOWS:

ITEM NUMBER 730-12.42 - CURB MARKERS (CURB MOUNTED CABLE MARKER)

MISCELLANEOUS

1. THE LOCATIONS OF ALL NEW PULL BOXES AND CABINETS ARE SCHEMATIC. ADDITIONAL PULL BOXES MAY BE REQUIRED FOR BORING UNDER DRIVEWAYS. THE ENGINEER SHALL APPROVE THE FINAL LOCATIONS OF ALL PULL BOXES IN THE FIELD. THE CONTRACTOR SHALL PROVIDE AS-BUILT DOCUMENTATION (RED-LINE OF PLAN SET) WHICH SHOWS EXACT, FINAL DIMENSIONS BETWEEN PULL BOXES AND OTHER POINTS OF CONDUIT TERMINATION.
2. CONTACT SHELBY COUNTY DEPARTMENT OF ROADS AND BRIDGES AT (901) 222-7742 AT LEAST 72 HOURS BEFORE BEGINNING ANY WORK ON THIS PROJECT.
3. SIGNAL EQUIPMENT AND INSTALLATION SHALL COMPLY WITH THE CITY OF MEMPHIS TRAFFIC SIGNAL SPECIFICATIONS.
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLING THE SIGNAL TIMING IN THE CONTROLLER. CONTACT THE ENGINEER TO OBTAIN TIMINGS.
5. ALL SALVAGEABLE ITEMS TO BE DELIVERED TO THE LOCAL JURISDICTION:

CITY OF MEMPHIS: 980 SOUTH THIRD STREET
CITY OF BARTLETT: 3585 ALTURIA ROAD
6. THE CONTRACTOR SHALL BRING THE NEW CONTROLLER UNITS AND THE SIGNAL TIMING SHEETS TO THE CITY OF MEMPHIS TRAFFIC SIGNAL MAINTENANCE OFFICE FOR REVIEW PRIOR TO INSTALLATION OF THE CONTROLLERS IN THE CABINET.
7. THE CONTRACTOR SHALL COIL 50' OF (EACH) FIBER OPTIC CABLE IN ALL FIBER OPTIC PULL BOXES.
8. CONTRACTOR SHALL HAVE SIGNAL MAINTENANCE RESPONSIBILITY OF THE INTERSECTION ONCE WORK ON EACH INTERSECTION HAS BEGUN. THE RESPONSIBILITY SHALL EXTEND TO CONTRACT ITEMS ONLY AND SHALL END UPON SUBSTANTIAL COMPLETION AND ACCEPTANCE OF THE WORK AT THE INTERSECTION.
9. THE CONTRACTOR SHALL NOT SPLICE ANY VIDEO DETECTION OR EVP EQUIPMENT CABLES.
10. THE CONTRACTOR SHALL INSTALL EVP EQUIPMENT THAT INCLUDES MULTI-MODE GPS/IR AT INTERSECTIONS IN CITY OF MEMPHIS.

APPLICABLE CITY OF MEMPHIS DESIGN STANDARDS
T-S-1

APPLICABLE T.D.O.T. STANDARD DRAWINGS
T-SG-2, T-SG-3, T-SG-5, T-SG-9A, T-WZ-50, T-FO-1,
T-FO-2, T-FO-3, T-FO-4

SPECIAL DETAILS WITHIN THIS PLAN SET SHALL SUPERSEDE THOSE FOUND ON THE LISTED STANDARD DRAWINGS.

GENERAL NOTES

UTILITIES

1. THE CONTRACTOR SHALL NOTIFY EACH INDIVIDUAL UTILITY OWNER OF THEIR PLAN OF OPERATION IN THE AREA OF THE UTILITIES. PRIOR TO COMMENCING WORK, THE CONTRACTOR SHALL CONTACT THE UTILITY OWNERS AND REQUEST THEM TO PROPERLY LOCATE THEIR RESPECTIVE UTILITY ON THE GROUND. THIS NOTIFICATION SHALL BE GIVEN AT LEAST THREE (3) BUSINESS DAYS PRIOR TO COMMENCEMENT OF OPERATIONS AROUND THE UTILITY.
2. IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE AND AVOID ALL UTILITIES AND UNDERGROUND STRUCTURES. THE CONTRACTOR SHOULD NOTE THAT EXISTING GAS LINES, WATER LINES, STORM DRAINAGE AND SANITARY SEWER STRUCTURES, AND OTHER UTILITIES MAY BE PRESENT.
3. EXISTING UTILITY LOCATIONS, AS SHOWN ON THESE PLANS, WERE COMPILED BASED ON INFORMATION AVAILABLE TO THE ENGINEER. UTILITY LOCATIONS SHOWN ARE APPROXIMATE AND ARE NOT INTENDED TO BE EXACT OR COMPLETE.
4. SOME UTILITIES CAN BE LOCATED BY CALLING THE TENNESSEE ONE CALL SYSTEM, INC. AT 1-800-351-1111. THE CONTRACTOR SHALL CALL THE TENNESSEE ONE CALL SYSTEM, INC. AT LEAST 72 HOURS, BUT NOT MORE THAN FIVE (5) DAYS PRIOR TO ANY PLANNED EXCAVATION BY THE CONTRACTOR.

PHASE DIAGRAM LEGEND

DISPLAYED VEHICULAR GREEN	
PROTECTED TURN	
PERMISSIVE TURN	
DISPLAYED WALK INDICATION	
NOTE: CLEARANCE INTERVALS ARE NOT SHOWN	

REVISIONS		
DATE	DESCRIPTIONS	APPROVED



Kimley»Horn

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
GENERAL NOTES

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: N.T.S.
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: _____ SHEET 2 OF 72

DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bld Set 5\Plans\BldSet 5-03-Quantities.dwg Layout1 Jan 30, 2015 3:25PM BY: bldme.lynch

CONGESTION MANAGEMENT PROGRAM (SIGNAL SYSTEM SET #5)			
ITEM NO.	DESCRIPTION	UNIT	QUANTITY
1	105-01 CONSTRUCTION STAKES, LINES AND GRADES	L.S.	1
	201-01 CLEARING AND GRUBBING	L.S.	1
2	209-05 SEDIMENT REMOVAL	C.Y.	10
	209-08.02 TEMPORARY SILT FENCE (WITH BACKING)	L.F.	300
3	209-09-43 CURB INLET PROTECTION (TYPE 4)	EACH	100
	701-01.01 CONCRETE SIDEWALK	S.F.	340
4	712-01 TRAFFIC CONTROL	L.S.	1
5	714-25.09 ELECTRICAL CONNECTION (FOR MLGW COST ONLY)	EACH	4
	716-02.05 PLASTIC PAVEMENT MARKING (STOPLINE)	L.F.	120
6	716-03.02 PLASTIC WORD PAVEMENT MARKING (RXR)	EACH	4
	717-01 MOBILIZATION	L.S.	1
7	725-02.79 FIBER SPLICE ENCLOSURE (WEATHER PROOF)	EACH	19
	725-03.09 ETHERNET SWITCH (TYPE A)	EACH	20
8	725-03.28 RAILROAD FLAGMAN	DAY	20
	725-21.22 TERMINAL SERVER (SERIAL DEVICE SERVER)	EACH	8
9	725-21.88 BLUETOOTH DETECTION SYSTEM	EACH	6
	725-21.91 RADAR DETECTION SYSTEM	EACH	6
10	725-21.96 RDS COMM CABLE	EACH	6
	725-24.01 CABINET (TYPE A)	EACH	4
11	725-24.04 CABINET (TYPE D)	EACH	2
	730-03.12 AERIAL SPLICE ENCLOSURE	EACH	2
12	730-03.21 INSTALL PULL BOX (TYPE B)	EACH	17
	730-03.23 INSTALL PULL BOX (FIBER OPTIC-TYPE A)	EACH	89
13	730-03.24 INSTALL PULL BOX (FIBER OPTIC-TYPE B)	EACH	20
	730-03.31 FIBER DISTRIBUTION BOX	EACH	19
14	730-05.01 ELECTRICAL SERVICE CONNECTION	EACH	10
	730-08.07 SIGNAL CABLE - 16 CONDUCTOR	L.F.	465
15	730-08.40 INTERCONNECT CABLE - FIBER OPTIC (36-FIBER, SINGLE MODE)	L.F.	76,000
	730-08.41 INTERCONNECT CABLE - FIBER OPTIC (DROP CABLE, 6-FIBER, SINGLE MODE)	L.F.	3,390
16	730-11.10 RISER ASSEMBLY (3" WEATHERHEAD)	EACH	13
	730-11.11 RISER ASSEMBLY (2")	EACH	1
17	730-11.12 RISER ASSEMBLY (3")	EACH	3
	730-12.02 CONDUIT 2" DIAMETER (PVC)	L.F.	1,700
18	730-12.03 CONDUIT 3" DIAMETER (PVC)	L.F.	532
	730-12.09 CONDUIT 3" DIAMETER (RGS)	L.F.	2,995
19	730-12.13 CONDUIT 2" DIAMETER (JACK AND BORE)	L.F.	43,625
	730-12.14 CONDUIT 3" DIAMETER (JACK AND BORE)	L.F.	13
20	730-12.42 CURB MARKERS (CURB MOUNTED CABLE MARKERS)	EACH	413
	730-13.02 VEHICLE DETECTOR (VIDEO)	EACH	16
21	730-13.03 VEHICLE DETECTOR (4-CHANNEL, RACK-MOUNT)	EACH	1
	730-13.06 VEHICLE DETECTOR (OPTICALLY ACTIVATED PRIORITY CONTROL)	EACH	15
22	730-14.01 SHIELDED DETECTOR CABLE	L.F.	795
	730-14.02 SAW SLOT	L.F.	130
23	730-14.03 LOOP WIRE	L.F.	365
	730-15.11 MODIFY CABINET (POLE-MOUNT ENTRANCE)	EACH	3
24	730-15.11 MODIFY CABINET (BASE-MOUNT ENTRANCE)	EACH	7
	730-15.32 CABINET (EIGHT PHASE BASE MOUNTED)	EACH	6
25	730-16.02 EIGHT PHASE ACTUATED CONTROLLER	EACH	3
	730-18.01 MASTER CONTROLLER	EACH	1
26	730-23.30 PEDESTAL POLE (ALUMINUM, 20' LENGTH)	EACH	6
	801-03 WATER (SEEDING & SODDING)	M.G.	3
27	803-01 SODDING (NEW SOD)	S.Y.	300
	920-16.07 RAILROAD PROTECTIVE INSURANCE	EACH	1

- FOOTNOTES
- 1

FOR TREE TRIMMING AS DIRECTED BY THE ENGINEER.
- 2

TO BE USED AS DIRECTED BY THE ENGINEER.
- 3

SEE SUBSECTION 209.07 OF THE TENNESSEE DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR MAINTENANCE REPLACEMENT.
- 4

TO INCLUDE ALL NECESSARY ITEMS TO PROVIDE TRAFFIC CONTROL IN ACCORDANCE WITH TDOT STANDARD DRAWINGS T-WZ-12, T-WZ-51, AND T-WZ-52.
- 5

ALLOWANCE TO COVER THE COST ASSOCIATED WITH POWER CONNECTION FOR THE TRAFFIC SIGNAL OR RDS UNIT FROM THE TRANSFORMER TO THE DEMARCATION POINT.
- 6

SEE THE LATEST "CITY OF MEMPHIS - STANDARD CONSTRUCTION SPECIFICATIONS" FOR TECHNICAL REQUIREMENTS.
- 7

SEE CITY OF MEMPHIS STANDARD SPECIFICATIONS FOR "RUGGEDIZED ETHERNET CABINET SWITCH."
- 8

SEE CITY OF MEMPHIS STANDARD SPECIFICATIONS FOR "SERIAL DEVICE SERVER."
- 9

THE INSTALLATION AT EACH LOCATION SHALL INCLUDE BLUETOOTH SENSOR, NEMA ENCLOSURE, CONDUIT AND RISER FROM CONTROLLER CABINET TO SIGNAL POLE, CELLULAR COMMUNICATION SYSTEM, POWER OVER ETHERNET SUBSYSTEM, ANTENNA, ETHERNET CABLE, AND ALL OTHER CABLING, CONNECTIONS AND HARWARE TO COMPLETE THE INSTALLATION OF A FULLY FUNCTIONAL BLUETOOTH DETECTION SYSTEM. THIS LUMP SUM ITEM ALSO INCLUDES THE BLUETOOTH SOFTWARE LICENSE FEE AND 24-MONTH BLUETOOTH CELLULAR SERVICE FEE FOR ALL INSTALLED UNITS. THE LUMP SUM PRICE INCLUDES ALL SOFTWARE AND HARDWARE INSTALLATION AND INTEGRATION WORK PROVIDE A FULLY FUNCTIONAL BLUETOOTH SYSTEM THAT ALLOWS THE CITY TO MONITOR AND RETRIEVE TRAVEL TIME AND SPEED DATA REMOTELY.
- 10

SEE PROJECT SPECIAL PROVISIONS FOR RADAR DETECTION EQUIPMENT.
- 11

SEE PROJECT SPECIAL PROVISIONS FOR UTILITY CABINETS. TYPE A CABINETS ARE FOR PRIMARY CABINETS. TYPE D CABINETS ARE FOR SECONDARY CABINETS. TYPE D CABINET TO INCLUDE ALL NECESSARY CABLING TO CONNECT TO TYPE A CABINET.
- 12

COST INCLUDES ALL LABOR AND MATERIALS (REMOVING AND REPLACING NECESSARY SIDE WALK PANELS, REPAIR LANDSCAPING, REMOVING EXISTING PULL BOX, AND OTHER MISCELLANEOUS MATERIALS) TO COMPLETE PULL BOX INSTALLATION.
- 13

CONTRACTOR RESPONSIBLE FOR ALL COST ASSOCIATED WITH POWER CONNECTION FOR TRAFFIC SIGNAL OR RDS UNIT FROM THE DEMARCATION POINT TO THE CABINET.
- 14

CONTRACTOR SHALL INSTALL A TRACER WIRE WITH THE FIBER OPTIC CABLE FOR ALL CONDUIT ROUTING. TRACER WIRE SHALL BE 10 AWG STRANDED COPPER CONDUCTOR CABLE WITH BOTH THHN AND THWN RATINGS AND YELLOW IN COLOR.
- 15

TO BE INSTALLED ON EXISTING SIGNAL POLE (SEE IL SHEETS AS NOTED ON LEGEND NOTE 24)
- 16

SEE CONSTRUCTION DETAIL SHEETS FOR BRIDGE ATTACHMENT DETAILS. ITEM TO INCLUDE ALL MATERIALS NESSESSARY TO ATTACH CONDUIT TO BRIDGE.
- 17

TO BE ITERIS VANTAGE SYSTEM OR APPROVED EQUIVALENT. INCLUDES DETECTION CAMERAS, PROCESSOR UNIT, CARD RACK, POWER SUPPLY UNIT, 10" COLOR LCD MONITOR, VIDEO REMOTE MANAGEMENT CARD, MOUSE AND ALL OTHER CABLING, CONNECTIONS AND HARDWARE TO COMPLETE THE INSTALLATION OF A FULLY FUNCTIONAL VIDEO DETECTION SYSTEM.
- 18

INSTALL ONE (1) DETECTOR CARD PER INTERSECTION APPROACH WHERE ADVANCE DETECTION LOOPS ARE TO BE REPAIRED OR REPLACED. SEE INTERSECTION LAYOUT SHEETS.
- 19

TO BE GTT OPTICOM SYSTEM OR APPROVED EQUIVALENT. INCLUDES OPTICAL DETECTORS, CONFIRMATION LAMPS (PAR 90), POLE-MOUNTED BEACONS, FOUR-CHANNEL PHASE SELECTOR, CARD RACK (OPTICOM 760) AND ALL CABLING, CONNECTIONS AND HARDWARE TO COMPLETE THE INSTALLATION OF A FULLY-FUNCTIONAL PREEMPTION SYSTEM, INCLUDING FIELD FINE-TUNING.
- 20

SEE INTERSECTION LAYOUT SHEET FOR CABINET MODIFICATION DETAILS.
- 21

THE CONTROLLER CABINET SHALL BE AN EIGHT PHASE CABINET SIZE P CABINET. CABINET SHALL INCLUDE 1 VEHICLE DETECTOR CARD (4-CHANNEL) IN ADDITION TO THE QUANTITIES OF ITEM NUMBER 730-13.02.
- 22

THE TRAFFIC SIGNAL CONTROLLER SHALL BE AN EAGLE EPAC M52 KEYBOARD UNIT OR APPROVED EQUIVALENT WITH BUILT-IN PORT 3 FIBER MODEM (SINGLE MODE), AND BUILT-IN STRETCH AND DELAY FEATURES FOR EACH PHASE. THE TRAFFIC CONTROLLER INSTALLATION ALONG WITH ALL AUXILIARY EQUIPMENT TO BE INSTALLED IN THE CABINET SHALL BE MANUFACTURED, SUPPLIED AND INSTALLED IN ACCORDANCE WITH THE LATEST CITY OF MEMPHIS TRAFFIC SIGNAL CONTROLLER AND CABINET SPECIFICATIONS. THE INSTALLATION SHALL HAVE A 12-CHANNEL MALFUNCTION MONITOR UNIT INSTALLED AS MODEL EDI SSM12LE-P.
- 23

INCLUDES CONCRETE FOUNDATION OR SCREW DOWN ANCHOR FOUNDATION AS APPROVED BY THE ENGINEER.
- 24

SEE TYPICAL COUNT ZONE DETAIL FOR ZONE LOCATION SETUP.

REVISIONS

DATE	DESCRIPTIONS	APPROVED





CABLE LAYOUT SHEET NO.	INTERSECTION/RDS ID	LOCATION																					PULLBOX/SPICE ENCLOSURE				RADAR DETECTION SYSTEM								
				CABINET			CONTROLLER		CABINET ENTRY				EMERGENCY VEHICLE PREEMPTION					VIDEO DETECTION					FIBER OPTIC EQUIPMENT												
				RETAIN EXISTING CABINET	INSTALL VEHICLE DETECTOR CARD (4-CHANNEL, RACK-MOUNT)	INSTALL NEW BASE MOUNTED CONTROLLER CABINET	REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER	INSTALL FIELD MASTER CONTROLLER	INSTALL 2" RISER INTO BOTTOM OF CABINET	INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET	INSTALL 3" CONDUIT INTO TOP OF CABINET	INSTALL 3" RISER INTO BOTTOM OF CABINET	INSTALL OPTICOM DETECTOR MODEL 711	INSTALL OPTICOM DETECTOR MODEL 722	INSTALL EVP PHASE SELECTOR MODEL 754 (4-CHANNEL)	INSTALL EVP CONFIRMATION LAMP	INSTALL EVP CONFIRMATION BEACON	VIDEO DETECTION CAMERA TYPE 2 MOUNT	VIDEO DETECTION CAMERA TYPE 3 MOUNT	VIDEO DETECTION CARD RACK	VIDEO DETECTION PROCESSOR (DUAL CHANNEL)	VIDEO REMOTE MANAGEMENT CARD	MONITOR AND MOUSE	INSTALL ETHERNET CABINET SWITCH	INSTALL SERIAL DEVICE SERVER	INSTALL FIBER DISTRIBUTION BOX IN LOCAL CONTROLLER CABINET	INSTALL PULLBOX (TYPE B)	INSTALL PULLBOX (F.O. TYPE B)	INSTALL WEATHERPROOF SPICE ENCLOSURE IN PULLBOX	INSTALL 3" RISER WITH WEATHER HEAD	INSTALL RADAR DETECTION SYSTEM	INSTALL 20' ALUMINUM PEDESTAL POLE	INSTALL NEW PRIMARY POLE MOUNTED RDS CABINET (TYPE A)	INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET (TYPE D)	MIGW POWER SERVICE CONNECTION
				B1	D10	B3	C4	C3	3	8	14	17	D1	D1	D8	D3	D2	D5	D6	-	D9	D14	-	C6	C7	B7	B9	B11	B6	13	D13	B13	D12	D15	B15
PLAN SHEET CALL-OUT SYMBOL		B1	D10	B3	C4	C3	3	8	14	17	D1	D1	D8	D3	D2	D5	D6	-	D9	D14	-	C6	C7	B7	B9	B11	B6	13	D13	B13	D12	D15	B15		
ITEM NUMBER		-	730-13.03	-	-	730-18.01	-	-	-	-	730-13.06	730-13.06	730-13.06	730-13.06	730-13.06	730-13.02	730-13.02	730-13.02	730-13.02	730-13.02	730-13.02	730-13.02	725-10.01	725-10.03	730-03.16	730-03.21	730-03.24	725-02.79	730-11.11	725-21.91	730-23.30	725-24.01	725-24.04	714-25.09	
UNIT		EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH		
CITY OF MEMPHIS																																			
CL-01	8157	JACKSON	TREZEVANT	1	-	-	1		-	-	-	-	1	1	3	2	3	-	1	1	1	1	1	-	1	-	1	-	1	-	-	-	-		
CL-01	8448	JACKSON	HOLLYWOOD	-	-	1	-		-	-	-	-	-	2	1	4	2	4	-	1	1	1	1	1	-	1	1	1	1	1	-	-	-	-	
CL-02	8445	JACKSON	MEAGHER	1	-	-	-		-	-	-	-	1	1	3	2	3	-	1	1	1	1	1	1	1	1	1	1	1	1	-	-	-	-	
CL-03	8443	JACKSON	WARFORD	-	-	1	-		-	-	-	1	1	1	3	2	1	2	1	1	1	1	1	-	1	1	1	1	1	1	1	-	-	-	
CL-03	RD1	JACKSON	BTWN WARFORD AND POPE	-	-	-	-		-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	-	-	-	1	1	1	1	-	2	2	1	1
CL-03	8442	JACKSON	POPE	-	1	1	-		-	-	-	-	1	1	3	2	4	-	1	1	1	1	1	-	1	5	1	1	1	1	-	-	-	-	
CL-04	8155	JACKSON	HUDSON	-	-	1	-		-	-	-	1	1	1	3	2	4	-	1	1	1	1	1	-	1	1	1	1	1	1	-	-	-	-	
CL-04	8440	JACKSON	MACON	1	-	-	-		-	2	-	-	-	-	-	3	-	1	1	1	1	1	1	1	1	1	1	1	1	1	-	-	-	-	
CL-05	RD2	JACKSON	BTWN MACON AND BAYLISS	-	-	-	-		-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	-	-	1	1	1	1	1	-	2	2	1	1
CL-06	8438	JACKSON	BAYLISS	-	-	1	-		-	-	-	-	2	1	4	2	4	-	1	1	1	1	1	-	1	1	1	1	1	1	-	-	-	-	
CL-07	8436	JACKSON	ORCHI	-	-	1	-		-	-	-	1	1	1	3	2	3	1	1	1	1	1	1	-	1	1	1	1	1	1	-	-	-	-	
CL-08	8435	JACKSON	WALES	1	-	-	1		-	1	1	-	-	2	1	4	2	4	-	1	1	1	1	1	-	1	1	1	1	1	1	-	-	-	-
			CITY OF BARTLETT																																
CL-09	5506	YALE	SYCAMORE VIEW	1	-	-	-		-	1	1	-	-	2	1	4	2	2	-	1	1	1	1	1	1	1	1	1	1	1	-	-	-	-	
CL-09	6100	YALE	BARTLETT	1	-	-	-		1	1	-	-	-	2	1	4	2	4	-	1	1	1	1	1	1	1	1	1	1	1	1	-	-	-	-
CL-09	RD3	YALE	BTWN BARTLETT AND ALTRURIA	-	-	-	-		-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	-	-	-	1	1	1	1	1	1	1	1	
CL-11	6103	YALE	ALTRURIA	1	-	-	-		-	1	1	-	1	-	1	4	2	4	-	1	1	1	1	1	1	1	1	1	1	1	1	-	-	-	-
CL-12	6106	YALE	KIRBY WHITTEN	1	-	-	1		-	1	1	-	-	2	1	4	2	4	-	1	1	1	1	1	1	1	1	1	1	1	1	-	-	-	-
CL-13	RD4	YALE	BTWN KIRBY WHITTEN AND U.S. 70	-	-	-	-		-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	-	-	-	1	1	1	1	-	1	1	1	
CL-14	5551	YALE	U.S. 70	1	-	-	-		-	1	1	-	-	2	1	4	2	4	-	1	1	1	1	1	1	1	1	1	1	1	1	-	-	-	-
CL-15	5548	YALE	BROTHER	1	-	-	-	1	-	1	1	-	1	1	3	2	3	-	1	1	1	1	1	1	-	1	1	1	1	1	1	-	-	-	-
TOTALS				10	1	6	3	1	1	9	6	3	8	21	15	53	30	54	3	16	16	16	16	20	8	13	17	20	19	3	6	6	4	2	4




REVISIONS

DATE	DESCRIPTIONS	APPROVED

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
TABULATED QUANTITIES

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: N.T.S.
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: _____ SHEET 4 OF 72

DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bld Set 5\Plans\BldSet 5-05-Plan Sheet Layout.dwg Layout1 Jan 30, 2015 3:25PM BY: blaine.lynch



REVISIONS		
DATE	DESCRIPTIONS	APPROVED






Kimley»Horn

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
CABLE LAYOUT AND UTILITY
SHEET KEY MAP

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: N.T.S.
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: _____ SHEET 5 OF 72

DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bld Set 5\Plans\BldSet 5-06-System Detectors.dwg Layout1 Jan 30, 2015 3:25PM BY: blaine.lynn



LEGEND


- 300 INTERSECTION ID.
- RD1 RADAR DETECTION SYSTEM

REVISIONS		
DATE	DESCRIPTIONS	APPROVED



Kimley»Horn

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
SYSTEM DETECTORS AND
INTERSECTION I.D.
SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: N.T.S.
DESIGNED: KHA DATE: 12/13 CHECKED: JEC DATE: 12/13
JURISDICTION: _____ SHEET 6 OF 72



* DENOTES CABLES AND SPLICE ENCLOSURES INSTALLED AS PART OF PROJECT 040723 (CMAQ YEAR 3 - BID SET 1)

** DENOTES CABLES AND SPLICE ENCLOSURES INSTALLED AS PART OF PROJECT 112875 (STP - JACKSON AVE SIGNAL SYSTEM)


REVISIONS		
DATE	DESCRIPTIONS	APPROVED



E1

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
**COMMUNICATIONS
CABLE SCHEMATIC**

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: N.T.S.
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: _____ SHEET 7 OF 72



NOTES

- THIS SCHEMATIC IS AN OVERVIEW OF THE BACKBONE NETWORK AND FIELD SUB-NETWORK TOPOLOGY. THE PURPOSE IS TO SHOW THE COMMUNICATION CHANNEL ASSIGNMENT AND THE UPSTREAM/DOWNSTREAM RELATIONSHIP OF THE LOCAL CONTROLLERS.
- ALL SPLICE ENCLOSURES AND DROP CABLES ARE NOT SHOWN. SEE COMMUNICATION CABLE SCHEMATIC SHEET FOR CABLE AND SPLICE ENCLOSURE DETAILS. SEE SPLICE DIAGRAMS (SHEET SD1-SD13) FOR SPLICING DETAILS AND FIBER STRANDS IN USE.
- EACH LINE SHOWN ON THIS SCHEMATIC REPRESENTS TWO STRANDS OF FIBERS (TRANSMIT AND RECEIVE).
- COMMUNICATION CHANNELS ARE NAMED BY THE FOLLOWING CONVENTION:

CHANNEL TYPE	FROM HUB ID	TO HUB ID	CHANNEL SEQUENCE
T			BACKBONE CHANNEL FOR HUB TO HUB COMMUNICATIONS
D			DISTRIBUTION CHANNEL FOR FIELD DEVICE COMMUNICATIONS

EXAMPLE:
T-GJ-1 BACKBONE CHANNEL #1 FROM HUB G TO J
D-JM-2 DISTRIBUTION CHANNEL #2 FROM HUB J TO M

HUB ID:
CH - CITY HALL
LC - LOCAL CONTROLLER

REVISIONS		
DATE	DESCRIPTIONS	APPROVED




Kimley»Horn



CC1

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.

COMMUNICATION
CHANNEL SCHEMATIC

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: N.T.S.
DESIGNED: KHA DATE: 12/13 CHECKED: JEC DATE: 12/13
JURISDICTION: _____ SHEET 8 OF 72






MATCH LINE STA. 12+50 SEE THIS SHEET


MATCH LINE STA. 25+00 SEE DWG. NO. CL-02

△ NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.

- B1 RETAIN AND MODIFY EXISTING CABINET
- B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
- B7 INSTALL FIBER DISTRIBUTION BOX
- B9 INSTALL TRAFFIC SIGNAL PULLBOX
- B10 INSTALL FIBER OPTIC PULLBOX TYPE A
- B11 INSTALL FIBER OPTIC PULLBOX TYPE B
- B13 INSTALL 20' PEDESTAL POLE
- B15 MLGW POWER SERVICE CONNECTION
- C2 INSTALL 8-PHASE CONTROLLER
- C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5 INSTALL FIBER OPTIC MODEM
- C6 INSTALL ETHERNET CABINET SWITCH
- C7 INSTALL SERIAL DEVICE SERVER
- D1 INSTALL EVP DETECTOR
- D2 INSTALL EVP CONFIRMATION BEACON
- D3 INSTALL EVP CONFIRMATION LAMP
- D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8 INSTALL EVP PHASE SELECTOR
- D9 INSTALL VIDEO DETECTION PROCESSOR
- D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12 INSTALL NEW POLE MOUNTED RDS CABINET
- D13 INSTALL RADAR DETECTION SYSTEM
- D14 VIDEO REMOTE MANAGEMENT CARD
- D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- W1 EVP DETECTOR CABLE(S)
- W2 EVP CONFIRMATION BEACON POWER CABLE(S)
- W3 EVP CONFIRMATION LAMP POWER CABLE(S)
- W4 VIDEO DETECTOR CABLE(S)
- W5 2C DETECTOR CABLE(S)
- W6 SMFO CABLE
- W7 SMFO TRUNK CABLE
- W9 DROP CABLES (8-FIBER)
- W11 RDS CABLE
- W12 RDS POWER CABLE
- W13 ETHERNET DATA CABLE
- 3 INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4 INSTALL 2" RISER WITH WEATHERHEAD
- 5 INSTALL 2" RISER WITH SEALING BUSHING
- 6 INSTALL 2" CONDUIT ENTRANCE INTO EXISTING FOUNDATION
- 7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9 INSTALL 2" PVC CONDUIT
- 10 JACK AND BORE 2" CONDUIT
- 11 INSTALL 3" PVC CONDUIT
- 13 INSTALL 3" RISER WITH WEATHERHEAD
- 14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 17 REUSE EXISTING RISER WITH SEALING BUSHING
- 18 TIE CONDUIT INTO EXISTING PULLBOX
- 19 REUSE EXISTING CONDUIT
- 20 REUSE EXISTING RISER WITH WEATHERHEAD
- 21 ATTACH CONDUIT TO EXISTING CONDUIT STUB-OUT
- 23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25 INSTALL CABLES IN EXISTING WEATHERHEAD
- 26 INSTALL CABLES IN EXISTING POLE
- 27 INSTALL CABLES IN PROPOSED POLE
- 29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32 ATTACH CONDUIT TO BRIDGE



REVISIONS		
DATE	DESCRIPTIONS	APPROVED





POWERS HILL DESIGN
CIVIL ENGINEERING, CIVIL RESPONSIBILITY.

Kimley-Horn and Associates, Inc.

CL-01


DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVENUE
CABLE LAYOUT
FROM 0+00 TO 25+00

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: _____ SHEET 10 OF 72




- B1 RETAIN AND MODIFY EXISTING CABINET
- B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
- B7 INSTALL FIBER DISTRIBUTION BOX
- B9 INSTALL TRAFFIC SIGNAL PULLBOX
- B10 INSTALL FIBER OPTIC PULLBOX TYPE A
- B11 INSTALL FIBER OPTIC PULLBOX TYPE B
- B13 INSTALL 20' PEDESTAL POLE
- B15 MLGW POWER SERVICE CONNECTION
- C2 INSTALL 8-PHASE CONTROLLER
- C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5 INSTALL FIBER OPTIC MODEM
- C6 INSTALL ETHERNET CABINET SWITCH
- C7 INSTALL SERIAL DEVICE SERVER
- D1 INSTALL EVP DETECTOR
- D2 INSTALL EVP CONFIRMATION BEACON
- D3 INSTALL EVP CONFIRMATION LAMP
- D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8 INSTALL EVP PHASE SELECTOR
- D9 INSTALL VIDEO DETECTION PROCESSOR
- D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12 INSTALL NEW POLE MOUNTED RDS CABINET
- D13 INSTALL RADAR DETECTION SYSTEM
- D14 VIDEO REMOTE MANAGEMENT CARD
- D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- W1 EVP DETECTOR CABLE(S)
- W2 EVP CONFIRMATION BEACON POWER CABLE(S)
- W3 EVP CONFIRMATION LAMP POWER CABLE(S)
- W4 VIDEO DETECTOR CABLE(S)
- W5 2C DETECTOR CABLE(S)
- W6 SMFO CABLE
- W7 SMFO TRUNK CABLE
- W9 DROP CABLES (8-FIBER)
- W11 RDS CABLE
- W12 RDS POWER CABLE
- W13 ETHERNET DATA CABLE
- 3 INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4 INSTALL 2" RISER WITH WEATHERHEAD
- 5 INSTALL 2" RISER WITH SEALING BUSHING
- 6 INSTALL 2" CONDUIT ENTRANCE INTO EXISTING FOUNDATION
- 7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9 INSTALL 2" PVC CONDUIT
- 10 JACK AND BORE 2" CONDUIT
- 11 INSTALL 3" PVC CONDUIT
- 13 INSTALL 3" RISER WITH WEATHERHEAD
- 14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 17 REUSE EXISTING RISER WITH SEALING BUSHING
- 18 TIE CONDUIT INTO EXISTING PULLBOX
- 19 REUSE EXISTING CONDUIT
- 20 REUSE EXISTING RISER WITH WEATHERHEAD
- 21 ATTACH CONDUIT TO EXISTING CONDUIT STUB-OUT
- 23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25 INSTALL CABLES IN EXISTING WEATHERHEAD
- 26 INSTALL CABLES IN EXISTING POLE
- 27 INSTALL CABLES IN PROPOSED POLE
- 29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32 ATTACH CONDUIT TO BRIDGE

△ NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.





REVISIONS		
DATE	DESCRIPTIONS	APPROVED




CL-02

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVENUE
CABLE LAYOUT
FROM 25+00 TO 50+00


SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: _____ SHEET 11 OF 72



△ NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.



REVISIONS		
DATE	DESCRIPTIONS	APPROVED





POWERS HILL DESIGN
CIVIL ENGINEERING, CIVIL RESPONSIBILITY.

Kimley-Horn and Associates, Inc.

CL-03


DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVENUE
CABLE LAYOUT
FROM 50+00 TO 75+00

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: SHEET 12 OF 72



△ NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.

- B1 RETAIN AND MODIFY EXISTING CABINET
- B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
- B7 INSTALL FIBER DISTRIBUTION BOX
- B9 INSTALL TRAFFIC SIGNAL PULLBOX
- B10 INSTALL FIBER OPTIC PULLBOX TYPE A
- B11 INSTALL FIBER OPTIC PULLBOX TYPE B
- B13 INSTALL 20' PEDESTAL POLE
- B15 MLGW POWER SERVICE CONNECTION
- C2 INSTALL 8-PHASE CONTROLLER
- C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5 INSTALL FIBER OPTIC MODEM
- C6 INSTALL ETHERNET CABINET SWITCH
- C7 INSTALL SERIAL DEVICE SERVER
- D1 INSTALL EVP DETECTOR
- D2 INSTALL EVP CONFIRMATION BEACON
- D3 INSTALL EVP CONFIRMATION LAMP
- D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8 INSTALL EVP PHASE SELECTOR
- D9 INSTALL VIDEO DETECTION PROCESSOR
- D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12 INSTALL NEW POLE MOUNTED RDS CABINET
- D13 INSTALL RADAR DETECTION SYSTEM
- D14 VIDEO REMOTE MANAGEMENT CARD
- D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- W1 EVP DETECTOR CABLE(S)
- W2 EVP CONFIRMATION BEACON POWER CABLE(S)
- W3 EVP CONFIRMATION LAMP POWER CABLE(S)
- W4 VIDEO DETECTOR CABLE(S)
- W5 2C DETECTOR CABLE(S)
- W6 SMFO CABLE
- W7 SMFO TRUNK CABLE
- W9 DROP CABLES (8-FIBER)
- W11 RDS CABLE
- W12 RDS POWER CABLE
- W13 ETHERNET DATA CABLE
- 3 INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4 INSTALL 2" RISER WITH WEATHERHEAD
- 5 INSTALL 2" RISER WITH SEALING BUSHING
- 6 INSTALL 2" CONDUIT ENTRANCE INTO EXISTING FOUNDATION
- 7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9 INSTALL 2" PVC CONDUIT
- 10 JACK AND BORE 2" CONDUIT
- 11 INSTALL 3" PVC CONDUIT
- 13 INSTALL 3" RISER WITH WEATHERHEAD
- 14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 17 REUSE EXISTING RISER WITH SEALING BUSHING
- 18 TIE CONDUIT INTO EXISTING PULLBOX
- 19 REUSE EXISTING CONDUIT
- 20 REUSE EXISTING RISER WITH WEATHERHEAD
- 21 ATTACH CONDUIT TO EXISTING CONDUIT STUB-OUT
- 23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25 INSTALL CABLES IN EXISTING WEATHERHEAD
- 26 INSTALL CABLES IN EXISTING POLE
- 27 INSTALL CABLES IN PROPOSED POLE
- 29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32 ATTACH CONDUIT TO BRIDGE



REVISIONS		
DATE	DESCRIPTIONS	APPROVED





POWERS HILL DESIGN
CIVIL ENGINEERING. CIVIL RESPONSIBILITY.

Kimley-Horn and Associates, Inc.


CL-04

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVENUE
CABLE LAYOUT
FROM 75+00 TO 100+00

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: _____ SHEET 13 OF 72



△ NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.



- B1 RETAIN AND MODIFY EXISTING CABINET
- B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
- B7 INSTALL FIBER DISTRIBUTION BOX
- B9 INSTALL TRAFFIC SIGNAL PULLBOX
- B10 INSTALL FIBER OPTIC PULLBOX TYPE A
- B11 INSTALL FIBER OPTIC PULLBOX TYPE B
- B13 INSTALL 20' PEDESTAL POLE
- B15 MLGW POWER SERVICE CONNECTION
- C2 INSTALL 8-PHASE CONTROLLER
- C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5 INSTALL FIBER OPTIC MODEM
- C6 INSTALL ETHERNET CABINET SWITCH
- C7 INSTALL SERIAL DEVICE SERVER
- D1 INSTALL EVP DETECTOR
- D2 INSTALL EVP CONFIRMATION BEACON
- D3 INSTALL EVP CONFIRMATION LAMP
- D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8 INSTALL EVP PHASE SELECTOR
- D9 INSTALL VIDEO DETECTION PROCESSOR
- D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12 INSTALL NEW POLE MOUNTED RDS CABINET
- D13 INSTALL RADAR DETECTION SYSTEM
- D14 VIDEO REMOTE MANAGEMENT CARD
- D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- W1 EVP DETECTOR CABLE(S)
- W2 EVP CONFIRMATION BEACON POWER CABLE(S)
- W3 EVP CONFIRMATION LAMP POWER CABLE(S)
- W4 VIDEO DETECTOR CABLE(S)
- W5 2C DETECTOR CABLE(S)
- W6 SMFO CABLE
- W7 SMFO TRUNK CABLE
- W9 DROP CABLES (8-FIBER)
- W11 RDS CABLE
- W12 RDS POWER CABLE
- W13 ETHERNET DATA CABLE
- 3 INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4 INSTALL 2" RISER WITH WEATHERHEAD
- 5 INSTALL 2" RISER WITH SEALING BUSHING
- 6 INSTALL 2" CONDUIT ENTRANCE INTO EXISTING FOUNDATION
- 7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9 INSTALL 2" PVC CONDUIT
- 10 JACK AND BORE 2" CONDUIT
- 11 INSTALL 3" PVC CONDUIT
- 13 INSTALL 3" RISER WITH WEATHERHEAD
- 14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 17 REUSE EXISTING RISER WITH SEALING BUSHING
- 18 TIE CONDUIT INTO EXISTING PULLBOX
- 19 REUSE EXISTING CONDUIT
- 20 REUSE EXISTING RISER WITH WEATHERHEAD
- 21 ATTACH CONDUIT TO EXISTING CONDUIT STUB-OUT
- 23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25 INSTALL CABLES IN EXISTING WEATHERHEAD
- 26 INSTALL CABLES IN EXISTING POLE
- 27 INSTALL CABLES IN PROPOSED POLE
- 29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32 ATTACH CONDUIT TO BRIDGE

REVISIONS		
DATE	DESCRIPTIONS	APPROVED



Powers Hill Design
CIVIL ENGINEERING. CIVIL RESPONSIBILITY.

Kimley-Horn and Associates, Inc.


CL-05

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVENUE
CABLE LAYOUT
FROM 100+00 TO 125+00

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: _____ SHEET 14 OF 72



△ NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.



REVISIONS		
DATE	DESCRIPTIONS	APPROVED



- B1 RETAIN AND MODIFY EXISTING CABINET
- B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
- B7 INSTALL FIBER DISTRIBUTION BOX
- B9 INSTALL TRAFFIC SIGNAL PULLBOX
- B10 INSTALL FIBER OPTIC PULLBOX TYPE A
- B11 INSTALL FIBER OPTIC PULLBOX TYPE B
- B13 INSTALL 20' PEDESTAL POLE
- B15 MLGW POWER SERVICE CONNECTION
- C2 INSTALL 8-PHASE CONTROLLER
- C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5 INSTALL FIBER OPTIC MODEM
- C6 INSTALL ETHERNET CABINET SWITCH
- C7 INSTALL SERIAL DEVICE SERVER
- D1 INSTALL EVP DETECTOR
- D2 INSTALL EVP CONFIRMATION BEACON
- D3 INSTALL EVP CONFIRMATION LAMP
- D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8 INSTALL EVP PHASE SELECTOR
- D9 INSTALL VIDEO DETECTION PROCESSOR
- D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12 INSTALL NEW POLE MOUNTED RDS CABINET
- D13 INSTALL RADAR DETECTION SYSTEM
- D14 VIDEO REMOTE MANAGEMENT CARD
- D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- W1 EVP DETECTOR CABLE(S)
- W2 EVP CONFIRMATION BEACON POWER CABLE(S)
- W3 EVP CONFIRMATION LAMP POWER CABLE(S)
- W4 VIDEO DETECTOR CABLE(S)
- W5 2C DETECTOR CABLE(S)
- W6 SMFO CABLE
- W7 SMFO TRUNK CABLE
- W9 DROP CABLES (8-FIBER)
- W11 RDS CABLE
- W12 RDS POWER CABLE
- W13 ETHERNET DATA CABLE
- 3 INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4 INSTALL 2" RISER WITH WEATHERHEAD
- 5 INSTALL 2" RISER WITH SEALING BUSHING
- 6 INSTALL 2" CONDUIT ENTRANCE INTO EXISTING FOUNDATION
- 7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9 INSTALL 2" PVC CONDUIT
- 10 JACK AND BORE 2" CONDUIT
- 11 INSTALL 3" PVC CONDUIT
- 13 INSTALL 3" RISER WITH WEATHERHEAD
- 14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 17 REUSE EXISTING RISER WITH SEALING BUSHING
- 18 TIE CONDUIT INTO EXISTING PULLBOX
- 19 REUSE EXISTING CONDUIT
- 20 REUSE EXISTING RISER WITH WEATHERHEAD
- 21 ATTACH CONDUIT TO EXISTING CONDUIT STUB-OUT
- 23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25 INSTALL CABLES IN EXISTING WEATHERHEAD
- 26 INSTALL CABLES IN EXISTING POLE
- 27 INSTALL CABLES IN PROPOSED POLE
- 29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32 ATTACH CONDUIT TO BRIDGE

CL-06

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVENUE
CABLE LAYOUT
FROM 125+00 TO 150+00


SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: SHEET 15 OF 72

MATCH LINE STA. 150+00 SEE DWG. NO. CL-06

MATCH LINE STA. 162+50 SEE THIS SHEET

MATCH LINE STA. 162+50 SEE THIS SHEET

MATCH LINE STA. 175+00 SEE DWG. NO. CL-08



REVISIONS		
DATE	DESCRIPTIONS	APPROVED

POWERS HILL DESIGN
CIVIL ENGINEERING, CIVIL RESPONSIBILITY.

**Kimley-Horn
and Associates, Inc.**



CL-07


DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVENUE
CABLE LAYOUT
FROM 150+00 TO 175+00

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: SHEET 16 OF 72

- B1 RETAIN AND MODIFY EXISTING CABINET
- B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
- B7 INSTALL FIBER DISTRIBUTION BOX
- B9 INSTALL TRAFFIC SIGNAL PULLBOX
- B10 INSTALL FIBER OPTIC PULLBOX TYPE A
- B11 INSTALL FIBER OPTIC PULLBOX TYPE B
- B13 INSTALL 20' PEDESTAL POLE
- B15 MLGW POWER SERVICE CONNECTION
- C2 INSTALL 8-PHASE CONTROLLER
- C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5 INSTALL FIBER OPTIC MODEM
- C6 INSTALL ETHERNET CABINET SWITCH
- C7 INSTALL SERIAL DEVICE SERVER
- D1 INSTALL EVP DETECTOR
- D2 INSTALL EVP CONFIRMATION BEACON
- D3 INSTALL EVP CONFIRMATION LAMP
- D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8 INSTALL EVP PHASE SELECTOR
- D9 INSTALL VIDEO DETECTION PROCESSOR
- D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12 INSTALL NEW POLE MOUNTED RDS CABINET
- D13 INSTALL RADAR DETECTION SYSTEM
- D14 VIDEO REMOTE MANAGEMENT CARD
- D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- W1 EVP DETECTOR CABLE(S)
- W2 EVP CONFIRMATION BEACON POWER CABLE(S)
- W3 EVP CONFIRMATION LAMP POWER CABLE(S)
- W4 VIDEO DETECTOR CABLE(S)
- W5 2C DETECTOR CABLE(S)
- W6 SMFO CABLE
- W7 SMFO TRUNK CABLE
- W9 DROP CABLES (6-FIBER)
- W11 RDS CABLE
- W12 RDS POWER CABLE
- W13 ETHERNET DATA CABLE
- 3 INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4 INSTALL 2" RISER WITH WEATHERHEAD
- 5 INSTALL 2" RISER WITH SEALING BUSHING
- 6 INSTALL 2" CONDUIT ENTRANCE INTO EXISTING FOUNDATION
- 7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9 INSTALL 2" PVC CONDUIT
- 10 JACK AND BORE 2" CONDUIT
- 11 INSTALL 3" PVC CONDUIT
- 13 INSTALL 3" RISER WITH WEATHERHEAD
- 14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 17 REUSE EXISTING RISER WITH SEALING BUSHING
- 18 TIE CONDUIT INTO EXISTING PULLBOX
- 19 REUSE EXISTING CONDUIT
- 20 REUSE EXISTING RISER WITH WEATHERHEAD
- 21 ATTACH CONDUIT TO EXISTING CONDUIT STUB-OUT
- 23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25 INSTALL CABLES IN EXISTING WEATHERHEAD
- 26 INSTALL CABLES IN EXISTING POLE
- 27 INSTALL CABLES IN PROPOSED POLE
- 29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32 ATTACH CONDUIT TO BRIDGE


- △ NUMBER OF CABLES, LOOPS, ETC.
- ✕ NUMBER OF CONDUCTORS, PAIRS, ETC.

MATCH LINE STA. 175+00 SEE DWG. NO. CL-07



MATCH LINE STA. 187+50 SEE THIS SHEET


MATCH LINE STA. 187+50 SEE THIS SHEET



SEE DWG. NO. IL-10
FOR INTERSECTION DETAILS

CONDUIT AND FIBER TO BE
INSTALLED AS PART OF A
FUTURE PROJECT

△ NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.



REVISIONS		
DATE	DESCRIPTIONS	APPROVED



POWERS HILL DESIGN
CIVIL ENGINEERING. CIVIL RESPONSIBILITY.

Kimley-Horn and Associates, Inc.

- B1

RETAIN AND MODIFY EXISTING CABINET
- B3

INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6

INSTALL WEATHER PROOF SPLICE ENCLOSURE
- B7

INSTALL FIBER DISTRIBUTION BOX
- B9

INSTALL TRAFFIC SIGNAL PULLBOX
- B10

INSTALL FIBER OPTIC PULLBOX TYPE A
- B11

INSTALL FIBER OPTIC PULLBOX TYPE B
- B13

INSTALL 20' PEDESTAL POLE
- B15

MLGW POWER SERVICE CONNECTION
- C2

INSTALL 8-PHASE CONTROLLER
- C4

REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5

INSTALL FIBER OPTIC MODEM
- C6

INSTALL ETHERNET CABINET SWITCH
- C7

INSTALL SERIAL DEVICE SERVER
- D1

INSTALL EVP DETECTOR
- D2

INSTALL EVP CONFIRMATION BEACON
- D3

INSTALL EVP CONFIRMATION LAMP
- D4

INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5

INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6

INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8

INSTALL EVP PHASE SELECTOR
- D9

INSTALL VIDEO DETECTION PROCESSOR
- D10

INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11

REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12

INSTALL NEW POLE MOUNTED RDS CABINET
- D13

INSTALL RADAR DETECTION SYSTEM
- D14

VIDEO REMOTE MANAGEMENT CARD
- D15

INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- W1

EVP DETECTOR CABLE(S)
- W2

EVP CONFIRMATION BEACON POWER CABLE(S)
- W3

EVP CONFIRMATION LAMP POWER CABLE(S)
- W4

VIDEO DETECTOR CABLE(S)
- W5

2C DETECTOR CABLE(S)
- W6

SMFO CABLE
- W7

SMFO TRUNK CABLE
- W9

DROP CABLES (8-FIBER)
- W11

RDS CABLE
- W12

RDS POWER CABLE
- W13

ETHERNET DATA CABLE
- 3

INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4

INSTALL 2" RISER WITH WEATHERHEAD
- 5

INSTALL 2" RISER WITH SEALING BUSHING
- 6

INSTALL 2" CONDUIT ENTRANCE INTO EXISTING FOUNDATION
- 7

INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8

INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9

INSTALL 2" PVC CONDUIT
- 10

JACK AND BORE 2" CONDUIT
- 11

INSTALL 3" PVC CONDUIT
- 13

INSTALL 3" RISER WITH WEATHERHEAD
- 14

INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 17

REUSE EXISTING RISER WITH SEALING BUSHING
- 18

TIE CONDUIT INTO EXISTING PULLBOX
- 19

REUSE EXISTING CONDUIT
- 20

REUSE EXISTING RISER WITH WEATHERHEAD
- 21

ATTACH CONDUIT TO EXISTING CONDUIT STUB-OUT
- 23

INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24

INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25

INSTALL CABLES IN EXISTING WEATHERHEAD
- 26

INSTALL CABLES IN EXISTING POLE
- 27

INSTALL CABLES IN PROPOSED POLE
- 29

INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30

LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32

ATTACH CONDUIT TO BRIDGE

CL-08

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVENUE
CABLE LAYOUT
FROM 175+00 TO 192+72

SURVEY: N/A

DATE: N/A

BOOK: N/A

DRAFTED: APL

DATE: 01/14

SCALE: 1"=50'

DESIGNED: SH



DATE: 01/14

CHECKED: SH

DATE: 01/14


JURISDICTION: _____

SHEET 17 OF 72




△ NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.

- B1 RETAIN AND MODIFY EXISTING CABINET
- B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
- B7 INSTALL FIBER DISTRIBUTION BOX
- B9 INSTALL TRAFFIC SIGNAL PULLBOX
- B10 INSTALL FIBER OPTIC PULLBOX TYPE A
- B11 INSTALL FIBER OPTIC PULLBOX TYPE B
- B13 INSTALL 20' PEDESTAL POLE
- B15 MLGW POWER SERVICE CONNECTION
- C2 INSTALL 8-PHASE CONTROLLER
- C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5 INSTALL FIBER OPTIC MODEM
- C6 INSTALL ETHERNET CABINET SWITCH
- C7 INSTALL SERIAL DEVICE SERVER
- D1 INSTALL EVP DETECTOR
- D2 INSTALL EVP CONFIRMATION BEACON
- D3 INSTALL EVP CONFIRMATION LAMP
- D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8 INSTALL EVP PHASE SELECTOR
- D9 INSTALL VIDEO DETECTION PROCESSOR
- D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12 INSTALL NEW POLE MOUNTED RDS CABINET
- D13 INSTALL RADAR DETECTION SYSTEM
- D14 VIDEO REMOTE MANAGEMENT CARD
- D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- W1 EVP DETECTOR CABLE(S)
- W2 EVP CONFIRMATION BEACON POWER CABLE(S)
- W3 EVP CONFIRMATION LAMP POWER CABLE(S)
- W4 VIDEO DETECTOR CABLE(S)
- W5 2C DETECTOR CABLE(S)
- W6 SMFO CABLE
- W7 SMFO TRUNK CABLE
- W9 DROP CABLES (6-FIBER)
- W11 RDS CABLE
- W12 RDS POWER CABLE
- W13 ETHERNET DATA CABLE
- 3 INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4 INSTALL 2" RISER WITH WEATHERHEAD
- 5 INSTALL 2" RISER WITH SEALING BUSHING
- 6 INSTALL 2" CONDUIT ENTRANCE INTO EXISTING FOUNDATION
- 7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9 INSTALL 2" PVC CONDUIT
- 10 JACK AND BORE 2" CONDUIT
- 11 INSTALL 3" PVC CONDUIT
- 13 INSTALL 3" RISER WITH WEATHERHEAD
- 14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 17 REUSE EXISTING RISER WITH SEALING BUSHING
- 18 TIE CONDUIT INTO EXISTING PULLBOX
- 19 REUSE EXISTING CONDUIT
- 20 REUSE EXISTING RISER WITH WEATHERHEAD
- 21 ATTACH CONDUIT TO EXISTING CONDUIT STUB-OUT
- 23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25 INSTALL CABLES IN EXISTING WEATHERHEAD
- 26 INSTALL CABLES IN EXISTING POLE
- 27 INSTALL CABLES IN PROPOSED POLE
- 29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32 ATTACH CONDUIT TO BRIDGE





REVISIONS		
DATE	DESCRIPTIONS	APPROVED



CL-09


DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
YALE ROAD
CABLE LAYOUT
FROM 8+00 TO 32+50

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: SHEET 18 OF 72




- B1 RETAIN AND MODIFY EXISTING CABINET
- B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
- B7 INSTALL FIBER DISTRIBUTION BOX
- B9 INSTALL TRAFFIC SIGNAL PULLBOX
- B10 INSTALL FIBER OPTIC PULLBOX TYPE A
- B11 INSTALL FIBER OPTIC PULLBOX TYPE B
- B13 INSTALL 20' PEDESTAL POLE
- B15 MLGW POWER SERVICE CONNECTION
- C2 INSTALL 8-PHASE CONTROLLER
- C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5 INSTALL FIBER OPTIC MODEM
- C6 INSTALL ETHERNET CABINET SWITCH
- C7 INSTALL SERIAL DEVICE SERVER
- D1 INSTALL EVP DETECTOR
- D2 INSTALL EVP CONFIRMATION BEACON
- D3 INSTALL EVP CONFIRMATION LAMP
- D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8 INSTALL EVP PHASE SELECTOR
- D9 INSTALL VIDEO DETECTION PROCESSOR
- D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12 INSTALL NEW POLE MOUNTED RDS CABINET
- D13 INSTALL RADAR DETECTION SYSTEM
- D14 VIDEO REMOTE MANAGEMENT CARD
- D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- W1 EVP DETECTOR CABLE(S)
- W2 EVP CONFIRMATION BEACON POWER CABLE(S)
- W3 EVP CONFIRMATION LAMP POWER CABLE(S)
- W4 VIDEO DETECTOR CABLE(S)
- W5 2C DETECTOR CABLE(S)
- W6 SMFO CABLE
- W7 SMFO TRUNK CABLE
- W9 DROP CABLES (6-FIBER)
- W11 RDS CABLE
- W12 RDS POWER CABLE
- W13 ETHERNET DATA CABLE
- 3 INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4 INSTALL 2" RISER WITH WEATHERHEAD
- 5 INSTALL 2" RISER WITH SEALING BUSHING
- 6 INSTALL 2" CONDUIT ENTRANCE INTO EXISTING FOUNDATION
- 7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9 INSTALL 2" PVC CONDUIT
- 10 JACK AND BORE 2" CONDUIT
- 11 INSTALL 3" PVC CONDUIT
- 13 INSTALL 3" RISER WITH WEATHERHEAD
- 14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 17 REUSE EXISTING RISER WITH SEALING BUSHING
- 18 TIE CONDUIT INTO EXISTING PULLBOX
- 19 REUSE EXISTING CONDUIT
- 20 REUSE EXISTING RISER WITH WEATHERHEAD
- 21 ATTACH CONDUIT TO EXISTING CONDUIT STUB-OUT
- 23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25 INSTALL CABLES IN EXISTING WEATHERHEAD
- 26 INSTALL CABLES IN EXISTING POLE
- 27 INSTALL CABLES IN PROPOSED POLE
- 29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32 ATTACH CONDUIT TO BRIDGE

△ NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.



REVISIONS		
DATE	DESCRIPTIONS	APPROVED



CL-10

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
YALE ROAD
CABLE LAYOUT
FROM 32+50 TO 57+50

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: _____ SHEET 19 OF 72


MATCH LINE STA. 57+50 SEE DWG. NO. CL-10

MATCH LINE STA. 70+00 SEE THIS SHEET


MATCH LINE STA. 70+00 SEE THIS SHEET

MATCH LINE STA. 82+50 SEE DWG. CL-12

SEE DWG. NO. IL-13
FOR INTERSECTION
DETAILS



REVISIONS		
DATE	DESCRIPTIONS	APPROVED



**Kimley-Horn
and Associates, Inc.**



- | | |
|-----|--|
| B1 | RETAIN AND MODIFY EXISTING CABINET |
| B3 | INSTALL NEW BASE MOUNTED CONTROLLER CABINET |
| B6 | INSTALL WEATHER PROOF SPLICE ENCLOSURE |
| B7 | INSTALL FIBER DISTRIBUTION BOX |
| B9 | INSTALL TRAFFIC SIGNAL PULLBOX |
| B10 | INSTALL FIBER OPTIC PULLBOX TYPE A |
| B11 | INSTALL FIBER OPTIC PULLBOX TYPE B |
| B13 | INSTALL 20' PEDESTAL POLE |
| B15 | MLGW POWER SERVICE CONNECTION |
| C2 | INSTALL 8-PHASE CONTROLLER |
| C4 | REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER |
| C5 | INSTALL FIBER OPTIC MODEM |
| C6 | INSTALL ETHERNET CABINET SWITCH |
| C7 | INSTALL SERIAL DEVICE SERVER |
| D1 | INSTALL EVP DETECTOR |
| D2 | INSTALL EVP CONFIRMATION BEACON |
| D3 | INSTALL EVP CONFIRMATION LAMP |
| D4 | INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT |
| D5 | INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT |
| D6 | INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT |
| D8 | INSTALL EVP PHASE SELECTOR |
| D9 | INSTALL VIDEO DETECTION PROCESSOR |
| D10 | INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET |
| D11 | REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM) |
| D12 | INSTALL NEW POLE MOUNTED RDS CABINET |
| D13 | INSTALL RADAR DETECTION SYSTEM |
| D14 | VIDEO REMOTE MANAGEMENT CARD |
| D15 | INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET |
| W1 | EVP DETECTOR CABLE(S) |
| W2 | EVP CONFIRMATION BEACON POWER CABLE(S) |
| W3 | EVP CONFIRMATION LAMP POWER CABLE(S) |
| W4 | VIDEO DETECTOR CABLE(S) |
| W5 | 2C DETECTOR CABLE(S) |
| W6 | SMFO CABLE |
| W7 | SMFO TRUNK CABLE |
| W9 | DROP CABLES (6-FIBER) |
| W11 | RDS CABLE |
| W12 | RDS POWER CABLE |
| W13 | ETHERNET DATA CABLE |
| 3 | INSTALL 2" RISER INTO BOTTOM OF CABINET |
| 4 | INSTALL 2" RISER WITH WEATHERHEAD |
| 5 | INSTALL 2" RISER WITH SEALING BUSHING |
| 6 | INSTALL 2" CONDUIT ENTRANCE INTO EXISTING FOUNDATION |
| 7 | INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE |
| 8 | INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET |
| 9 | INSTALL 2" PVC CONDUIT |
| 10 | JACK AND BORE 2" CONDUIT |
| 11 | INSTALL 3" PVC CONDUIT |
| 13 | INSTALL 3" RISER WITH WEATHERHEAD |
| 14 | INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET |
| 17 | REUSE EXISTING RISER WITH SEALING BUSHING |
| 18 | TIE CONDUIT INTO EXISTING PULLBOX |
| 19 | REUSE EXISTING CONDUIT |
| 20 | REUSE EXISTING RISER WITH WEATHERHEAD |
| 21 | ATTACH CONDUIT TO EXISTING CONDUIT STUB-OUT |
| 23 | INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD |
| 24 | INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD |
| 25 | INSTALL CABLES IN EXISTING WEATHERHEAD |
| 26 | INSTALL CABLES IN EXISTING POLE |
| 27 | INSTALL CABLES IN PROPOSED POLE |
| 29 | INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET |
| 30 | LASH TO EXISTING MESSENGER WIRE/SPANWIRE |
| 32 | ATTACH CONDUIT TO BRIDGE |

△ NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.

CL-11


DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
YALE ROAD
CABLE LAYOUT
FROM 57+50 TO 82+50

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: SHEET 20 OF 72



△ NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.

- B1 RETAIN AND MODIFY EXISTING CABINET
- B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
- B7 INSTALL FIBER DISTRIBUTION BOX
- B9 INSTALL TRAFFIC SIGNAL PULLBOX
- B10 INSTALL FIBER OPTIC PULLBOX TYPE A
- B11 INSTALL FIBER OPTIC PULLBOX TYPE B
- B13 INSTALL 20' PEDESTAL POLE
- B15 MLGW POWER SERVICE CONNECTION
- C2 INSTALL 8-PHASE CONTROLLER
- C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5 INSTALL FIBER OPTIC MODEM
- C6 INSTALL ETHERNET CABINET SWITCH
- C7 INSTALL SERIAL DEVICE SERVER
- D1 INSTALL EVP DETECTOR
- D2 INSTALL EVP CONFIRMATION BEACON
- D3 INSTALL EVP CONFIRMATION LAMP
- D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8 INSTALL EVP PHASE SELECTOR
- D9 INSTALL VIDEO DETECTION PROCESSOR
- D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12 INSTALL NEW POLE MOUNTED RDS CABINET
- D13 INSTALL RADAR DETECTION SYSTEM
- D14 VIDEO REMOTE MANAGEMENT CARD
- D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- W1 EVP DETECTOR CABLE(S)
- W2 EVP CONFIRMATION BEACON POWER CABLE(S)
- W3 EVP CONFIRMATION LAMP POWER CABLE(S)
- W4 VIDEO DETECTOR CABLE(S)
- W5 2C DETECTOR CABLE(S)
- W6 SMFO CABLE
- W7 SMFO TRUNK CABLE
- W9 DROP CABLES (6-FIBER)
- W11 RDS CABLE
- W12 RDS POWER CABLE
- W13 ETHERNET DATA CABLE
- 3 INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4 INSTALL 2" RISER WITH WEATHERHEAD
- 5 INSTALL 2" RISER WITH SEALING BUSHING
- 6 INSTALL 2" CONDUIT ENTRANCE INTO EXISTING FOUNDATION
- 7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9 INSTALL 2" PVC CONDUIT
- 10 JACK AND BORE 2" CONDUIT
- 11 INSTALL 3" PVC CONDUIT
- 13 INSTALL 3" RISER WITH WEATHERHEAD
- 14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 17 REUSE EXISTING RISER WITH SEALING BUSHING
- 18 TIE CONDUIT INTO EXISTING PULLBOX
- 19 REUSE EXISTING CONDUIT
- 20 REUSE EXISTING RISER WITH WEATHERHEAD
- 21 ATTACH CONDUIT TO EXISTING CONDUIT STUB-OUT
- 23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25 INSTALL CABLES IN EXISTING WEATHERHEAD
- 26 INSTALL CABLES IN EXISTING POLE
- 27 INSTALL CABLES IN PROPOSED POLE
- 29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32 ATTACH CONDUIT TO BRIDGE





REVISIONS		
DATE	DESCRIPTIONS	APPROVED



CL-12


DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
YALE ROAD
CABLE LAYOUT
FROM 82+50 TO 107+50

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: _____ SHEET 21 OF 72




- B1 RETAIN AND MODIFY EXISTING CABINET
- B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
- B7 INSTALL FIBER DISTRIBUTION BOX
- B9 INSTALL TRAFFIC SIGNAL PULLBOX
- B10 INSTALL FIBER OPTIC PULLBOX TYPE A
- B11 INSTALL FIBER OPTIC PULLBOX TYPE B
- B13 INSTALL 20' PEDESTAL POLE
- B15 MLGW POWER SERVICE CONNECTION
- C2 INSTALL 8-PHASE CONTROLLER
- C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5 INSTALL FIBER OPTIC MODEM
- C6 INSTALL ETHERNET CABINET SWITCH
- C7 INSTALL SERIAL DEVICE SERVER
- D1 INSTALL EVP DETECTOR
- D2 INSTALL EVP CONFIRMATION BEACON
- D3 INSTALL EVP CONFIRMATION LAMP
- D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8 INSTALL EVP PHASE SELECTOR
- D9 INSTALL VIDEO DETECTION PROCESSOR
- D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12 INSTALL NEW POLE MOUNTED RDS CABINET
- D13 INSTALL RADAR DETECTION SYSTEM
- D14 VIDEO REMOTE MANAGEMENT CARD
- D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- W1 EVP DETECTOR CABLE(S)
- W2 EVP CONFIRMATION BEACON POWER CABLE(S)
- W3 EVP CONFIRMATION LAMP POWER CABLE(S)
- W4 VIDEO DETECTOR CABLE(S)
- W5 2C DETECTOR CABLE(S)
- W6 SMFO CABLE
- W7 SMFO TRUNK CABLE
- W9 DROP CABLES (6-FIBER)
- W11 RDS CABLE
- W12 RDS POWER CABLE
- W13 ETHERNET DATA CABLE
- 3 INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4 INSTALL 2" RISER WITH WEATHERHEAD
- 5 INSTALL 2" RISER WITH SEALING BUSHING
- 6 INSTALL 2" CONDUIT ENTRANCE INTO EXISTING FOUNDATION
- 7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9 INSTALL 2" PVC CONDUIT
- 10 JACK AND BORE 2" CONDUIT
- 11 INSTALL 3" PVC CONDUIT
- 13 INSTALL 3" RISER WITH WEATHERHEAD
- 14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 17 REUSE EXISTING RISER WITH SEALING BUSHING
- 18 TIE CONDUIT INTO EXISTING PULLBOX
- 19 REUSE EXISTING CONDUIT
- 20 REUSE EXISTING RISER WITH WEATHERHEAD
- 21 ATTACH CONDUIT TO EXISTING CONDUIT STUB-OUT
- 23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25 INSTALL CABLES IN EXISTING WEATHERHEAD
- 26 INSTALL CABLES IN EXISTING POLE
- 27 INSTALL CABLES IN PROPOSED POLE
- 29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32 ATTACH CONDUIT TO BRIDGE

△ NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.





REVISIONS		
DATE	DESCRIPTIONS	APPROVED



CL-13


DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
YALE ROAD
CABLE LAYOUT
FROM 107+50 TO 132+50

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: SHEET 22 OF 72




- B1 RETAIN AND MODIFY EXISTING CABINET
- B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
- B7 INSTALL FIBER DISTRIBUTION BOX
- B9 INSTALL TRAFFIC SIGNAL PULLBOX
- B10 INSTALL FIBER OPTIC PULLBOX TYPE A
- B11 INSTALL FIBER OPTIC PULLBOX TYPE B
- B13 INSTALL 20' PEDESTAL POLE
- B15 MLGW POWER SERVICE CONNECTION
- C2 INSTALL 8-PHASE CONTROLLER
- C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5 INSTALL FIBER OPTIC MODEM
- C6 INSTALL ETHERNET CABINET SWITCH
- C7 INSTALL SERIAL DEVICE SERVER
- D1 INSTALL EVP DETECTOR
- D2 INSTALL EVP CONFIRMATION BEACON
- D3 INSTALL EVP CONFIRMATION LAMP
- D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8 INSTALL EVP PHASE SELECTOR
- D9 INSTALL VIDEO DETECTION PROCESSOR
- D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12 INSTALL NEW POLE MOUNTED RDS CABINET
- D13 INSTALL RADAR DETECTION SYSTEM
- D14 VIDEO REMOTE MANAGEMENT CARD
- D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- W1 EVP DETECTOR CABLE(S)
- W2 EVP CONFIRMATION BEACON POWER CABLE(S)
- W3 EVP CONFIRMATION LAMP POWER CABLE(S)
- W4 VIDEO DETECTOR CABLE(S)
- W5 2C DETECTOR CABLE(S)
- W6 SMFO CABLE
- W7 SMFO TRUNK CABLE
- W9 DROP CABLES (6-FIBER)
- W11 RDS CABLE
- W12 RDS POWER CABLE
- W13 ETHERNET DATA CABLE
- 3 INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4 INSTALL 2" RISER WITH WEATHERHEAD
- 5 INSTALL 2" RISER WITH SEALING BUSHING
- 6 INSTALL 2" CONDUIT ENTRANCE INTO EXISTING FOUNDATION
- 7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9 INSTALL 2" PVC CONDUIT
- 10 JACK AND BORE 2" CONDUIT
- 11 INSTALL 3" PVC CONDUIT
- 13 INSTALL 3" RISER WITH WEATHERHEAD
- 14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 17 REUSE EXISTING RISER WITH SEALING BUSHING
- 18 TIE CONDUIT INTO EXISTING PULLBOX
- 19 REUSE EXISTING CONDUIT
- 20 REUSE EXISTING RISER WITH WEATHERHEAD
- 21 ATTACH CONDUIT TO EXISTING CONDUIT STUB-OUT
- 23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25 INSTALL CABLES IN EXISTING WEATHERHEAD
- 26 INSTALL CABLES IN EXISTING POLE
- 27 INSTALL CABLES IN PROPOSED POLE
- 29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32 ATTACH CONDUIT TO BRIDGE

△ NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.




REVISIONS		
DATE	DESCRIPTIONS	APPROVED



CL-14

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
YALE ROAD
CABLE LAYOUT
FROM 132+50 TO 157+50

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: _____ SHEET 23 OF 72



GRAPHIC SCALE



50 0 25 50 100

(IN FEET)
1 inch = 50 ft.

JURISDICTION: _____ SHEET 24 OF 72


DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bia Set 5\Plans\BldSet 5-25-IL-01-Jackson at Trezevant.dwg Layout Jan 30, 2015 3:26PM BY: blaine.lynn

NOTES:
1) ALL CONDUIT WORK IS SCHEMATIC AND MUST BE PERFORMED WITHIN THE EXISTING R.O.W.



REMOVAL DIAGRAM

* EXISTING SIGNAL POLES TO REMAIN.
- REMOVE ALL STOP BAR VEHICLE DETECTOR AMPLIFIERS FROM CABINET.
- REMOVE EXISTING POLE MOUNTED CABINET AND CONTROLLER.




1 2

EXISTING SIGNAL HEAD TYPES

STREET NAME

A

EXISTING SIGNS




PHASE DIAGRAM

PREEMPT TABLE	
DETECTOR	PHASE(S) CALLED
1	1
3	3

ZONE	MODE	ZONE	MODE
01-1	PRESENCE	02-1	PRESENCE
01-2	PRESENCE	03-1	PRESENCE
01-3	PRESENCE	03-2	PRESENCE
01-4	PRESENCE	03-3*	PRESENCE
01-5	PRESENCE		

* 5 SECOND DELAY

ZONE ASSIGNMENT CHART



GENERAL WIRING DIAGRAM

NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.

REVISIONS		
DATE	DESCRIPTIONS	APPROVED



- B1 RETAIN AND MODIFY EXISTING CABINET
- B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
- B7 INSTALL FIBER DISTRIBUTION BOX
- B9 INSTALL TRAFFIC SIGNAL PULLBOX
- B10 INSTALL FIBER OPTIC PULLBOX TYPE A
- B11 INSTALL FIBER OPTIC PULLBOX TYPE B
- B13 INSTALL 20' PEDESTAL POLE
- B15 MLGW POWER SERVICE CONNECTION
- B16 INSTALL JUNCTION BOX
- C2 INSTALL 8-PHASE CONTROLLER
- C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5 INSTALL FIBER OPTIC MODEM
- C6 INSTALL ETHERNET CABINET SWITCH
- C7 INSTALL SERIAL DEVICE SERVER
- D1 INSTALL EVP DETECTOR
- D2 INSTALL EVP CONFIRMATION BEACON
- D3 INSTALL EVP CONFIRMATION LAMP
- D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8 INSTALL EVP PHASE SELECTOR
- D9 INSTALL VIDEO DETECTION PROCESSOR
- D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12 INSTALL NEW POLE MOUNTED RDS CABINET
- D13 INSTALL RADAR DETECTION SYSTEM
- D14 INSTALL VIDEO REMOTE MANAGEMENT CARD
- D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- D16 INSTALL BLUETOOTH DETECTION SYSTEM
- W1 EVP DETECTOR CABLE(S)
- W2 EVP CONFIRMATION BEACON POWER CABLE(S)
- W3 EVP CONFIRMATION LAMP POWER CABLE(S)
- W4 VIDEO DETECTOR CABLE(S)
- W5 2C DETECTOR CABLE(S)
- W6 SMFO CABLE
- W7 SMFO TRUNK CABLE
- W9 DROP CABLES (6-FIBER)
- W11 RDS CABLE
- W13 COIL 50' OF SMFO CABLE
- W14 16 CONDUCTOR CABLE
- 3 INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4 INSTALL 2" RISER WITH WEATHERHEAD
- 7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9 INSTALL 2" PVC CONDUIT
- 10 JACK AND BORE 2" CONDUIT
- 11 INSTALL 3" PVC CONDUIT
- 13 INSTALL 3" RISER WITH WEATHERHEAD
- 14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 16 JACK AND BORE 3" CONDUIT
- 17 INSTALL 3" RISER INTO BOTTOM OF CABINET
- 18 INSTALL 3" RGS CONDUIT
- 23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25 INSTALL CABLES IN EXISTING WEATHERHEAD
- 26 INSTALL CABLES IN EXISTING POLE
- 27 INSTALL CABLES IN PROPOSED POLE
- 29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32 ATTACH CONDUIT TO BRIDGE

IL-01




DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVE. AT TREZEVANT ST.
INTERSECTION LAYOUT

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: 1"=20'
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: CITY OF MEMPHIS SHEET 25 OF 72


Kimley»Horn

DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bia Set 5\Plans\BldSet 5-26-IL-02-Jackson at Hollywood.dwg Layout Jan 30, 2015 3:28PM BY: blaine.lynch

NOTES:
1) ALL CONDUIT WORK IS SCHEMATIC AND MUST BE PERFORMED WITHIN THE EXISTING R.O.W.




REMOVAL DIAGRAM



EXISTING SIGNAL HEAD TYPES



EXISTING SIGNS




PHASE DIAGRAM

PREEMPT TABLE	
DETECTOR	PHASE(S) CALLED
1	1
2	2

ZONE	MODE	ZONE	MODE
Ø1-1	PRESENCE	Ø1-6	PRESENCE
Ø1-2	PRESENCE	Ø2-1	PRESENCE
Ø1-3	PRESENCE	Ø2-2	PRESENCE
Ø1-4	PRESENCE	Ø2-3	PRESENCE
Ø1-5	PRESENCE	Ø2-4	PRESENCE

ZONE ASSIGNMENT CHART



GENERAL WIRING DIAGRAM

△ NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.

REVISIONS		
DATE	DESCRIPTIONS	APPROVED



- B1 RETAIN AND MODIFY EXISTING CABINET
- B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
- B7 INSTALL FIBER DISTRIBUTION BOX
- B9 INSTALL TRAFFIC SIGNAL PULLBOX
- B10 INSTALL FIBER OPTIC PULLBOX TYPE A
- B11 INSTALL FIBER OPTIC PULLBOX TYPE B
- B13 INSTALL 20' PEDESTAL POLE
- B15 MLGW POWER SERVICE CONNECTION
- B16 INSTALL JUNCTION BOX
- C2 INSTALL 8-PHASE CONTROLLER
- C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5 INSTALL FIBER OPTIC MODEM
- C6 INSTALL ETHERNET CABINET SWITCH
- C7 INSTALL SERIAL DEVICE SERVER
- D1 INSTALL EVP DETECTOR
- D2 INSTALL EVP CONFIRMATION BEACON
- D3 INSTALL EVP CONFIRMATION LAMP
- D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8 INSTALL EVP PHASE SELECTOR
- D9 INSTALL VIDEO DETECTION PROCESSOR
- D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12 INSTALL NEW POLE MOUNTED RDS CABINET
- D13 INSTALL RADAR DETECTION SYSTEM
- D14 INSTALL VIDEO REMOTE MANAGEMENT CARD
- D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- D16 INSTALL BLUETOOTH DETECTION SYSTEM
- W1 EVP DETECTOR CABLE(S)
- W2 EVP CONFIRMATION BEACON POWER CABLE(S)
- W3 EVP CONFIRMATION LAMP POWER CABLE(S)
- W4 VIDEO DETECTOR CABLE(S)
- W5 2C DETECTOR CABLE(S)
- W6 SMFO CABLE
- W7 SMFO TRUNK CABLE
- W9 DROP CABLES (6-FIBER)
- W11 RDS CABLE
- W13 COIL 50' OF SMFO CABLE
- W14 16 CONDUCTOR CABLE
- 3 INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4 INSTALL 2" RISER WITH WEATHERHEAD
- 7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9 INSTALL 2" PVC CONDUIT
- 10 JACK AND BORE 2" CONDUIT
- 11 INSTALL 3" PVC CONDUIT
- 13 INSTALL 3" RISER WITH WEATHERHEAD
- 14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 16 JACK AND BORE 3" CONDUIT
- 17 INSTALL 3" RISER INTO BOTTOM OF CABINET
- 18 INSTALL 3" RGS CONDUIT
- 23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25 INSTALL CABLES IN EXISTING WEATHERHEAD
- 26 INSTALL CABLES IN EXISTING POLE
- 27 INSTALL CABLES IN PROPOSED POLE
- 29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32 ATTACH CONDUIT TO BRIDGE

IL-02

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVE. AT N. HOLLYWOOD ST.
INTERSECTION LAYOUT




SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: 1"=20'
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: CITY OF MEMPHIS SHEET 26 OF 72

Kimley»Horn

DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bia Set 5\Plans\BldSet 5-27-IL-03-Jackson at Meagher.dwg Layout Jan 30, 2015 3:26PM BY: blaine.lynch


NOTES:

- 1) ALL CONDUIT WORK IS SCHEMATIC AND MUST BE PERFORMED WITHIN THE EXISTING R.O.W.




REMOVAL DIAGRAM

- * EXISTING SIGNAL POLES TO REMAIN.
- REMOVE ALL STOP BAR VEHICLE DETECTOR AMPLIFIERS FROM CABINET.
- REMOVE EXISTING POLE MOUNTED CABINET AND CONTROLLER.



EXISTING SIGNAL HEAD TYPES




PHASE DIAGRAM

PREEMPT TABLE	
DETECTOR	PHASE(S) CALLED
1	1
2	2

ZONE	MODE	ZONE	MODE
ø1-1	PRESENCE	ø1-4	PRESENCE
ø1-2	PRESENCE	ø1-5	PRESENCE
ø1-3	PRESENCE	ø2-1	PRESENCE

ZONE ASSIGNMENT CHART



GENERAL WIRING DIAGRAM

- △ NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.

REVISIONS		
DATE	DESCRIPTIONS	APPROVED



Kimley»Horn

- B1 RETAIN AND MODIFY EXISTING CABINET
B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
B7 INSTALL FIBER DISTRIBUTION BOX
B9 INSTALL TRAFFIC SIGNAL PULLBOX
B10 INSTALL FIBER OPTIC PULLBOX TYPE A
B11 INSTALL FIBER OPTIC PULLBOX TYPE B
B13 INSTALL 20" PEDESTAL POLE
B15 MLGW POWER SERVICE CONNECTION
B16 INSTALL JUNCTION BOX
C2 INSTALL 8-PHASE CONTROLLER
C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
C5 INSTALL FIBER OPTIC MODEM
C6 INSTALL ETHERNET CABINET SWITCH
C7 INSTALL SERIAL DEVICE SERVER
D1 INSTALL EVP DETECTOR
D2 INSTALL EVP CONFIRMATION BEACON
D3 INSTALL EVP CONFIRMATION LAMP
D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
D8 INSTALL EVP PHASE SELECTOR
D9 INSTALL VIDEO DETECTION PROCESSOR
D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
D12 INSTALL NEW POLE MOUNTED RDS CABINET
D13 INSTALL RADAR DETECTION SYSTEM
D14 INSTALL VIDEO REMOTE MANAGEMENT CARD
D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
D16 INSTALL BLUETOOTH DETECTION SYSTEM
W1 EVP DETECTOR CABLE(S)
W2 EVP CONFIRMATION BEACON POWER CABLE(S)
W3 EVP CONFIRMATION LAMP POWER CABLE(S)
W4 VIDEO DETECTOR CABLE(S)
W5 2C DETECTOR CABLE(S)
W6 SMFO CABLE
W7 SMFO TRUNK CABLE
W9 DROP CABLES (6-FIBER)
W11 RDS CABLE
W13 COIL 50' OF SMFO CABLE
W14 16 CONDUCTOR CABLE
3 INSTALL 2" RISER INTO BOTTOM OF CABINET
4 INSTALL 2" RISER WITH WEATHERHEAD
7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
9 INSTALL 2" PVC CONDUIT
10 JACK AND BORE 2" CONDUIT
11 INSTALL 3" PVC CONDUIT
13 INSTALL 3" RISER WITH WEATHERHEAD
14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
16 JACK AND BORE 3" CONDUIT
17 INSTALL 3" RISER INTO BOTTOM OF CABINET
18 INSTALL 3" RGS CONDUIT
23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
25 INSTALL CABLES IN EXISTING WEATHERHEAD
26 INSTALL CABLES IN EXISTING POLE
27 INSTALL CABLES IN PROPOSED POLE
29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
32 ATTACH CONDUIT TO BRIDGE

IL-03


DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVE. AT MEAGHER ST.
INTERSECTION LAYOUT

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: 1"=20'
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: CITY OF MEMPHIS SHEET 27 OF 72


DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bia Set 5\Plans\BldSet 5-28-IL-04-Jackson at Warford.dwg Layout Jan 30, 2015 3:26PM BY: blaine.lynch

NOTES:

- 1) POLES 1, 2 AND 3: CONTRACTOR TO COORDINATE CAMERA INSTALLATION WITH MLGW AND ENGINEER FOR POTENTIAL OVERHEAD UTILITY CONFLICTS.
- 2) ALL CONDUIT WORK IS SCHEMATIC AND MUST BE PERFORMED WITHIN THE EXISTING R.O.W.



PHASE DIAGRAM




PREEMPT TABLE	
DETECTOR	PHASE(S) CALLED
1	1
2	2

ZONE	MODE	ZONE	MODE
Ø1-1	PRESENCE	Ø1-6	PRESENCE
Ø1-2	PRESENCE	Ø2-1	PRESENCE
Ø1-3	PRESENCE	Ø2-2	PRESENCE
Ø1-4	PRESENCE	Ø2-3*	PRESENCE
Ø1-5	PRESENCE		

* 5 SECOND DELAY

ZONE ASSIGNMENT CHART



GENERAL WIRING DIAGRAM

- △ NUMBER OF CABLES, LOOPS, ETC.
- ⊗ NUMBER OF CONDUCTORS, PAIRS, ETC.

REVISIONS		
DATE	DESCRIPTIONS	APPROVED



- B1 RETAIN AND MODIFY EXISTING CABINET
- B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
- B7 INSTALL FIBER DISTRIBUTION BOX
- B9 INSTALL TRAFFIC SIGNAL PULLBOX
- B10 INSTALL FIBER OPTIC PULLBOX TYPE A
- B11 INSTALL FIBER OPTIC PULLBOX TYPE B
- B13 INSTALL 20' PEDESTAL POLE
- B15 MLGW POWER SERVICE CONNECTION
- B16 INSTALL JUNCTION BOX
- C2 INSTALL 8-PHASE CONTROLLER
- C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5 INSTALL FIBER OPTIC MODEM
- C6 INSTALL ETHERNET CABINET SWITCH
- C7 INSTALL SERIAL DEVICE SERVER
- D1 INSTALL EVP DETECTOR
- D2 INSTALL EVP CONFIRMATION BEACON
- D3 INSTALL EVP CONFIRMATION LAMP
- D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8 INSTALL EVP PHASE SELECTOR
- D9 INSTALL VIDEO DETECTION PROCESSOR
- D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12 INSTALL NEW POLE MOUNTED RDS CABINET
- D13 INSTALL RADAR DETECTION SYSTEM
- D14 INSTALL VIDEO REMOTE MANAGEMENT CARD
- D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- D16 INSTALL BLUETOOTH DETECTION SYSTEM
- W1 EVP DETECTOR CABLE(S)
- W2 EVP CONFIRMATION BEACON POWER CABLE(S)
- W3 EVP CONFIRMATION LAMP POWER CABLE(S)
- W4 VIDEO DETECTOR CABLE(S)
- W5 2C DETECTOR CABLE(S)
- W6 SMFO CABLE
- W7 SMFO TRUNK CABLE
- W9 DROP CABLES (6-FIBER)
- W11 RDS CABLE
- W13 COIL 50' OF SMFO CABLE
- W14 16 CONDUCTOR CABLE
- 3 INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4 INSTALL 2" RISER WITH WEATHERHEAD
- 7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9 INSTALL 2" PVC CONDUIT
- 10 JACK AND BORE 2" CONDUIT
- 11 INSTALL 3" PVC CONDUIT
- 13 INSTALL 3" RISER WITH WEATHERHEAD
- 14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 16 JACK AND BORE 3" CONDUIT
- 17 INSTALL 3" RISER INTO BOTTOM OF CABINET
- 18 INSTALL 3" RGS CONDUIT
- 23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25 INSTALL CABLES IN EXISTING WEATHERHEAD
- 26 INSTALL CABLES IN EXISTING POLE
- 27 INSTALL CABLES IN PROPOSED POLE
- 29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32 ATTACH CONDUIT TO BRIDGE

IL-04

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVE. AT WARFORD ST.
INTERSECTION LAYOUT

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: 1"=20'
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: CITY OF MEMPHIS SHEET 28 OF 72

Kimley»Horn




DRAWING NAME: K:\VEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bia Set 5\Plans\BldSet 5-29-IL-05-Jackson at Pope.dwg Layout Jan 30, 2015 3:28PM BY: blaine.lynch

NOTES:

- 1) POLE 1: CONTRACTOR TO COORDINATE CAMERA INSTALLATION WITH MLGW AND ENGINEER FOR POTENTIAL OVERHEAD UTILITY CONFLICTS.
- 2) ALL CONDUIT WORK IS SCHEMATIC AND MUST BE PERFORMED WITHIN THE EXISTING R.O.W.


† ADVANCE DETECTION NOTES:

- 1) INSTALL NEW ADVANCE DETECTION LOOPS FOR EB APPROACH (ø1-7) AND WB APPROACH (ø1-8) 230' FROM STOP BAR
- 2) SEE DETAIL "A" ON ADVANCE LOOP DETECTION DETAIL SHEET




REMOVAL DIAGRAM


- *EXISTING SIGNAL POLES TO REMAIN.
- REMOVE ALL STOP BAR VEHICLE DETECTOR AMPLIFIERS FROM CABINET.
 - REMOVE EXISTING POLE MOUNTED CABINET AND CONTROLLER.



EXISTING SIGNAL HEAD TYPES



EXISTING OVERHEAD SIGNS




PHASE DIAGRAM

PREEMPT TABLE	
DETECTOR	PHASE(S) CALLED
ø1	1
ø2	2

ZONE	MODE	ZONE	MODE
ø1-1	PRESENCE	ø1-7	PULSE
ø1-2	PRESENCE	ø1-8	PULSE
ø1-3	PRESENCE	ø2-1	PRESENCE
ø1-4	PRESENCE	ø2-2	PRESENCE
ø1-5	PRESENCE	ø2-3	PRESENCE
ø1-6	PRESENCE		

ZONE ASSIGNMENT CHART



GENERAL WIRING DIAGRAM

- △ NUMBER OF CABLES, LOOPS, ETC.
- ✕ NUMBER OF CONDUCTORS, PAIRS, ETC.

REVISIONS		
DATE	DESCRIPTIONS	APPROVED



- B1 RETAIN AND MODIFY EXISTING CABINET
- B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
- B7 INSTALL FIBER DISTRIBUTION BOX
- B9 INSTALL TRAFFIC SIGNAL PULLBOX
- B10 INSTALL FIBER OPTIC PULLBOX TYPE A
- B11 INSTALL FIBER OPTIC PULLBOX TYPE B
- B13 INSTALL 20" PEDESTAL POLE
- B15 MLGW POWER SERVICE CONNECTION
- B16 INSTALL JUNCTION BOX
- C2 INSTALL 8-PHASE CONTROLLER
- C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5 INSTALL FIBER OPTIC MODEM
- C6 INSTALL ETHERNET CABINET SWITCH
- C7 INSTALL SERIAL DEVICE SERVER
- D1 INSTALL EVP DETECTOR
- D2 INSTALL EVP CONFIRMATION BEACON
- D3 INSTALL EVP CONFIRMATION LAMP
- D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8 INSTALL EVP PHASE SELECTOR
- D9 INSTALL VIDEO DETECTION PROCESSOR
- D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12 INSTALL NEW POLE MOUNTED RDS CABINET
- D13 INSTALL RADAR DETECTION SYSTEM
- D14 INSTALL VIDEO REMOTE MANAGEMENT CARD
- D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- D16 INSTALL BLUETOOTH DETECTION SYSTEM
- W1 EVP DETECTOR CABLE(S)
- W2 EVP CONFIRMATION BEACON POWER CABLE(S)
- W3 EVP CONFIRMATION LAMP POWER CABLE(S)
- W4 VIDEO DETECTOR CABLE(S)
- W5 2C DETECTOR CABLE(S)
- W6 SMFO CABLE
- W7 SMFO TRUNK CABLE
- W9 DROP CABLES (6-FIBER)
- W11 RDS CABLE
- W13 COIL 50' OF SMFO CABLE
- W14 16 CONDUCTOR CABLE
- 3 INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4 INSTALL 2" RISER WITH WEATHERHEAD
- 7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9 INSTALL 2" PVC CONDUIT
- 10 JACK AND BORE 2" CONDUIT
- 11 INSTALL 3" PVC CONDUIT
- 13 INSTALL 3" RISER WITH WEATHERHEAD
- 14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 16 JACK AND BORE 3" CONDUIT
- 17 INSTALL 3" RISER INTO BOTTOM OF CABINET
- 18 INSTALL 3" RGS CONDUIT
- 23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25 INSTALL CABLES IN EXISTING WEATHERHEAD
- 26 INSTALL CABLES IN EXISTING POLE
- 27 INSTALL CABLES IN PROPOSED POLE
- 29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32 ATTACH CONDUIT TO BRIDGE

IL-05




DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVE. AT POPE ST.
INTERSECTION LAYOUT

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: 1"=20'
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: CITY OF MEMPHIS

Kimley»Horn


1) ALL CONDUIT WORK IS SCHEMATIC AND MUST BE PERFORMED WITHIN THE EXISTING R.O.W.

DRAWING NAME: K:\MEM_TPTO\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bid Set 5\Plans\BidSet 5-30-11-06-Jackson at Hudson.dwg Layout Jan 30, 2015 3:26PM BY: blaine.lynnch




REMOVAL DIAGRAM

- * EXISTING SIGNAL POLES TO REMAIN.
- REMOVE ALL STOP BAR VEHICLE DETECTOR AMPLIFIERS FROM CABINET.
- REMOVE EXISTING POLE MOUNTED CABINET AND CONTROLLER.



① ②

EXISTING SIGNAL HEAD TYPES




PHASE DIAGRAM


PREEMPT TABLE	
DETECTOR	PHASE(S) CALLED
1	1
2	2

ZONE	MODE	ZONE	MODE
$\phi 1-1$	PRESENCE	$\phi 1-5$	PRESENCE
$\phi 1-2$	PRESENCE	$\phi 1-6$	PRESENCE
$\phi 1-3$	PRESENCE	$\phi 2-1$	PRESENCE
$\phi 1-4$	PRESENCE	$\phi 2-2$	PRESENCE

ZONE ASSIGNMENT CHART



GENERAL WIRING DIAGRAM

[illegible]

Kimley»»Horn

B1	RETAIN AND MODIFY EXISTING CABINET
B3	INSTALL NEW BASE MOUNTED CONTROLLER CABINET
B6	INSTALL WEATHER PROOF SPLICE ENCLOSURE
B7	INSTALL FIBER DISTRIBUTION BOX
B9	INSTALL TRAFFIC SIGNAL PULLBOX
B10	INSTALL FIBER OPTIC PULLBOX TYPE A
B11	INSTALL FIBER OPTIC PULLBOX TYPE B
B13	INSTALL 20' PEDESTAL POLE
B15	MLGW POWER SERVICE CONNECTION
B16	INSTALL JUNCTION BOX
C2	INSTALL 8-PHASE CONTROLLER
C4	REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
C5	INSTALL FIBER OPTIC MODEM
C6	INSTALL ETHERNET CABINET SWITCH
C7	INSTALL SERIAL DEVICE SERVER
D1	INSTALL EVP DETECTOR
D2	INSTALL EVP CONFIRMATION BEACON
D3	INSTALL EVP CONFIRMATION LAMP
D4	INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
D5	INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
D6	INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
D8	INSTALL EVP PHASE SELECTOR
D9	INSTALL VIDEO DETECTION PROCESSOR
D10	INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
D11	REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
D12	INSTALL NEW POLE MOUNTED RDS CABINET
D13	INSTALL RADAR DETECTION SYSTEM
D14	INSTALL VIDEO REMOTE MANAGEMENT CARD
D15	INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
D16	INSTALL BLUETOOTH DETECTION SYSTEM
W1	EVP DETECTOR CABLE(S)
W2	EVP CONFIRMATION BEACON POWER CABLE(S)
W3	EVP CONFIRMATION LAMP POWER CABLE(S)
W4	VIDEO DETECTOR CABLE(S)
W5	2C DETECTOR CABLE(S)
W6	SMFO CABLE
W7	SMFO TRUNK CABLE
W9	DROP CABLES (6-FIBER)
W11	RDS CABLE
W13	COIL 50' OF SMFO CABLE
W14	16 CONDUCTOR CABLE
3	INSTALL 2" RISER INTO BOTTOM OF CABINET
4	INSTALL 2" RISER WITH WEATHERHEAD
7	INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
8	INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
9	INSTALL 2" PVC CONDUIT
10	JACK AND BORE 2" CONDUIT
11	INSTALL 3" PVC CONDUIT
13	INSTALL 3" RISER WITH WEATHERHEAD
14	INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
16	JACK AND BORE 3" CONDUIT
17	INSTALL 3" RISER INTO BOTTOM OF CABINET
18	INSTALL 3" RGS CONDUIT
23	INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
24	INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
25	INSTALL CABLES IN EXISTING WEATHERHEAD
26	INSTALL CABLES IN EXISTING POLE
27	INSTALL CABLES IN PROPOSED POLE
29	INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
30	LASH TO EXISTING MESSENGER WIRE/SPANWIRE
32	ATTACH CONDUIT TO BRIDGE

1L-06




DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVE AT HUDSON RD.
INTERSECTION LAYOUT

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: 1"=20'
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: CITY OF MEMPHIS

DRAWING NAME: K:\VEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bia Set 5\Plans\BldSet 5-31-IL-07-Jackson at Macon.dwg Layout Jan 30, 2015 3:27PM BY: blaine.lynnch


NOTES:

- 1) ALL CONDUIT WORK IS SCHEMATIC AND MUST BE PERFORMED WITHIN THE EXISTING R.O.W.






REMOVAL DIAGRAM


- * EXISTING SIGNAL POLES AND CONTROLLER CABINET TO REMAIN.
- TURN OFF STOP BAR VEHICLE DETECTOR CHANNELS ON EXISTING AMPLIFIERS IN CABINET.



EXISTING SIGNAL HEAD TYPES



EXISTING OVERHEAD SIGNS




PHASE DIAGRAM

PREEMPT TABLE	
DETECTOR	PHASE(S) CALLED
◇ 2	2
◇ 4	4

ZONE	MODE	ZONE	MODE
ø2-1	PRESENCE	ø2-6	PRESENCE
ø2-2	PRESENCE	ø4-1	PRESENCE
ø2-3	PRESENCE	ø4-2	PRESENCE
ø2-4	PRESENCE	ø4-3*	PRESENCE
ø2-5	PRESENCE	ø4-4	PRESENCE

* 5 SECOND DELAY

ZONE ASSIGNMENT CHART



GENERAL WIRING DIAGRAM

- △ NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.

REVISIONS		
DATE	DESCRIPTIONS	APPROVED



- B1 RETAIN AND MODIFY EXISTING CABINET
- B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
- B7 INSTALL FIBER DISTRIBUTION BOX
- B9 INSTALL TRAFFIC SIGNAL PULLBOX
- B10 INSTALL FIBER OPTIC PULLBOX TYPE A
- B11 INSTALL FIBER OPTIC PULLBOX TYPE B
- B13 INSTALL 20' PEDESTAL POLE
- B15 MLGW POWER SERVICE CONNECTION
- B16 INSTALL JUNCTION BOX
- C2 INSTALL 8-PHASE CONTROLLER
- C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5 INSTALL FIBER OPTIC MODEM
- C6 INSTALL ETHERNET CABINET SWITCH
- C7 INSTALL SERIAL DEVICE SERVER
- D1 INSTALL EVP DETECTOR
- D2 INSTALL EVP CONFIRMATION BEACON
- D3 INSTALL EVP CONFIRMATION LAMP
- D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8 INSTALL EVP PHASE SELECTOR
- D9 INSTALL VIDEO DETECTION PROCESSOR
- D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12 INSTALL NEW POLE MOUNTED RDS CABINET
- D13 INSTALL RADAR DETECTION SYSTEM
- D14 INSTALL VIDEO REMOTE MANAGEMENT CARD
- D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- D16 INSTALL BLUETOOTH DETECTION SYSTEM
- W1 EVP DETECTOR CABLE(S)
- W2 EVP CONFIRMATION BEACON POWER CABLE(S)
- W3 EVP CONFIRMATION LAMP POWER CABLE(S)
- W4 VIDEO DETECTOR CABLE(S)
- W5 2C DETECTOR CABLE(S)
- W6 SMFO CABLE
- W7 SMFO TRUNK CABLE
- W9 DROP CABLES (6-FIBER)
- W11 RDS CABLE
- W13 COIL 50' OF SMFO CABLE
- W14 16 CONDUCTOR CABLE
- 3 INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4 INSTALL 2" RISER WITH WEATHERHEAD
- 7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9 INSTALL 2" PVC CONDUIT
- 10 JACK AND BORE 2" CONDUIT
- 11 INSTALL 3" PVC CONDUIT
- 13 INSTALL 3" RISER WITH WEATHERHEAD
- 14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 16 JACK AND BORE 3" CONDUIT
- 17 INSTALL 3" RISER INTO BOTTOM OF CABINET
- 18 INSTALL 3" RGS CONDUIT
- 23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25 INSTALL CABLES IN EXISTING WEATHERHEAD
- 26 INSTALL CABLES IN EXISTING POLE
- 27 INSTALL CABLES IN PROPOSED POLE
- 29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32 ATTACH CONDUIT TO BRIDGE

IL-07




DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVE. AT MACON RD.
INTERSECTION LAYOUT

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: 1"=20'
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: CITY OF MEMPHIS SHEET 31 OF 72

Kimley»Horn


DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bld Set 5\Plans\BldSet 5-32-IL-08-Jackson at Bayliss.dwg Layout Jan 30, 2015 3:27PM BY: blaine.lynnch

- NOTES:
- 1) ALL CONDUIT WORK IS SCHEMATIC AND MUST BE PERFORMED WITHIN THE EXISTING R.O.W.
 - 2) CONTRACTOR TO CONNECT EXISTING SIGNAL CABLES IN EXISTING JUNCTION BOX TO PROPOSED JUNCTION BOX WITH 16 CONDUCTOR CABLE.




REMOVAL DIAGRAM

- * EXISTING SIGNAL POLES TO REMAIN.
- REMOVE ALL STOP BAR VEHICLE DETECTOR AMPLIFIERS FROM CABINET.
 - REMOVE EXISTING POLE MOUNTED CABINET AND CONTROLLER.



1 2

EXISTING SIGNAL HEAD TYPES




PHASE DIAGRAM

PREEMPT TABLE	
DETECTOR	PHASE(S) CALLED
1	1
2	2

ZONE	MODE	ZONE	MODE
Ø1-1	PRESENCE	Ø1-5	PRESENCE
Ø1-2	PRESENCE	Ø1-6	PRESENCE
Ø1-3	PRESENCE	Ø2-1	PRESENCE
Ø1-4	PRESENCE	Ø2-2	PRESENCE

ZONE ASSIGNMENT CHART



GENERAL WIRING DIAGRAM

- △ NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.

REVISIONS		
DATE	DESCRIPTIONS	APPROVED



Kimley»Horn

- B1 RETAIN AND MODIFY EXISTING CABINET
- B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
- B7 INSTALL FIBER DISTRIBUTION BOX
- B9 INSTALL TRAFFIC SIGNAL PULLBOX
- B10 INSTALL FIBER OPTIC PULLBOX TYPE A
- B11 INSTALL FIBER OPTIC PULLBOX TYPE B
- B13 INSTALL 20' PEDESTAL POLE
- B15 MLGW POWER SERVICE CONNECTION
- B16 INSTALL JUNCTION BOX
- C2 INSTALL 8-PHASE CONTROLLER
- C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5 INSTALL FIBER OPTIC MODEM
- C6 INSTALL ETHERNET CABINET SWITCH
- C7 INSTALL SERIAL DEVICE SERVER
- D1 INSTALL EVP DETECTOR
- D2 INSTALL EVP CONFIRMATION BEACON
- D3 INSTALL EVP CONFIRMATION LAMP
- D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8 INSTALL EVP PHASE SELECTOR
- D9 INSTALL VIDEO DETECTION PROCESSOR
- D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12 INSTALL NEW POLE MOUNTED RDS CABINET
- D13 INSTALL RADAR DETECTION SYSTEM
- D14 INSTALL VIDEO REMOTE MANAGEMENT CARD
- D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- D16 INSTALL BLUETOOTH DETECTION SYSTEM
- W1 EVP DETECTOR CABLE(S)
- W2 EVP CONFIRMATION BEACON POWER CABLE(S)
- W3 EVP CONFIRMATION LAMP POWER CABLE(S)
- W4 VIDEO DETECTOR CABLE(S)
- W5 2C DETECTOR CABLE(S)
- W6 SMFO CABLE
- W7 SMFO TRUNK CABLE
- W9 DROP CABLES (6-FIBER)
- W11 RDS CABLE
- W13 COIL 50' OF SMFO CABLE
- W14 16 CONDUCTOR CABLE
- 3 INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4 INSTALL 2" RISER WITH WEATHERHEAD
- 7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9 INSTALL 2" PVC CONDUIT
- 10 JACK AND BORE 2" CONDUIT
- 11 INSTALL 3" PVC CONDUIT
- 13 INSTALL 3" RISER WITH WEATHERHEAD
- 14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 16 JACK AND BORE 3" CONDUIT
- 17 INSTALL 3" RISER INTO BOTTOM OF CABINET
- 18 INSTALL 3" RGS CONDUIT
- 23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25 INSTALL CABLES IN EXISTING WEATHERHEAD
- 26 INSTALL CABLES IN EXISTING POLE
- 27 INSTALL CABLES IN PROPOSED POLE
- 29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32 ATTACH CONDUIT TO BRIDGE



IL-08

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVE. AT BAYLISS AVE.
INTERSECTION LAYOUT

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: 1"=20'
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: CITY OF MEMPHIS SHEET 32 OF 72


DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bld Set 5\Plans\BldSet 5-33-IL-09-Jackson at Orchid.dwg Layout Jan 30, 2015 3:27PM BY: bliane.lynch

NOTES:
1) ALL CONDUIT WORK IS SCHEMATIC AND MUST BE PERFORMED WITHIN THE EXISTING R.O.W.



REMOVAL DIAGRAM

- * EXISTING SIGNAL POLES TO REMAIN.
- REMOVE ALL STOP BAR VEHICLE DETECTOR AMPLIFIERS FROM CABINET.
- REMOVE EXISTING POLE MOUNTED CABINET AND CONTROLLER.




1 2

EXISTING SIGNAL HEAD TYPES

STREET NAME



EXISTING SIGNAL POLE-MOUNTED SIGNS




PHASE DIAGRAM

PREEMPT TABLE	
DETECTOR	PHASE(S) CALLED
1	1
2	2

ZONE	MODE	ZONE	MODE
Ø1-1	PRESENCE	Ø1-6	PRESENCE
Ø1-2	PRESENCE	Ø1-7	PRESENCE
Ø1-3	PRESENCE	Ø2-1	PRESENCE
Ø1-4	PRESENCE	Ø2-2	PRESENCE
Ø1-5	PRESENCE		

ZONE ASSIGNMENT CHART



GENERAL WIRING DIAGRAM

REVISIONS		
DATE	DESCRIPTIONS	APPROVED



- B1 RETAIN AND MODIFY EXISTING CABINET
- B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
- B7 INSTALL FIBER DISTRIBUTION BOX
- B9 INSTALL TRAFFIC SIGNAL PULLBOX
- B10 INSTALL FIBER OPTIC PULLBOX TYPE A
- B11 INSTALL FIBER OPTIC PULLBOX TYPE B
- B13 INSTALL 20" PEDESTAL POLE
- B15 MLGW POWER SERVICE CONNECTION
- B16 INSTALL JUNCTION BOX
- C2 INSTALL 8-PHASE CONTROLLER
- C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5 INSTALL FIBER OPTIC MODEM
- C6 INSTALL ETHERNET CABINET SWITCH
- C7 INSTALL SERIAL DEVICE SERVER
- D1 INSTALL EVP DETECTOR
- D2 INSTALL EVP CONFIRMATION BEACON
- D3 INSTALL EVP CONFIRMATION LAMP
- D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8 INSTALL EVP PHASE SELECTOR
- D9 INSTALL VIDEO DETECTION PROCESSOR
- D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12 INSTALL NEW POLE MOUNTED RDS CABINET
- D13 INSTALL RADAR DETECTION SYSTEM
- D14 INSTALL VIDEO REMOTE MANAGEMENT CARD
- D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- D16 INSTALL BLUETOOTH DETECTION SYSTEM
- W1 EVP DETECTOR CABLE(S)
- W2 EVP CONFIRMATION BEACON POWER CABLE(S)
- W3 EVP CONFIRMATION LAMP POWER CABLE(S)
- W4 VIDEO DETECTOR CABLE(S)
- W5 2C DETECTOR CABLE(S)
- W6 SMFO CABLE
- W7 SMFO TRUNK CABLE
- W9 DROP CABLES (6-FIBER)
- W11 RDS CABLE
- W13 COIL 50' OF SMFO CABLE
- W14 16 CONDUCTOR CABLE
- 3 INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4 INSTALL 2" RISER WITH WEATHERHEAD
- 7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9 INSTALL 2" PVC CONDUIT
- 10 JACK AND BORE 2" CONDUIT
- 11 INSTALL 3" PVC CONDUIT
- 13 INSTALL 3" RISER WITH WEATHERHEAD
- 14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 16 JACK AND BORE 3" CONDUIT
- 17 INSTALL 3" RISER INTO BOTTOM OF CABINET
- 18 INSTALL 3" RGS CONDUIT
- 23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25 INSTALL CABLES IN EXISTING WEATHERHEAD
- 26 INSTALL CABLES IN EXISTING POLE
- 27 INSTALL CABLES IN PROPOSED POLE
- 29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32 ATTACH CONDUIT TO BRIDGE

IL-09

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVE. AT ORCHI RD.
INTERSECTION LAYOUT

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: 1"=20'
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13



JURISDICTION: SHEET 33 OF 72

Kimley»Horn

DRAWING NAME: K:\WEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bld Set 5\Plans\BldSet 5-34-IL-10-Jackson at Wales.dwg Layout Jan 30, 2015 3:27PM BY: blaine.lynn


NOTES:

- 1) ALL CONDUIT WORK IS SCHEMATIC AND MUST BE PERFORMED WITHIN THE EXISTING R.O.W.




REMOVAL DIAGRAM


- * EXISTING SIGNAL POLES AND CONTROLLER CABINET TO REMAIN.
- TURN OFF STOP BAR VEHICLE DETECTOR CHANNELS ON EXISTING AMPLIFIERS IN CABINET.
 - ADVANCE DETECTION AMPLIFIERS TO REMAIN.
 - REMOVE EXISTING CAMERA ON POLE 4.



EXISTING SIGNAL HEAD TYPES



EXISTING OVERHEAD SIGNS




PHASE DIAGRAM

PREEMPT TABLE	
DETECTOR	PHASE(S) CALLED
Ø2	2
Ø4	4

ZONE	MODE	ZONE	MODE
Ø1-1	PRESENCE	Ø2-5	PRESENCE
Ø2-1	PRESENCE	Ø2-6	PRESENCE
Ø2-2	PRESENCE	Ø4-1	PRESENCE
Ø2-3	PRESENCE	Ø4-2	PRESENCE
Ø2-4	PRESENCE	Ø4-3	PRESENCE

ZONE ASSIGNMENT CHART



GENERAL WIRING DIAGRAM

- △ NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.

REVISIONS		
DATE	DESCRIPTIONS	APPROVED



- B1 RETAIN AND MODIFY EXISTING CABINET
- B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
- B7 INSTALL FIBER DISTRIBUTION BOX
- B9 INSTALL TRAFFIC SIGNAL PULLBOX
- B10 INSTALL FIBER OPTIC PULLBOX TYPE A
- B11 INSTALL FIBER OPTIC PULLBOX TYPE B
- B13 INSTALL 20' PEDESTAL POLE
- B15 MLGW POWER SERVICE CONNECTION
- B16 INSTALL JUNCTION BOX
- C2 INSTALL 8-PHASE CONTROLLER
- C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5 INSTALL FIBER OPTIC MODEM
- C6 INSTALL ETHERNET CABINET SWITCH
- C7 INSTALL SERIAL DEVICE SERVER
- D1 INSTALL EVP DETECTOR
- D2 INSTALL EVP CONFIRMATION BEACON
- D3 INSTALL EVP CONFIRMATION LAMP
- D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8 INSTALL EVP PHASE SELECTOR
- D9 INSTALL VIDEO DETECTION PROCESSOR
- D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12 INSTALL NEW POLE MOUNTED RDS CABINET
- D13 INSTALL RADAR DETECTION SYSTEM
- D14 INSTALL VIDEO REMOTE MANAGEMENT CARD
- D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- D16 INSTALL BLUETOOTH DETECTION SYSTEM
- W1 EVP DETECTOR CABLE(S)
- W2 EVP CONFIRMATION BEACON POWER CABLE(S)
- W3 EVP CONFIRMATION LAMP POWER CABLE(S)
- W4 VIDEO DETECTOR CABLE(S)
- W5 2C DETECTOR CABLE(S)
- W6 SMFO CABLE
- W7 SMFO TRUNK CABLE
- W9 DROP CABLES (6-FIBER)
- W11 RDS CABLE
- W13 COIL 50' OF SMFO CABLE
- W14 16 CONDUCTOR CABLE
- 3 INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4 INSTALL 2" RISER WITH WEATHERHEAD
- 7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9 INSTALL 2" PVC CONDUIT
- 10 JACK AND BORE 2" CONDUIT
- 11 INSTALL 3" PVC CONDUIT
- 13 INSTALL 3" RISER WITH WEATHERHEAD
- 14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 16 JACK AND BORE 3" CONDUIT
- 17 INSTALL 3" RISER INTO BOTTOM OF CABINET
- 18 INSTALL 3" RGS CONDUIT
- 23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25 INSTALL CABLES IN EXISTING WEATHERHEAD
- 26 INSTALL CABLES IN EXISTING POLE
- 27 INSTALL CABLES IN PROPOSED POLE
- 29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32 ATTACH CONDUIT TO BRIDGE

IL-10




DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVE. AT WALES AVE.
INTERSECTION LAYOUT

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: 1"=20'
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: CITY OF MEMPHIS SHEET 34 OF 72

Kimley»Horn


NOTES:

- 1) ALL CONDUIT WORK IS SCHEMATIC AND MUST BE PERFORMED WITHIN THE EXISTING R.O.W.




REMOVAL DIAGRAM


- * EXISTING SIGNAL POLES AND CONTROLLER CABINET TO REMAIN.
- TURN OFF STOP BAR VEHICLE DETECTOR CHANNELS ON EXISTING AMPLIFIERS IN CABINET.
- ADVANCE DETECTION AMPLIFIERS TO REMAIN.



EXISTING SIGNAL HEAD TYPES



EXISTING OVERHEAD SIGNS




PHASE DIAGRAM

PREEMPT TABLE	
DETECTOR	PHASE(S) CALLED
2	2 & 6
4	4 & 8
6	2 & 6
8	4 & 8

ZONE	MODE	ZONE	MODE
Ø1-1	PRESENCE	Ø4-3*	PRESENCE
Ø2-1	PRESENCE	Ø6-1	PRESENCE
Ø2-2	PRESENCE	Ø6-2	PRESENCE
Ø2-3	PRESENCE	Ø8-1	PRESENCE
Ø4-1	PRESENCE	Ø8-2*	PRESENCE
Ø4-2	PRESENCE		

* 5 SECOND DELAY

ZONE ASSIGNMENT CHART



GENERAL WIRING DIAGRAM

- △ NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.

REVISIONS		
DATE	DESCRIPTIONS	APPROVED



- B1 RETAIN AND MODIFY EXISTING CABINET
B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
B7 INSTALL FIBER DISTRIBUTION BOX
B9 INSTALL TRAFFIC SIGNAL PULLBOX
B10 INSTALL FIBER OPTIC PULLBOX TYPE A
B11 INSTALL FIBER OPTIC PULLBOX TYPE B
B13 INSTALL 20' PEDESTAL POLE
B15 MLGW POWER SERVICE CONNECTION
B16 INSTALL JUNCTION BOX
C2 INSTALL 8-PHASE CONTROLLER
C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
C5 INSTALL FIBER OPTIC MODEM
C6 INSTALL ETHERNET CABINET SWITCH
C7 INSTALL SERIAL DEVICE SERVER
D1 INSTALL EVP DETECTOR
D2 INSTALL EVP CONFIRMATION BEACON
D3 INSTALL EVP CONFIRMATION LAMP
D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
D8 INSTALL EVP PHASE SELECTOR
D9 INSTALL VIDEO DETECTION PROCESSOR
D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
D12 INSTALL NEW POLE MOUNTED RDS CABINET
D13 INSTALL RADAR DETECTION SYSTEM
D14 INSTALL VIDEO REMOTE MANAGEMENT CARD
D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
D16 INSTALL BLUETOOTH DETECTION SYSTEM
W1 EVP DETECTOR CABLE(S)
W2 EVP CONFIRMATION BEACON POWER CABLE(S)
W3 EVP CONFIRMATION LAMP POWER CABLE(S)
W4 VIDEO DETECTOR CABLE(S)
W5 2C DETECTOR CABLE(S)
W6 SMFO CABLE
W7 SMFO TRUNK CABLE
W9 DROP CABLES (6-FIBER)
W11 RDS CABLE
W13 COIL 50' OF SMFO CABLE
W14 16 CONDUCTOR CABLE
3 INSTALL 2" RISER INTO BOTTOM OF CABINET
4 INSTALL 2" RISER WITH WEATHERHEAD
7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
9 INSTALL 2" PVC CONDUIT
10 JACK AND BORE 2" CONDUIT
11 INSTALL 3" PVC CONDUIT
13 INSTALL 3" RISER WITH WEATHERHEAD
14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
16 JACK AND BORE 3" CONDUIT
17 INSTALL 3" RISER INTO BOTTOM OF CABINET
18 INSTALL 3" RGS CONDUIT
23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
25 INSTALL CABLES IN EXISTING WEATHERHEAD
26 INSTALL CABLES IN EXISTING POLE
27 INSTALL CABLES IN PROPOSED POLE
29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
32 ATTACH CONDUIT TO BRIDGE

IL-11




DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
YALE RD. AT SYCAMORE VIEW RD.
INTERSECTION LAYOUT

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: 1"=20'
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: CITY OF BARTLETT SHEET 35 OF 72

Kimley»Horn


NOTES:

- POLE 2: TREE TRIMMING REQUIRED FOR CAMERA INSTALLATION.
- ALL CONDUIT WORK IS SCHEMATIC AND MUST BE PERFORMED WITHIN THE EXISTING R.O.W.



REMOVAL DIAGRAM

- * EXISTING SIGNAL POLES AND CONTROLLER CABINET TO REMAIN.
- TURN OFF STOP BAR VEHICLE DETECTOR CHANNELS ON EXISTING AMPLIFIERS IN CABINET.
 - ADVANCE DETECTION AMPLIFIERS TO REMAIN.



EXISTING SIGNAL HEAD TYPES



(2P) (4P)




(A)



(B)

EXISTING OVERHEAD SIGNS




PHASE DIAGRAM

PREEMPT TABLE	
DETECTOR	PHASE(S) CALLED
2	2 & 6
4	4 & 8
6	2 & 6
8	4 & 8

ZONE	MODE	ZONE	MODE
01-1	PRESENCE	05-1	PRESENCE
02-1	PRESENCE	06-1	PRESENCE
02-2	PRESENCE	06-2	PRESENCE
02-3*	PRESENCE	06-3*	PRESENCE
03-1	PRESENCE	07-1	PRESENCE
04-1	PRESENCE	08-1	PRESENCE
04-2	PRESENCE	08-2	PRESENCE
04-3	PRESENCE	08-3	PRESENCE

* 5 SECOND DELAY

ZONE ASSIGNMENT CHART



GENERAL WIRING DIAGRAM

- △ NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.

REVISIONS		
DATE	DESCRIPTIONS	APPROVED



- B1 RETAIN AND MODIFY EXISTING CABINET
- B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
- B7 INSTALL FIBER DISTRIBUTION BOX
- B9 INSTALL TRAFFIC SIGNAL PULLBOX
- B10 INSTALL FIBER OPTIC PULLBOX TYPE A
- B11 INSTALL FIBER OPTIC PULLBOX TYPE B
- B13 INSTALL 20" PEDESTAL POLE
- B15 MLGW POWER SERVICE CONNECTION
- B16 INSTALL JUNCTION BOX
- C2 INSTALL 8-PHASE CONTROLLER
- C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5 INSTALL FIBER OPTIC MODEM
- C6 INSTALL ETHERNET CABINET SWITCH
- C7 INSTALL SERIAL DEVICE SERVER
- D1 INSTALL EVP DETECTOR
- D2 INSTALL EVP CONFIRMATION BEACON
- D3 INSTALL EVP CONFIRMATION LAMP
- D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8 INSTALL EVP PHASE SELECTOR
- D9 INSTALL VIDEO DETECTION PROCESSOR
- D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12 INSTALL NEW POLE MOUNTED RDS CABINET
- D13 INSTALL RADAR DETECTION SYSTEM
- D14 INSTALL VIDEO REMOTE MANAGEMENT CARD
- D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- D16 INSTALL BLUETOOTH DETECTION SYSTEM
- W1 EVP DETECTOR CABLE(S)
- W2 EVP CONFIRMATION BEACON POWER CABLE(S)
- W3 EVP CONFIRMATION LAMP POWER CABLE(S)
- W4 VIDEO DETECTOR CABLE(S)
- W5 2C DETECTOR CABLE(S)
- W6 SMFO CABLE
- W7 SMFO TRUNK CABLE
- W9 DROP CABLES (6-FIBER)
- W11 RDS CABLE
- W13 COIL 50' OF SMFO CABLE
- W14 16 CONDUCTOR CABLE
- 3 INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4 INSTALL 2" RISER WITH WEATHERHEAD
- 7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9 INSTALL 2" PVC CONDUIT
- 10 JACK AND BORE 2" CONDUIT
- 11 INSTALL 3" PVC CONDUIT
- 13 INSTALL 3" RISER WITH WEATHERHEAD
- 14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 16 JACK AND BORE 3" CONDUIT
- 17 INSTALL 3" RISER INTO BOTTOM OF CABINET
- 18 INSTALL 3" RGS CONDUIT
- 23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25 INSTALL CABLES IN EXISTING WEATHERHEAD
- 26 INSTALL CABLES IN EXISTING POLE
- 27 INSTALL CABLES IN PROPOSED POLE
- 29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32 ATTACH CONDUIT TO BRIDGE

IL-12



DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
YALE RD. AT BARTLETT BLVD.
INTERSECTION LAYOUT

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: 1"=20'
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: CITY OF BARTLETT

DRAWING NAME: K:\WEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bia Set 5\Plans\BldSet 5-37-IL-13-Yale at Altruria.dwg Layout Jan 30, 2015 3:27PM BY: blaine.lynch


NOTES:

- POLE 2: CONTRACTOR TO COORDINATE CAMERA INSTALLATION WITH MLGW AND ENGINEER FOR POTENTIAL OVERHEAD UTILITY CONFLICTS.
- ALL CONDUIT WORK IS SCHEMATIC AND MUST BE PERFORMED WITHIN THE EXISTING R.O.W.




REMOVAL DIAGRAM

- * EXISTING SIGNAL POLES AND CONTROLLER CABINET TO REMAIN.
- TURN OFF STOP BAR VEHICLE DETECTOR CHANNELS ON EXISTING AMPLIFIERS IN CABINET.
 - ADVANCE DETECTION AMPLIFIERS TO REMAIN.
 - REMOVE EXISTING CAMERA ON POLE 4.



EXISTING SIGNAL HEAD TYPES




PHASE DIAGRAM

PREEMPT TABLE	
DETECTOR	PHASE(S) CALLED
2	2 & 6
4	4 & 8
6	2 & 6
8	4 & 8

ZONE	MODE	ZONE	MODE
ø1-1	PRESENCE	ø5-1	PRESENCE
ø2-1	PRESENCE	ø6-1	PRESENCE
ø2-2	PRESENCE	ø6-2	PRESENCE
ø3-1	PRESENCE	ø7-1	PRESENCE
ø4-1	PRESENCE	ø8-1	PRESENCE
ø4-2*	PRESENCE		


* 5 SECOND DELAY

ZONE ASSIGNMENT CHART



GENERAL WIRING DIAGRAM

- NUMBER OF CABLES, LOOPS, ETC.
- NUMBER OF CONDUCTORS, PAIRS, ETC.



EXISTING OVERHEAD SIGNS

- RETAIN AND MODIFY EXISTING CABINET
- INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- INSTALL WEATHER PROOF SPLICE ENCLOSURE
- INSTALL FIBER DISTRIBUTION BOX
- INSTALL TRAFFIC SIGNAL PULLBOX
- INSTALL FIBER OPTIC PULLBOX TYPE A
- INSTALL FIBER OPTIC PULLBOX TYPE B
- INSTALL 20" PEDESTAL POLE
- MLGW POWER SERVICE CONNECTION
- INSTALL JUNCTION BOX
- INSTALL 8-PHASE CONTROLLER
- REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- INSTALL FIBER OPTIC MODEM
- INSTALL ETHERNET CABINET SWITCH
- INSTALL SERIAL DEVICE SERVER
- INSTALL EVP DETECTOR
- INSTALL EVP CONFIRMATION BEACON
- INSTALL EVP CONFIRMATION LAMP
- INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- INSTALL EVP PHASE SELECTOR
- INSTALL VIDEO DETECTION PROCESSOR
- INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- INSTALL NEW POLE MOUNTED RDS CABINET
- INSTALL RADAR DETECTION SYSTEM
- INSTALL VIDEO REMOTE MANAGEMENT CARD
- INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- INSTALL BLUETOOTH DETECTION SYSTEM
- EVP DETECTOR CABLE(S)
- EVP CONFIRMATION BEACON POWER CABLE(S)
- EVP CONFIRMATION LAMP POWER CABLE(S)
- VIDEO DETECTOR CABLE(S)
- 2C DETECTOR CABLE(S)
- SMFO CABLE
- SMFO TRUNK CABLE
- DROP CABLES (6-FIBER)
- RDS CABLE
- COIL 50' OF SMFO CABLE
- 16 CONDUCTOR CABLE
- INSTALL 2" RISER INTO BOTTOM OF CABINET
- INSTALL 2" RISER WITH WEATHERHEAD
- INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- INSTALL 2" PVC CONDUIT
- JACK AND BORE 2" CONDUIT
- INSTALL 3" PVC CONDUIT
- INSTALL 3" RISER WITH WEATHERHEAD
- INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- JACK AND BORE 3" CONDUIT
- INSTALL 3" RISER INTO BOTTOM OF CABINET
- INSTALL 3" RGS CONDUIT
- INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- INSTALL CABLES IN EXISTING WEATHERHEAD
- INSTALL CABLES IN EXISTING POLE
- INSTALL CABLES IN PROPOSED POLE
- INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- ATTACH CONDUIT TO BRIDGE

IL-13

REVISIONS		
DATE	DESCRIPTIONS	APPROVED



DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
YALE RD. AT ALTRURIA RD.
INTERSECTION LAYOUT




SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: 1"=20'
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: CITY OF BARTLETT

Kimley»Horn

DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bld Set 5\Plans\BldSet 5-38-IL-14-Yale at Kirby Whitten.dwg Layout Jan 30, 2015 3:28PM BY: blaine.lynn

NOTES:

- 1) ALL CONDUIT WORK IS SCHEMATIC AND MUST BE PERFORMED WITHIN THE EXISTING R.O.W.




PHASE DIAGRAM

PREEMPT TABLE	
DETECTOR	PHASE(S) CALLED
2	2 & 6
4	4 & 8
6	2 & 6
8	4 & 8

ZONE	MODE	ZONE	MODE
01-1	PRESENCE	05-1	PRESENCE
02-1	PRESENCE	06-1	PRESENCE
02-2	PRESENCE	06-2	PRESENCE
02-3	PRESENCE	06-3	PRESENCE
03-1	PRESENCE	07-1	PRESENCE
04-1	PRESENCE	08-1	PRESENCE
04-2	PRESENCE	08-2	PRESENCE

ZONE ASSIGNMENT CHART



GENERAL WIRING DIAGRAM

- △ NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.

REVISIONS		
DATE	DESCRIPTIONS	APPROVED




- B1 RETAIN AND MODIFY EXISTING CABINET
- B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6 INSTALL WEATHER PROOF SPICE ENCLOSURE
- B7 INSTALL FIBER DISTRIBUTION BOX
- B9 INSTALL TRAFFIC SIGNAL PULLBOX
- B10 INSTALL FIBER OPTIC PULLBOX TYPE A
- B11 INSTALL FIBER OPTIC PULLBOX TYPE B
- B13 INSTALL 20" PEDESTAL POLE
- B15 MLGW POWER SERVICE CONNECTION
- B16 INSTALL JUNCTION BOX
- C2 INSTALL 8-PHASE CONTROLLER
- C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5 INSTALL FIBER OPTIC MODEM
- C6 INSTALL ETHERNET CABINET SWITCH
- C7 INSTALL SERIAL DEVICE SERVER
- D1 INSTALL EVP DETECTOR
- D2 INSTALL EVP CONFIRMATION BEACON
- D3 INSTALL EVP CONFIRMATION LAMP
- D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8 INSTALL EVP PHASE SELECTOR
- D9 INSTALL VIDEO DETECTION PROCESSOR
- D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12 INSTALL NEW POLE MOUNTED RDS CABINET
- D13 INSTALL RADAR DETECTION SYSTEM
- D14 INSTALL VIDEO REMOTE MANAGEMENT CARD
- D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- D16 INSTALL BLUETOOTH DETECTION SYSTEM
- W1 EVP DETECTOR CABLE(S)
- W2 EVP CONFIRMATION BEACON POWER CABLE(S)
- W3 EVP CONFIRMATION LAMP POWER CABLE(S)
- W4 VIDEO DETECTOR CABLE(S)
- W5 2C DETECTOR CABLE(S)
- W6 SMFO CABLE
- W7 SMFO TRUNK CABLE
- W9 DROP CABLES (6-FIBER)
- W11 RDS CABLE
- W13 COIL 50' OF SMFO CABLE
- W14 16 CONDUCTOR CABLE
- 3 INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4 INSTALL 2" RISER WITH WEATHERHEAD
- 7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9 INSTALL 2" PVC CONDUIT
- 10 JACK AND BORE 2" CONDUIT
- 11 INSTALL 3" PVC CONDUIT
- 13 INSTALL 3" RISER WITH WEATHERHEAD
- 14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 16 JACK AND BORE 3" CONDUIT
- 17 INSTALL 3" RISER INTO BOTTOM OF CABINET
- 18 INSTALL 3" RGS CONDUIT
- 23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25 INSTALL CABLES IN EXISTING WEATHERHEAD
- 26 INSTALL CABLES IN EXISTING POLE
- 27 INSTALL CABLES IN PROPOSED POLE
- 29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32 ATTACH CONDUIT TO BRIDGE

IL-14


DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
YALE RD. AT KIRBY WHITTEN RD.
INTERSECTION LAYOUT

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: 1"=20'
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: CITY OF BARTLETT SHEET 38 OF 72



REMOVAL DIAGRAM

- * EXISTING SIGNAL POLES AND CONTROLLER CABINET TO REMAIN.
- TURN OFF STOP BAR VEHICLE DETECTOR CHANNELS ON EXISTING AMPLIFIERS IN CABINET.
- ADVANCE DETECTION AMPLIFIERS TO REMAIN.



EXISTING SIGNAL HEAD TYPES





EXISTING OVERHEAD SIGNS

DRAWING NAME: K:\WEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bld Set 5\Plans\BldSet 5-39-IL-15-Yale at US-70.dwg Layout Jan 30, 2015 3:28PM BY: blaine.lynn


NOTES:

- 1) ALL CONDUIT WORK IS SCHEMATIC AND MUST BE PERFORMED WITHIN THE EXISTING R.O.W.



REMOVAL DIAGRAM




- * EXISTING SIGNAL POLES AND CONTROLLER CABINET TO REMAIN.
- TURN OFF STOP BAR VEHICLE DETECTOR CHANNELS ON EXISTING AMPLIFIERS IN CABINET.
- ADVANCE DETECTION AMPLIFIERS TO REMAIN.



DRAWING NAME: K:\VEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bld Set 5\Plans\BldSet 5-40-IL-16-Yale at Brother.dwg Layout Jan 30, 2015 3:28PM BY: blaine.lynch


NOTES:

- 1) ALL CONDUIT WORK IS SCHEMATIC AND MUST BE PERFORMED WITHIN THE EXISTING R.O.W.






REMOVAL DIAGRAM


- * EXISTING SIGNAL POLES AND CONTROLLER CABINET TO REMAIN.
- TURN OFF STOP BAR VEHICLE DETECTOR CHANNELS ON EXISTING AMPLIFIERS IN CABINET.
- ADVANCE DETECTION AMPLIFIERS TO REMAIN.



EXISTING SIGNAL HEAD TYPES



EXISTING OVERHEAD SIGNS




PHASE DIAGRAM

PREEMPT TABLE	
DETECTOR	PHASE(S) CALLED
2	2 & 6
4	4
6	2 & 6

ZONE	MODE	ZONE	MODE
ø1-1	PRESENCE	ø4-2	PRESENCE
ø2-1	PRESENCE	ø4-3*	PRESENCE
ø2-2	PRESENCE	ø6-1	PRESENCE
ø4-1	PRESENCE	ø6-2	PRESENCE

* 5 SECOND DELAY

ZONE ASSIGNMENT CHART



GENERAL WIRING DIAGRAM

- △ NUMBER OF CABLES, LOOPS, ETC.
X NUMBER OF CONDUCTORS, PAIRS, ETC.

REVISIONS		
DATE	DESCRIPTIONS	APPROVED



- B1 RETAIN AND MODIFY EXISTING CABINET
- B3 INSTALL NEW BASE MOUNTED CONTROLLER CABINET
- B6 INSTALL WEATHER PROOF SPLICE ENCLOSURE
- B7 INSTALL FIBER DISTRIBUTION BOX
- B9 INSTALL TRAFFIC SIGNAL PULLBOX
- B10 INSTALL FIBER OPTIC PULLBOX TYPE A
- B11 INSTALL FIBER OPTIC PULLBOX TYPE B
- B13 INSTALL 20" PEDESTAL POLE
- B15 MLGW POWER SERVICE CONNECTION
- B16 INSTALL JUNCTION BOX
- C2 INSTALL 8-PHASE CONTROLLER
- C4 REMOVE EXISTING CONTROLLER AND INSTALL NEW CONTROLLER
- C5 INSTALL FIBER OPTIC MODEM
- C6 INSTALL ETHERNET CABINET SWITCH
- C7 INSTALL SERIAL DEVICE SERVER
- D1 INSTALL EVP DETECTOR
- D2 INSTALL EVP CONFIRMATION BEACON
- D3 INSTALL EVP CONFIRMATION LAMP
- D4 INSTALL VIDEO DETECTION CAMERA WITH TYPE 1 MOUNT
- D5 INSTALL VIDEO DETECTION CAMERA WITH TYPE 2 MOUNT
- D6 INSTALL VIDEO DETECTION CAMERA WITH TYPE 3 MOUNT
- D8 INSTALL EVP PHASE SELECTOR
- D9 INSTALL VIDEO DETECTION PROCESSOR
- D10 INSTALL DETECTOR AMPLIFIER (4-CHANNEL) IN CABINET
- D11 REUSE SYSTEM DETECTOR AMPLIFIER(S) (SEE REMOVAL DIAGRAM)
- D12 INSTALL NEW POLE MOUNTED RDS CABINET
- D13 INSTALL RADAR DETECTION SYSTEM
- D14 INSTALL VIDEO REMOTE MANAGEMENT CARD
- D15 INSTALL NEW SECONDARY POLE MOUNTED RDS CABINET
- D16 INSTALL BLUETOOTH DETECTION SYSTEM
- W1 EVP DETECTOR CABLE(S)
- W2 EVP CONFIRMATION BEACON POWER CABLE(S)
- W3 EVP CONFIRMATION LAMP POWER CABLE(S)
- W4 VIDEO DETECTOR CABLE(S)
- W5 2C DETECTOR CABLE(S)
- W6 SMFO CABLE
- W7 SMFO TRUNK CABLE
- W9 DROP CABLES (6-FIBER)
- W11 RDS CABLE
- W13 COIL 50' OF SMFO CABLE
- W14 16 CONDUCTOR CABLE
- 3 INSTALL 2" RISER INTO BOTTOM OF CABINET
- 4 INSTALL 2" RISER WITH WEATHERHEAD
- 7 INSTALL 2" RGS CONDUIT ON EXISTING STRUCTURE
- 8 INSTALL 2" CONDUIT INTO EXTERIOR OF CABINET
- 9 INSTALL 2" PVC CONDUIT
- 10 JACK AND BORE 2" CONDUIT
- 11 INSTALL 3" PVC CONDUIT
- 13 INSTALL 3" RISER WITH WEATHERHEAD
- 14 INSTALL 3" CONDUIT INTO EXTERIOR OF CABINET
- 16 JACK AND BORE 3" CONDUIT
- 17 INSTALL 3" RISER INTO BOTTOM OF CABINET
- 18 INSTALL 3" RGS CONDUIT
- 23 INSTALL CABLES IN EXISTING POLE IN EXISTING WEATHERHEAD
- 24 INSTALL CABLES IN EXISTING POLE IN PROPOSED WEATHERHEAD
- 25 INSTALL CABLES IN EXISTING WEATHERHEAD
- 26 INSTALL CABLES IN EXISTING POLE
- 27 INSTALL CABLES IN PROPOSED POLE
- 29 INSTALL CABLES IN EXISTING CONDUIT(S) INTO CABINET
- 30 LASH TO EXISTING MESSENGER WIRE/SPANWIRE
- 32 ATTACH CONDUIT TO BRIDGE


IL-16

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
YALE RD. AT BROTHER BLVD.
INTERSECTION LAYOUT

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: 1"=20'
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: CITY OF BARTLETT

Kimley»Horn

DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bld Set 5\Plans\BldSet 5-41-SD-01.dwg Layout1 Jan 30, 2015 3:28PM BY: blaine.lynn



* DENOTES CABLES AND SPLICE ENCLOSURES INSTALLED AS PART OF PROJECT 112875 (STP - JACKSON AVE SIGNAL SYSTEM)

* DENOTES CABLE OR SPLICE ENCLOSURE TO BE INSTALLED AS PART OF PROJECT 040723 (CMAQ YEAR 3 BID SET 1).

NOTES:
1. FIBER INTERCONNECT CENTER RACKS ARE SCHEMATIC ONLY ACTUAL EQUIPMENT FORM MAY VARY.

COLOR CODE TIA/EIA 598-A		X - FUSION SPLICE INDIVIDUAL FIBER	
(1) BLUE	(7) RED	BUFFER TUBE	SPLICE OR EXPRESS ENTIRE BUFFER TUBE AS NOTED
(2) ORANGE	(8) BLACK		
(3) GREEN	(9) YELLOW	————	ACTIVE EXISTING FIBER
(4) BROWN	(10) VIOLET	————	ACTIVE FIBER
(5) SLATE	(11) ROSE	—— ———	INACTIVE FIBER
(6) WHITE	(12) AQUA	—— X ——	CONNECTION/SPLICE TO BE MADE BY OTHERS.

SPLICE DIAGRAM FOR
HUB CABINET F
JACKSON AVE. AT
TREZEVANT ST.

REVISIONS		
DATE	DESCRIPTIONS	APPROVED



Kimley»Horn

SD-01

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
SPLICE DIAGRAM


SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: N.T.S.
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: _____ SHEET 41 OF 72

DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bid Set 5\Plans\BidSet 5-42-SD-02.dwg Jan 30, 2015 3:28PM BY: blaine.lynnch Layout1

- * DENOTES CABLES AND SPLICE ENCLOSURES INSTALLED AS PART OF PROJECT 040723 (CMAQ YEAR 3 - BID SET 1)
- ** DENOTES CABLES AND SPLICE ENCLOSURES INSTALLED AS PART OF PROJECT 112875 (STP - JACKSON AVE SIGNAL SYSTEM)

NOTES:
1.FIBER INTERCONNECT CENTER RACKS ARE SCHEMATIC ONLY ACTUAL EQUIPMENT FORM MAY VARY.

COLOR CODE TIA/EIA 598-A		X - FUSION SPLICE INDIVIDUAL FIBER	
(1) BLUE	(7) RED		SPLICE OR EXPRESS ENTIRE BUFFER TUBE AS NOTED
(2) ORANGE	(8) BLACK		ACTIVE EXISTING FIBER
(3) GREEN	(9) YELLOW		ACTIVE FIBER
(4) BROWN	(10) VIOLET		INACTIVE FIBER
(5) SLATE	(11) ROSE		CONNECTION/SPLICE TO BE MADE BY OTHERS.
(6) WHITE	(12) AQUA		



SPLICE DIAGRAM FOR
INTERSECTION #8157
JACKSON AVE AT
TREZEVANT ST.

REVISIONS		
DATE	DESCRIPTIONS	APPROVED





Kimley»Horn

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.

SPLICE DIAGRAM

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: N.T.S.
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: SHEET 42 OF 72

DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bld Set 5\Plans\BldSet 5-43-SD-03.dwg Jan 30, 2015 3:28PM BY: blaine.lynn



* DENOTES CABLES AND SPLICE ENCLOSURES INSTALLED AS PART OF PROJECT 112875 (STP - JACKSON AVE SIGNAL SYSTEM)

NOTES:
1. FIBER INTERCONNECT CENTER RACKS ARE SCHEMATIC ONLY ACTUAL EQUIPMENT FORM MAY VARY.

COLOR CODE	
TIA/EIA 598-A	
(1) BLUE	(7) RED
(2) ORANGE	(8) BLACK
(3) GREEN	(9) YELLOW
(4) BROWN	(10) VIOLET
(5) SLATE	(11) ROSE
(6) WHITE	(12) AQUA

X - FUSION SPLICE INDIVIDUAL FIBER

BUFFER TUBE SPLICE OR EXPRESS ENTIRE BUFFER TUBE AS NOTED

— ACTIVE EXISTING FIBER


— ACTIVE FIBER

— INACTIVE FIBER

— CONNECTION/SPLICE TO BE MADE BY OTHERS.

SPICE DIAGRAM FOR INTERSECTION #8448 JACKSON AVE. AT TREZEVANT ST.

REVISIONS		
DATE	DESCRIPTIONS	APPROVED



Kimley»Horn


SD-03

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.

SPLICE DIAGRAM

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: N.T.S.
DESIGNED: KHA DATE: 12/13 CHECKED: JEC DATE: 12/13
JURISDICTION: SHEET 43 OF 72

DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bia Set 5\Plans\BldSet 5-44-SD-04.dwg Jan 30, 2015 3:28PM BY: blaine,lynch Layout1



SPLICE DIAGRAM FOR
INTERSECTION #8445
JACKSON AVE. AT
MEAGHER ST.

* DENOTES EXISTING CABLES OR
 SPLICE ENCLOSURES

NOTES:
1. FIBER INTERCONNECT CENTER RACKS ARE
 SCHEMATIC ONLY ACTUAL EQUIPMENT FORM
 MAY VARY.

COLOR CODE
TIA/EIA 598-A

(1) BLUE

(2) ORANGE

(3) GREEN

(4) BROWN

(5) SLATE

(6) WHITE

(7) RED

(8) BLACK

(9) YELLOW

(10) VIOLET

(11) ROSE

(12) AQUA

X - FUSION SPLICE INDIVIDUAL FIBER


BUFFER TUBE

SPLICE OR EXPRESS ENTIRE
BUFFER TUBE AS NOTED

ACTIVE FIBER

INACTIVE FIBER

CONNECTION/SPLICE TO
BE MADE BY OTHERS.



SPLICE DIAGRAM FOR
INTERSECTION #8443
JACKSON AVE. AT
WARFORD ST.

REVISIONS

DATE	DESCRIPTIONS	APPROVED


Kimley»Horn

SD-04

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
SPLICE DIAGRAM

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: N.T.S.
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: SHEET 44 OF 72

DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bld Set 5\Plans\BldSet 5-45-SD-05.dwg Jan 30, 2015 3:28PM BY: blaine,lynch Layout1




SPLICE DIAGRAM FOR
RADAR DETECTION SYSTEM #1

* DENOTES EXISTING CABLES OR
 SPLICE ENCLOSURES

NOTES:
1. FIBER INTERCONNECT CENTER RACKS ARE
 SCHEMATIC ONLY ACTUAL EQUIPMENT FORM
 MAY VARY.

COLOR CODE TIA/EIA 598-A		X - FUSION SPLICE INDIVIDUAL FIBER	
(1) BLUE	(7) RED	BUFFER TUBE	SPLICE OR EXPRESS ENTIRE BUFFER TUBE AS NOTED
(2) ORANGE	(8) BLACK		
(3) GREEN	(9) YELLOW	— — — —	ACTIVE FIBER
(4) BROWN	(10) VIOLET		
(5) SLATE	(11) ROSE	— X — —	INACTIVE FIBER CONNECTION/SPLICE TO BE MADE BY OTHERS.
(6) WHITE	(12) AQUA		



SPLICE DIAGRAM FOR
INTERSECTION #8442
JACKSON AVE. AT
POPE ST.

REVISIONS		
DATE	DESCRIPTIONS	APPROVED



Kimley»Horn


DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.

SPLICE DIAGRAM

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: N.T.S.
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: _____ SHEET 45 OF 72

SD-05

DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bia Set 5\Plans\BldSet 5-46-SD-06.dwg Jan 30, 2015 3:28PM BY: blaine,lynch Layout1



SPLICE DIAGRAM FOR
INTERSECTION #8155
JACKSON AVE. AT
HUDSON ST.

* DENOTES EXISTING CABLES OR
 SPLICE ENCLOSURES

NOTES:
1. FIBER INTERCONNECT CENTER RACKS ARE
 SCHEMATIC ONLY ACTUAL EQUIPMENT FORM
 MAY VARY.

COLOR CODE
TIA/EIA 598-A

(1) BLUE

(2) ORANGE

(3) GREEN

(4) BROWN

(5) SLATE

(6) WHITE

(7) RED

(8) BLACK

(9) YELLOW

(10) VIOLET

(11) ROSE

(12) AQUA

X - FUSION SPLICE INDIVIDUAL FIBER


BUFFER TUBE

SPLICE OR EXPRESS ENTIRE
BUFFER TUBE AS NOTED

ACTIVE FIBER

INACTIVE FIBER

CONNECTION/SPLICE TO
BE MADE BY OTHERS.



SPLICE DIAGRAM FOR
INTERSECTION #8440
JACKSON AVE. AT
MACON RD.

REVISIONS

DATE	DESCRIPTIONS	APPROVED

DALLAS

AGRICULTURE

1/19/15

COMMISSION


STATE OF TENNESSEE

Kimley»Horn

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
SPLICE DIAGRAM

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: N.T.S.
DESIGNED: KHA DATE: 12/13 CHECKED: JEC DATE: 12/13
JURISDICTION: SHEET 46 OF 72

DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bld Set 5\Plans\BldSet 5-47-SD-07.dwg Jan 30, 2015 3:28PM BY: blaine,lynch Layout1




SPLICE DIAGRAM FOR
RADAR DETECTION SYSTEM #2

* DENOTES EXISTING CABLES OR
 SPLICE ENCLOSURES


NOTES:
1. FIBER INTERCONNECT CENTER RACKS ARE
 SCHEMATIC ONLY ACTUAL EQUIPMENT FORM
 MAY VARY.

COLOR CODE TIA/EIA 598-A		X - FUSION SPLICE INDIVIDUAL FIBER	
(1) BLUE	(7) RED	BUFFER TUBE	SPLICE OR EXPRESS ENTIRE BUFFER TUBE AS NOTED
(2) ORANGE	(8) BLACK		
(3) GREEN	(9) YELLOW	— — — —	ACTIVE FIBER
(4) BROWN	(10) VIOLET		
(5) SLATE	(11) ROSE	— X — —	INACTIVE FIBER CONNECTION/SPLICE TO BE MADE BY OTHERS.
(6) WHITE	(12) AQUA		



SPLICE DIAGRAM FOR
INTERSECTION #8438
JACKSON AVE. AT
BAYLISS AVE.

REVISIONS		
DATE	DESCRIPTIONS	APPROVED




Kimley»Horn

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
SPLICE DIAGRAM

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: N.T.S.
DESIGNED: KHA DATE: 12/13 CHECKED: JEC DATE: 12/13
JURISDICTION: _____ SHEET 47 OF 72

SD-07

DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bld Set 5\Plans\BldSet 5-48-SD-08.dwg Layout1 Jan 30, 2015 3:29PM BY: blaine.lynn



SPLICE DIAGRAM FOR
INTERSECTION #8436
JACKSON AVE. AT
ORCHI RD.

* DENOTES EXISTING CABLES OR
 SPLICE ENCLOSURES

NOTES:
1. FIBER INTERCONNECT CENTER RACKS ARE
 SCHEMATIC ONLY ACTUAL EQUIPMENT FORM
 MAY VARY.

COLOR CODE
TIA/EIA 598-A

(1) BLUE

(2) ORANGE

(3) GREEN

(4) BROWN

(5) SLATE

(6) WHITE

(7) RED

(8) BLACK

(9) YELLOW

(10) VIOLET

(11) ROSE

(12) AQUA

X - FUSION SPLICE INDIVIDUAL FIBER


BUFFER TUBE

SPLICE OR EXPRESS ENTIRE
BUFFER TUBE AS NOTED

ACTIVE FIBER

INACTIVE FIBER

CONNECTION/SPLICE TO
BE MADE BY OTHERS.



SPLICE DIAGRAM FOR
INTERSECTION #8435
JACKSON AVE. AT
WALES AVE.

REVISIONS		
DATE	DESCRIPTIONS	APPROVED



Kimley»Horn


SD-08

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.

SPLICE DIAGRAM

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: N.T.S.
DESIGNED: KHA DATE: 12/13 CHECKED: JEC DATE: 12/13
JURISDICTION: SHEET 48 OF 72

DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\System\Bld Set 5\Plans\BldSet 5-49-SD-09.dwg Jan 30, 2015 3:29PM BY: blaine.lynch




SPLICE DIAGRAM FOR
INTERSECTION #5506
YALE RD. AT
SYCAMORE VIEW RD./
MEMPHIS ARLINGTON RD.

* DENOTES EXISTING CABLES OR
SPLICE ENCLOSURES

NOTES:
1. FIBER INTERCONNECT CENTER RACKS ARE
SCHEMATIC ONLY ACTUAL EQUIPMENT FORM
MAY VARY.

COLOR CODE TIA/EIA 598-A	X - FUSION SPLICE INDIVIDUAL FIBER
(1) BLUE	(7) RED
(2) ORANGE	(8) BLACK
(3) GREEN	(9) YELLOW
(4) BROWN	(10) VIOLET
(5) SLATE	(11) ROSE
(6) WHITE	(12) AQUA
BUFFER TUBE	SPLICE OR EXPRESS ENTIRE BUFFER TUBE AS NOTED
—	ACTIVE FIBER
—	INACTIVE FIBER
X	CONNECTION/SPLICE TO BE MADE BY OTHERS.



SPLICE DIAGRAM FOR
INTERSECTION #6100
YALE RD. AT
BARTLETT BLVD.

REVISIONS		
DATE	DESCRIPTIONS	APPROVED




Kimley»Horn

SD-09

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
SPLICE DIAGRAM

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: N.T.S.
DESIGNED: KHA DATE: 12/13 CHECKED: JEC DATE: 12/13
JURISDICTION: SHEET 49 OF 72

DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bld Set 5\Plans\BldSet 5-50-SD-10.dwg Layout1 Jan 30, 2015 3:29PM BY: blaine.lynn



SPLICE DIAGRAM FOR
RADAR DETECTION SYSTEM #3

* DENOTES EXISTING CABLES OR
SPLICE ENCLOSURES

NOTES:
1. FIBER INTERCONNECT CENTER RACKS ARE
SCHEMATIC ONLY ACTUAL EQUIPMENT FORM
MAY VARY.

COLOR CODE
TIA/EIA 598-A

X - FUSION SPLICE INDIVIDUAL FIBER

BUFFER TUBE

SPLICE OR EXPRESS ENTIRE
BUFFER TUBE AS NOTED

ACTIVE FIBER

INACTIVE FIBER

CONNECTION/SPLICE TO
BE MADE BY OTHERS.

(1) BLUE

(2) ORANGE

(3) GREEN

(4) BROWN

(5) SLATE

(6) WHITE

(7) RED


(8) BLACK

(9) YELLOW

(10) VIOLET

(11) ROSE

(12) AQUA



SPLICE DIAGRAM FOR
INTERSECTION #6103
YALE RD. AT
ALTRURIA RD.

REVISIONS

DATE	DESCRIPTIONS	APPROVED

DALLAS A

AGRICULTURE

1/9/15

COMMISSIONER

STATE OF TENNESSEE

Kimley»Horn

SD-10

DIVISION OF PUBLIC WORKS

CONGESTION MANAGEMENT PROGRAM

SIGNAL SYSTEM PROJECT SET #5

SHELBY COUNTY, TN.

SPLICE DIAGRAM

SURVEY: N/A

DATE: N/A

BOOK: N/A

DRAFTED: KHA

DATE: 12/13

SCALE: N.T.S.

DESIGNED: KHA

DATE: 12/13


CHECKED: JFC

DATE: 12/13

JURISDICTION:

SHEET 50 OF 72

DRAWING NAME: K:\VEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bia Set 5\Plans\BldSet 5-51-SD-11.dwg Layout1 Jan 30, 2015 3:29PM BY: blaine.lynch



SPLICE DIAGRAM FOR
INTERSECTION #6106
YALE RD. AT
KIRBY WHITTEN RD.

* DENOTES EXISTING CABLES OR
SPLICE ENCLOSURES

NOTES:
1. FIBER INTERCONNECT CENTER RACKS ARE
SCHEMATIC ONLY ACTUAL EQUIPMENT FORM
MAY VARY.

COLOR CODE
TIA/EIA 598-A

X - FUSION SPLICE INDIVIDUAL FIBER

BUFFER TUBE

SPLICE OR EXPRESS ENTIRE
BUFFER TUBE AS NOTED

ACTIVE FIBER

INACTIVE FIBER

CONNECTION/SPLICE TO
BE MADE BY OTHERS.

(1) BLUE

(2) ORANGE

(3) GREEN

(4) BROWN

(5) SLATE

(6) WHITE

(7) RED


(8) BLACK

(9) YELLOW

(10) VIOLET

(11) ROSE

(12) AQUA



SPLICE DIAGRAM FOR
RADAR DETECTION SYSTEM #4

REVISIONS

DATE	DESCRIPTIONS	APPROVED

DALLAS A

AGRICULTURE

1/9/15

COMMISSION

STATE OF TENNESSEE

Kimley»Horn

SD-11

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
SPLICE DIAGRAM

SURVEY: N/A

DATE: N/A

BOOK: N/A

DRAFTED: KHA

DATE: 12/13

SCALE: N.T.S.

DESIGNED: KHA

DATE: 12/13


CHECKED: JFC

DATE: 12/13

JURISDICTION:

SHEET 51 OF 72

DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bld Set 5\Plans\BldSet 5--52--SD--12.dwg Layout1 Jan 30, 2015 3:29PM BY: blaine.lynn



* DENOTES EXISTING CABLES OR SPLICE ENCLOSURES

NOTES:
1. FIBER INTERCONNECT CENTER RACKS ARE SCHEMATIC ONLY ACTUAL EQUIPMENT FORM MAY VARY.

COLOR CODE	
TIA/EIA 598-A	
(1) BLUE	(7) RED
(2) ORANGE	(8) BLACK
(3) GREEN	(9) YELLOW
(4) BROWN	(10) VIOLET
(5) SLATE	(11) ROSE
(6) WHITE	(12) AQUA


X - FUSION SPLICE INDIVIDUAL FIBER

BUFFER TUBE SPLICE OR EXPRESS ENTIRE BUFFER TUBE AS NOTED


— ACTIVE FIBER

— INACTIVE FIBER

— CONNECTION/SPLICE TO BE MADE BY OTHERS.



REVISIONS		
DATE	DESCRIPTIONS	APPROVED




Kimley»Horn

SD-12

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.

SPLICE DIAGRAM

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: N.T.S.
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: SHEET 52 OF 72




LEGEND

— E — E — EXISTING ELECTRIC LINE
— W — W — EXISTING WATER LINE
— G — G — EXISTING GAS LINE


SOME UTILITY INFORMATION FOR THE WORK AREAS
ARE NOT PROVIDED; CONTRACTOR TO VERIFY UTILITY
LOCATIONS PRIOR TO CONSTRUCTION

THE LOCATION OF SOME UTILITIES FOR THIS AREA
NOT PROVIDED. CONTRACTOR TO VERIFY UTILITY
LOCATION PRIOR TO CONSTRUCTION.



MATCH LINE STA. 12+50 SEE THIS SHEET

MATCH LINE STA. 25+00 SEE DWG. NO. U-02



REVISIONS		
DATE	DESCRIPTIONS	APPROVED


U-01

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVENUE
EXISTING UTILITIES
FROM 0+00 TO 25+00

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: _____ SHEET 53 OF 72

Powers Hill Design
CIVIL ENGINEERING. CIVIL RESPONSIBILITY.



Kimley-Horn and Associates, Inc.



LEGEND

— E — E — EXISTING ELECTRIC LINE
— W — W — EXISTING WATER LINE
— G — G — EXISTING GAS LINE

SOME UTILITY INFORMATION FOR THE WORK AREAS
ARE NOT PROVIDED; CONTRACTOR TO VERIFY UTILITY
LOCATIONS PRIOR TO CONSTRUCTION



REVISIONS		
DATE	DESCRIPTIONS	APPROVED


POWERS HILL DESIGN
CIVIL ENGINEERING, CIVIL RESPONSIBILITY.

Kimley-Horn and Associates, Inc.

U-03

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVENUE
EXISTING UTILITIES
FROM 50+00 TO 75+00



SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: _____ SHEET 55 OF 72



LEGEND

— E — E — EXISTING ELECTRIC LINE
— W — W — EXISTING WATER LINE
— G — G — EXISTING GAS LINE

SOME UTILITY INFORMATION FOR THE WORK AREAS
ARE NOT PROVIDED; CONTRACTOR TO VERIFY UTILITY
LOCATIONS PRIOR TO CONSTRUCTION



REVISIONS		
DATE	DESCRIPTIONS	APPROVED



POWERS HILL DESIGN
CIVIL ENGINEERING. CIVIL RESPONSIBILITY.

**Kimley-Horn
and Associates, Inc.**

U-04


DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVENUE
EXISTING UTILITIES
FROM 75+00 TO 100+00

SURVEY: N/A DATE: N/A BOOK: N/A

DRAFTED: APL DATE: 01/14 SCALE: 1"=50'

DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14



JURISDICTION: _____ SHEET 56 OF 72



LEGEND

— E — E — EXISTING ELECTRIC LINE
— W — W — EXISTING WATER LINE
— G — G — EXISTING GAS LINE

SOME UTILITY INFORMATION FOR THE WORK AREAS ARE NOT PROVIDED; CONTRACTOR TO VERIFY UTILITY LOCATIONS PRIOR TO CONSTRUCTION



REVISIONS		
DATE	DESCRIPTIONS	APPROVED


U-05

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVENUE
EXISTING UTILITIES
FROM 100+00 TO 125+00

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: _____ SHEET 57 OF 72

POWERS HILL DESIGN
CIVIL ENGINEERING. CIVIL RESPONSIBILITY.



Kimley-Horn and Associates, Inc.



LEGEND

— E — E — EXISTING ELECTRIC LINE
— W — W — EXISTING WATER LINE
— G — G — EXISTING GAS LINE

SOME UTILITY INFORMATION FOR THE WORK AREAS ARE NOT PROVIDED; CONTRACTOR TO VERIFY UTILITY LOCATIONS PRIOR TO CONSTRUCTION



REVISIONS		
DATE	DESCRIPTIONS	APPROVED

U-06

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVENUE
EXISTING UTILITIES
FROM 125+00 TO 150+00


SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: SHEET 58 OF 72

POWERS HILL DESIGN
CIVIL ENGINEERING. CIVIL RESPONSIBILITY.

Kimley-Horn and Associates, Inc.

MATCH LINE STA. 150+00 SEE DWG. NO. U-06

THE LOCATION OF SOME UTILITIES FOR THIS AREA NOT PROVIDED. CONTRACTOR TO VERIFY UTILITY LOCATION PRIOR TO CONSTRUCTION.




LEGEND

- E — E — EXISTING ELECTRIC LINE
— W — W — EXISTING WATER LINE
— G — G — EXISTING GAS LINE


SOME UTILITY INFORMATION FOR THE WORK AREAS ARE NOT PROVIDED; CONTRACTOR TO VERIFY UTILITY LOCATIONS PRIOR TO CONSTRUCTION

MATCH LINE STA. 162+50 SEE THIS SHEET

MATCH LINE STA. 162+50 SEE THIS SHEET



MATCH LINE STA. 175+00 SEE DWG. NO. U-08



REVISIONS		
DATE	DESCRIPTIONS	APPROVED



 **POWERS HILL DESIGN**
CIVIL ENGINEERING. CIVIL RESPONSIBILITY.

 **Kimley-Horn
and Associates, Inc.**


U-07

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.

JACKSON AVENUE
EXISTING UTILITIES
FROM 150+00 TO 175+00

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: _____ SHEET 59 OF 72

MATCH LINE STA. 175+00 SEE DWG. NO. U-07





LEGEND

- E — E — EXISTING ELECTRIC LINE
— W — W — EXISTING WATER LINE
— G — G — EXISTING GAS LINE

SOME UTILITY INFORMATION FOR THE WORK AREAS
ARE NOT PROVIDED; CONTRACTOR TO VERIFY UTILITY
LOCATIONS PRIOR TO CONSTRUCTION

MATCH LINE STA. 187+50 SEE THIS SHEET

MATCH LINE STA. 187+50 SEE THIS SHEET



REVISIONS		
DATE	DESCRIPTIONS	APPROVED




POWERS HILL DESIGN
CIVIL ENGINEERING. CIVIL RESPONSIBILITY.

Kimley-Horn and Associates, Inc.

U-08

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
JACKSON AVENUE
EXISTING UTILITIES
FROM 175+00 TO 192+72

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: SHEET 60 OF 72




MATCH LINE STA. 20+00 SEE THIS SHEET

LEGEND


- E — E — EXISTING ELECTRIC LINE
- W — W — EXISTING WATER LINE
- G — G — EXISTING GAS LINE
- W — W — BARTLETT WATER LINE
- SS — SS — SEWER

SOME UTILITY INFORMATION FOR THE WORK AREAS ARE NOT PROVIDED; CONTRACTOR TO VERIFY UTILITY LOCATIONS PRIOR TO CONSTRUCTION




MATCH LINE STA. 20+00 SEE THIS SHEET

MATCH LINE STA. 32+50 SEE DWG. NO. U-10



REVISIONS		
DATE	DESCRIPTIONS	APPROVED



**POWERS HILL DESIGN**
CIVIL ENGINEERING. CIVIL RESPONSIBILITY.

**Kimley-Horn and Associates, Inc.**



U-09

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
YALE ROAD
EXISTING UTILITIES
FROM 8+00 TO 32+50

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: _____ SHEET 61 OF 72

MATCH LINE STA. 32+50 SEE DWG. NO. U-09

MATCH LINE STA. 45+00 SEE THIS SHEET




LEGEND

- E — E — EXISTING ELECTRIC LINE
- W — W — EXISTING WATER LINE
- G — G — EXISTING GAS LINE
- W — W — BARTLETT WATER LINE
- SS — SS — SEWER

SOME UTILITY INFORMATION FOR THE WORK AREAS ARE NOT PROVIDED; CONTRACTOR TO VERIFY UTILITY LOCATIONS PRIOR TO CONSTRUCTION

CONTACT CITY OF MEMPHIS FOR ADDITIONAL SANITARY SEWER INFORMATION

GRAPHIC SCALE



REVISIONS		
DATE	DESCRIPTIONS	APPROVED



 **POWERS HILL DESIGN**
CIVIL ENGINEERING. CIVIL RESPONSIBILITY.

 **Kimley-Horn and Associates, Inc.**

U-10

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
YALE ROAD
EXISTING UTILITIES
FROM 32+50 TO 57+50

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: _____ SHEET 62 OF 72

MATCH LINE STA. 57+50 SEE DWG. NO. U-10

MATCH LINE STA. 70+00 SEE THIS SHEET

LEGEND

- E E EXISTING ELECTRIC LINE
- W W EXISTING WATER LINE
- G G EXISTING GAS LINE
- W -W BARTLETT WATER LINE
- SS SS SEWER


SOME UTILITY INFORMATION FOR THE WORK AREAS
ARE NOT PROVIDED; CONTRACTOR TO VERIFY UTILITY
LOCATIONS PRIOR TO CONSTRUCTION

MATCH LINE STA. 70+00 SEE THIS SHEET


MATCH LINE STA. 82+50 SEE DWG. NO. U-12

THE LOCATION OF SOME UTILITIES FOR THIS AREA
NOT PROVIDED. CONTRACTOR TO VERIFY UTILITY
LOCATION PRIOR TO CONSTRUCTION.

GRAPHIC SCALE



REVISIONS		
DATE	DESCRIPTIONS	APPROVED




POWERS HILL DESIGN
CIVIL ENGINEERING. CIVIL RESPONSIBILITY.

Kimley-Horn and Associates, Inc.

U-11

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
YALE ROAD
EXISTING UTILITIES
FROM 57+50 TO 82+50



SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: SHEET 63 OF 72



LEGEND

— E — E —	EXISTING ELECTRIC LINE
— W — W —	EXISTING WATER LINE
— G — G —	EXISTING GAS LINE
— W — W —	BARTLETT WATER LINE
— SS — SS —	SEWER

SOME UTILITY INFORMATION FOR THE WORK AREAS
ARE NOT PROVIDED; CONTRACTOR TO VERIFY UTILITY
LOCATIONS PRIOR TO CONSTRUCTION



REVISIONS		
DATE	DESCRIPTIONS	APPROVED

U-12

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
YALE ROAD
EXISTING UTILITIES
FROM 82+50 TO 107+50

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: _____ SHEET 64 OF 72

Powers Hill Design
CIVIL ENGINEERING. CIVIL RESPONSIBILITY.

Kimley-Horn and Associates, Inc.

MATCH LINE STA. 107+50 SEE DWG. NO. U-12

THE LOCATION OF SOME UTILITIES FOR THIS AREA NOT PROVIDED. CONTRACTOR TO VERIFY UTILITY LOCATION PRIOR TO CONSTRUCTION.

MATCH LINE STA. 120+00 SEE THIS SHEET


LEGEND

- E E EXISTING ELECTRIC LINE
- W W EXISTING WATER LINE
- G G EXISTING GAS LINE
- W -W BARTLETT WATER LINE
- SS SS SEWER


SOME UTILITY INFORMATION FOR THE WORK AREAS ARE NOT PROVIDED; CONTRACTOR TO VERIFY UTILITY LOCATIONS PRIOR TO CONSTRUCTION

MATCH LINE STA. 120+00 SEE THIS SHEET

MATCH LINE STA. 132+50 SEE DWG. U-14



REVISIONS		
DATE	DESCRIPTIONS	APPROVED




U-13

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
YALE ROAD
EXISTING UTILITIES
FROM 107+50 TO 132+50

POWERS HILL DESIGN
CIVIL ENGINEERING. CIVIL RESPONSIBILITY.



Kimley-Horn and Associates, Inc.

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: SHEET 65 OF 72



- LEGEND**
- E — E — EXISTING ELECTRIC LINE
 - W — W — EXISTING WATER LINE
 - G — G — EXISTING GAS LINE
 - -W- -W- BARTLETT WATER LINE
 - SS — SS — SEWER

SOME UTILITY INFORMATION FOR THE WORK AREAS ARE NOT PROVIDED; CONTRACTOR TO VERIFY UTILITY LOCATIONS PRIOR TO CONSTRUCTION




REVISIONS		
DATE	DESCRIPTIONS	APPROVED

U-14

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
YALE ROAD
EXISTING UTILITIES
FROM 132+50 TO 157+50

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: _____ SHEET 66 OF 72

MATCH LINE STA. 157+50 SEE DWG. NO. U-14





LEGEND

- E — E — EXISTING ELECTRIC LINE
- W — W — EXISTING WATER LINE
- G — G — EXISTING GAS LINE
- W- -W- BARTLETT WATER LINE
- SS — SS — SEWER


SOME UTILITY INFORMATION FOR THE WORK AREAS ARE NOT PROVIDED; CONTRACTOR TO VERIFY UTILITY LOCATIONS PRIOR TO CONSTRUCTION

MATCH LINE STA. 170+00 SEE THIS SHEET

MATCH LINE STA. 170+00 SEE THIS SHEET



REVISIONS		
DATE	DESCRIPTIONS	APPROVED



U-15


DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.
YALE ROAD
EXISTING UTILITIES
FROM 157+50 TO 176+50

POWERS HILL DESIGN
CIVIL ENGINEERING. CIVIL RESPONSIBILITY.

Kimley-Horn and Associates, Inc.


SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: APL DATE: 01/14 SCALE: 1"=50'
DESIGNED: SH DATE: 01/14 CHECKED: SH DATE: 01/14
JURISDICTION: SHEET 67 OF 72

DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal\System\Bld Set 5\Plans\BldSet 5--68--Details--01.dwg Layout1 Jan 30, 2015 3:29PM BY: blaine.lynnch




NOTE:
1. CONTRACTOR SHALL SET DEPTH TO AVOID EXISTING UTILITIES (MINIMUM OF 2' DEPTH)

DETAIL OF JACKED OR BORED CONDUIT
N.T.S.



BACK VIEW SIDE VIEW
9 DETAILS FOR INSTALLING NEW CONDUIT INTO EXISTING BASE MOUNTED CABINET FOUNDATION




14 UNDERGROUND ROUTING DETAILS FOR INSTALLING NEW CONDUIT (OPTION 2)

- NOTES:
1. CONDUIT SIZES SHALL BE AS SHOWN ON PLANS
 2. CABLE ACCESS TO CABINET SHALL BE MADE THROUGH 3" (MIN.) CUT & GROMMETED HOLE
 3. CABINET ENTRANCE CAN BE ON THE BACK OR SIDE OF THE CABINET, AS APPROVED BY THE ENGINEER.
 4. CABLE SHALL AT NO POINT IN ROUTING BE BENT BEYOND MANUFACTURER'S RECOMMENDED MINIMUM BENDING RADIUS

- NOTES:
1. THIS DETAIL IS THE APPROVED METHOD FOR ENTRY INTO A SOLID-BASE CABINET FOUNDATION THAT HAS NO SPARE CONDUITS AVAILABLE. ALL OTHER CASES MUST RECEIVE PRIOR APPROVAL FROM THE CITY OF MEMPHIS.
 2. WALL-MOUNTED JUNCTION BOX SHALL BE A NEMA 3R CONTINUOUS HINGED ENTRY BOX OR APPROVED EQUIVALENT. THE NEMA 3R BOX SHALL BE MADE OF GALVANIZED STEEL WITH A POWDER COATED FINISH AND SHALL HAVE A CONTINUOUS HINGE THAT IS MADE OF GALVANIZED STEEL WITH A STAINLESS STEEL PIN ON THE LEFT SIDE AND CAPTIVE SCREWS ON THE RIGHT SIDE. THE NEMA 3R BOX SHALL HAVE A HASP PROVISION (OR APPROVED ALTERNATE) ON THE RIGHT SIDE FOR PADLOCKING DOOR FOR SECURING THE DOOR.
 3. THE BOX SHALL BE MOUNTED ON THE BACK SIDE OF THE CABINET NEAR THE TOP. ALTERNATIVE LOCATIONS ON THE CABINET TO SECURE THE WALL-MOUNTED JUNCTION BOX MUST HAVE PRIOR APPROVAL BY THE CITY OF MEMPHIS.
 4. CONDUIT STRAP IS NOT TO BE SECURED TO THE CABINET. CONDUIT STRAP MUST BE SECURED TO THE CABINET FOUNDATION.
 5. DRILL HOLE INTO CABINET AND INSTALL THREADED NIPPLE. INSTALL RUBBER GASKET, FLAT METAL WASHER AND LOCKER RING ON BOTH SIDES.
 6. JUNCTION BOX SHALL BE ATTACHED SECURELY TO THE CABINET WITH FOUR METAL SCREWS. MOUNTING HOLES SHALL BE INSIDE THE BOX AROUND THE FOUR CORNERS.
 7. THE CONTRACTOR SHALL APPLY SEALANT BETWEEN THE EDGE OF THE JUNCTION BOX AND THE CABINET. SEALANT SHALL BE RATED FOR OUTDOOR USE, WATER-PROOF BELOW WATER LINES, UV RESISTANT AND CLEAR OR GRAY IN COLOR.



- NOTES FOR OPTION 1:
1. REUSE EXISTING CONDUIT
 2. PULL OUT ALL EXISTING CABLES
 3. SALVAGE EXISTING COMMUNICATIONS (IF ANY)
 4. REINSTALL EXISTING CABLES TO BE REUSED (IF ANY) AND INSTALL NEW FIBER OPTIC CABLE




UNDERGROUND ROUTING

VIDEO DETECTION CAMERA MOUNTING NOTES:


1. WHEN AIMING CAMERA, HORIZON SHALL NOT BE VISIBLE IN THE FIELD OF VIEW.
2. CAMERA ENCLOSURE ASSEMBLY SHALL BE ROTATABLE AFTER INSTALLATION TO PROVIDE PROPER ALIGNMENT.
3. VIDEO CABLE SHALL BE BELDEN OR ENGINEER-APPROVED EQUAL.
4. SUNSHIELD SHALL BE EXTENDED TO THE MAXIMUM EXTENT WITHOUT BEING IN THE CAMERA FIELD OF VIEW.



TYPE 2 MOUNT




TYPE 3 MOUNT



TYPE 1 MOUNT

VIDEO DETECTION CAMERA MOUNTING DETAILS
N.T.S.



- NOTES:
1. CONCRETE CUTS SHALL NOT BE MORE THAN 1" GREATER THAN THE DIAMETER OF THE CONDUIT BEING INSTALLED.
 2. FILL ALL CONCRETE CUTS WITH GROUT.
 3. ALL WORK ASSOCIATED WITH TYING CONDUIT INTO AN EXISTING FOUNDATION SHALL BE DONE WITHOUT INTERFERING WITH THE OPERATION OF THE SIGNAL.

DETAILS FOR INSTALLING NEW CONDUIT INTO EXISTING PEDESTAL/ POLE FOUNDATION

REVISIONS		
DATE	DESCRIPTIONS	APPROVED








DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.

MISCELLANEOUS DETAILS

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: N.T.S.
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: _____ SHEET 68 OF 72


Kimley»Horn

DRAWING NAME: K:\VEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bld Set 5\Plans\BldSet 5-69-Details-02.dwg Layout1 Jan 30, 2015 3:29PM BY: blaine.lynch



- NOTES:**
- NOTCHES SHALL BE PROVIDED FOR REMOVING THE COVER.
 - BRASS "L" BOLTS AND NUTS ARE TO BE PROVIDED IN DIAGONAL CORNERS - TWO REQUIRED (3/8").
 - COVER TO HAVE ROUGHENED TOP SURFACE OF 1/8" IN RELIEF. THE WORDS "TRAFFIC SIGNAL" TO BE INSCRIBED ON THE TOP COVER WITH LETTERS 1-1/2" HIGH WITH 1/8" RELIEF.
 - CONCRETE TO BE 5000 PSI.
 - CONDUITS MAY ENTER THE BOX AT AN ANGLE OF APPROX. 45 DEGREES FROM HORIZONTAL. RADIUS SHALL BE 24" (MIN.).
 - GROUNDING ELECTRODE AND GROUND WIRE REQUIRED ONLY IF PULL BOX CONTAINS METALLIC CONDUITS WITH CIRCUITS HAVING VOLTAGES GREATER THAN 24 VOLTS AND ONLY IF CONDUITS NOT OTHERWISE GROUNDED WITHIN 1000 LINEAR FEET.
 - A KNOCK-OUT MAY BE USED AT THE BOTTOM OF THE ENDS OF BOX IF NECESSARY TO ACCOMMODATE THE DEPTH OF EXISTING CONDUITS. IF USED, KNOCK-OUTS SHALL BE SEALED WITH GROUT AFTER BOX IS PLACED OVER CONDUITS.
 - NUMBER AND SIZES OF CONDUITS SHALL BE AS REQUIRED BY THE PLANS. NO MORE THAN 8 CONDUITS SHALL ENTER A PULL BOX. NO MORE THAN 3 OF THOSE CONDUITS SHALL BE 2" OR LARGER.
 - EXCEPT FOR DIMENSIONS AND ANGLE OF ENTERING CONDUITS, DESIGN AND INSTALLATION DETAILS SHALL BE SAME FOR STANDARD PULL BOX AND OVERSIZED PULL BOX.

REVISIONS		
DATE	DESCRIPTIONS	APPROVED




DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.

MISCELLANEOUS DETAILS


SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: N.T.S.
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: SHEET 69 OF 72

Kimley»Horn



DRAWING NAME: K:\VEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bld Set 5\Plans\BldSet 5-70-Details-03.dwg Layout1 Jan 30, 2015 3:29PM BY: bliame.lynnch



WEATHER HEAD LOCATION DETAIL (PLAN VIEW)




TYPICAL POLE FIELD DRILLING DETAIL



POLE MOUNTED CABINET DETAILS

- NOTES:
- SEE PROJECT SPECIAL PROVISIONS FOR MATERIAL AND INSTALLATION REQUIREMENTS FOR RDS UNIT, PRIMARY RADAR DETECTION SYSTEM CABINET, SECONDARY RADAR DETECTION SYSTEM CABINET AND RADAR DETECTION SYSTEM CABLE.
 - SEE TDOT STANDARD DRAWING TSG-10 FOR CONCRETE PEDESTAL POLE FOUNDATION DETAILS. ALTERNATIVELY, A STEEL ANCHOR FOUNDATION CAN BE USED. SEE TDOT STANDARD DRAWING T-L-1 FOR STEEL ANCHOR FOUNDATION DETAILS.

REVISIONS		
DATE	DESCRIPTIONS	APPROVED




DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.

MISCELLANEOUS DETAILS


Kimley»Horn

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: N.T.S.
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: SHEET 70 OF 72


DRAWING NAME: K:\MEM_TPTD\115087002 - Shelby County CMP 2\Design\System\Bld Set 5\Plans\BldSet 5-71-Details-04.dwg Layout1 Jan 30, 2015 3:29PM BY: blaine.lynnch




TYPICAL DETAIL "A" APPROACH
TWO OR MORE THROUGH-LANE



TYPICAL DETAIL "B" APPROACH
ONE THROUGH-LANE



TYPICAL SAW SLOT AND LOOP WIRE DETAIL




SAW SLOT CONSTRUCTION DETAIL

LOOP LENGTH	LOOP TURNS	
	NO. TURNS IN ASPHALT	NO. TURNS IN CONCRETE
6-24	3	4
24-50	2	3

INDUCTION DETECTION LOOP NOTES

- (A) THE DETECTOR LOOPS SHALL BE OF THE SIZE AND LOCATION DETAILED IN THE PLANS UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
- (B) THE CONTRACTOR SHALL INSTALL LOOPS BY WET CUTTING A NARROW SLOT ($\frac{3}{8}$ INCH WIDE) IN THE ROADWAY SURFACE WITH A DIAMOND SAW. INSTALLING THE WIRE AND BACKFILLING WITH A SUITABLE SEALER. SAW SLOTS SHALL BE A MINIMUM OF 2" IN DEPTH.
- (C) THE CONTRACTOR SHALL EXERCISE CARE IN PLACING THE DETECTION LOOPS AND LEAD-INS IN THE PAVEMENT SLOTS. PRESSURE CLEAN WITH WATER, THEN FILTERED COMPRESSED AIR SHALL BE USED TO REMOVE ALL DUST AND MOISTURE FROM THE SLOT. THE LOOP WIRE WILL THEN BE PUSHED INTO THE SLOTS WITHOUT THE USE OF SHARP OBJECTS WHICH MIGHT DAMAGE THE WIRE INSULATION. USE OF METAL TOOLS IS NOT PERMITTED.
- (D) THE DETECTION LOOPS IN ANY GIVEN TRAFFIC LANE SHALL BE WIRED TOGETHER IN SERIES TO ENTER ONE DETECTOR SENSOR UNIT UNLESS OTHERWISE NOTED ON THE PLANS. IF THE MANUFACTURER OF THE RELATED DETECTOR SENSOR UNIT RECOMMENDS ANOTHER WIRING SCHEME, APPROVAL SHALL BE OBTAINED FROM THE ENGINEER BEFORE CHANGING THE WIRING.
- (E) BEFORE THE SLOTS ARE SEALED, THE RESISTANCE OF THE DETECTION LOOPS AND LEAD-INS (INCLUDING SPLICES) SHALL BE CHECKED AGAINST GROUND WITH A MEGGAR. A RESISTANCE OF LESS THAN TEN MEGAOHMS WILL INDICATE A FAULT REQUIRING CORRECTION BEFORE THE SLOT IS SEALED.
- (F) ALSO BEFORE THE SLOTS ARE SEALED, THE INDUCTANCE OF THE DETECTION LOOP AND LEAD-INS SHALL BE CHECKED AT THE LOCATION OF THE DETECTOR SENSOR UNIT. THE INDUCTANCE SHALL BE NO LESS THAN 50 MICROHENRIES AND NO MORE THAN 300 MICROHENRIES. IF IT MEASURES OUT OF THIS RANGE ADDITIONAL TURNS SHALL BE ADDED OR SPLICING OF THE LOOPS (SERIES AND/OR PARALLEL) SHALL BE CHANGED TO PROVIDE AN INDUCTANCE READING BETWEEN 50 AND 300 MICROHENRIES.
- (G) AFTER THE LOOP WIRES ARE INSTALLED AND ALL CHECKS SATISFACTORILY COMPLETED, THE SLOT SHALL BE BACKFILLED AND SEALED WITH AN APPROVED LOOP SEALANT TO WITHIN $\frac{1}{8}$ " OF THE PAVEMENT SURFACE. SURPLUS SEALANT SHALL BE REMOVED FROM THE ADJACENT ROAD SURFACE WITHOUT THE USE OF SOLVENTS. ASPHALTIC BASED SEALERS ARE NOT ACCEPTABLE.
- (H) LOOPS AND HOME RUNS TO PULL BOXES SHALL BE ONE CONTINUOUS LENGTH OF NO. 14 AWG STRANDED CROSS-LINK POLYETHYLENE SINGLE CONDUCTOR WIRE. WHICH MEET THE REQUIREMENTS OF I.M.S.A. SPECIFICATION NO. 51-3. THE HOME RUN TO THE PULL BOX SHALL BE TWISTED 3 TIMES PER FOOT.
- (I) SPLICES SHALL BE PERMITTED ONLY IN PULL BOXES, POLE BASES, CONDULETS, OR CABINETS AND SHALL BE WATERPROOF.
- (J) ALL CABLE FROM PULL BOX TO CONTROLLER SHALL CONSIST OF A TWISTED PAIR OF SHIELDED CABLES, NO. 14 AWG STRANDED, WHICH MEET THE REQUIREMENTS OF I.M.S.A. SPECIFICATION NO. 50-2.
- (K) ALL CABLES ARE TO BE COLOR-CODED. ALL LOOP LEAD-INS ARE TO BE LABELED IN PULL BOXES, SHIELDED CABLE TO BE LABELED IN CONTROLLER CABINETS.
- (L) NO LOOPS ARE TO BE INSTALLED THROUGH, OVER, OR UNDER TRANSVERSE CONCRETE JOINTS IN CONCRETE PAVEMENT. AND NO MANHOLES, INLETS, ETC. MAY BE LOCATED WITHIN A LOOP. IF ANY OF THE ABOVE ARE ENCOUNTERED THE LOCATION OF THE LOOP MAY BE VARIED SLIGHTLY AS DIRECTED BY THE ENGINEER, IF THE ABOVE ITEMS ARE UNAVOIDABLE, SMALLER LOOPS IN THE SERIES MAY BE USED. SMALLER LOOPS USED TO REPLACE ONE LARGE LOOP MAY BE CONNECTED TO ONE CHANNEL.
- (M) ALL LOOPS TO BE CENTERED IN TRAVEL LANE.

REVISIONS		
DATE	DESCRIPTIONS	APPROVED



DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.

ADVANCED LOOP DETECTION DETAILS


SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: N.T.S.
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: _____ SHEET 71 OF 72

Kimley»Horn

DRAWING NAME: K:\VEM_TPTD\115087002 - Shelby County CMP 2\Design\Level 4 - Signal System\Bld Set 5\Plans\BldSet 5-72-Details-05.dwg Jan 30, 2015 3:29PM BY: blaine.lynnch

NOTES:

- 1. ALL COUNT ZONES TO BE DRAWN AS 6'X6' ZONES
- 2. ALL COUNT ZONES TO BE SET TO DIRECTIONAL AND TO COUNT ALL THE TIME UNLESS DIRECTED OTHERWISE BY THE ENGINEER
- 3. ALL COUNT ZONE LOCATIONS TO BE APPROVED BY THE ENGINEER PRIOR TO FINAL ACCEPTANCE OF THE INTERSECTION
- 4. COUNT ZONES TO BE NUMBERED SEQUENTIALLY AFTER THE DETECTION ZONES ACCORDING TO THE PHASE ASSIGNMENT AT THE INTERSECTION.



TYPICAL COUNT ZONE DETAIL

REVISIONS		
DATE	DESCRIPTIONS	APPROVED



Kimley»Horn

DIVISION OF PUBLIC WORKS
CONGESTION MANAGEMENT PROGRAM
SIGNAL SYSTEM PROJECT SET #5
SHELBY COUNTY, TN.

DETAILS

SURVEY: N/A DATE: N/A BOOK: N/A
DRAFTED: KHA DATE: 12/13 SCALE: N.T.S.
DESIGNED: KHA DATE: 12/13 CHECKED: JFC DATE: 12/13
JURISDICTION: SHEET 72 OF 72